



Functional Requirement Specification Document Registration

KAVERI 2.0 Online Services For Department of Stamps & Registration Government of Karnataka

Prepared by

Centre For Smart Governance (CSG)

2nd Floor, TTMC Yeshwanthapura, BMTC Bus station

Bangalore - 560022



FUNCTIONAL REQUIREMENT SPECIFICATION



KAVERI 2.0

MARCH 2022

Document Control

Version	Date of Revision	Author/Modified By	Description for Change	Affected Sections	Approved By
1.0	17-Sep-2021	FRS Team	Draft	- User Registration - Property Search - Appointment Scheduler	Saurabh Bhattacharya
1.1	01-Oct-2021	FRS Team	Process flow	- Document Information - Property Search - Party Information	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.2	5-Oct-2021	FRS Team	Draft	Market Valuation	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.3	12-Oct-2021	FRS Team	Process flow, Draft	- Document Information - Property Search - Property Schedule - Party Information - Fee Calculation - SRO Confirmation	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.4	18-Oct-2021	FRS Team	Process flow, Draft	Payment	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.5	2-Nov-2021	FRS Team	Process flow, Draft	- Verification Summary - Department Login & dashboard	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.6	10-Nov-2021	FRS Team	Process flow, Draft	- Application Allocation - Application Re-Allocation - Document Registration-DEO-Property Details - Document Registration-DEO-Property Schedule	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.7	16-Nov-2021	FRS Team	Process flow, Draft	- Document Registration-DEO-Party Details - Document Registration-DEO-Market valuation and fee calculation	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
1.8	20-Nov-2021	FRS Team	Process flow, Draft	- Document Registration-DEO-Payment Details - Document Registration-DEO-Document summary & Print - Document Registration-DEO-Endorsement generation & Print - Document Registration: Encumbrance Certificate & Print	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda

				- Document Registration: Scan and upload - Document Registration: Acknowledgement slip and Registration complete	
1.9	09-Dec-2021	FRS Team	Process flow, Draft	- EC Property Search - EC Payment - EC Document Summary - EC Generation	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.0	10-Dec-2021	FRS Team	Process flow, Draft	- Movable Property - Property Description - Stamp Duty and Fee Calculation - Party Information - Document Summary – Applicant (Online)	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.1	15-Dec-2021	FRS Team	Process flow, Draft	- CC Property Search - CC Payment - CC Document Summary - CC Generation	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.2	18-Dec-2021	FRS Team	Process flow, Draft	- Court Order Entry Module - Search and Add Court Order - Edit Court Order - Cancel Court Order	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.3	2-Feb-2022	FRS Team	Process flow, Draft	- Liability Module - Search Liability - Add Liability - Liability Report	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.4	3-Feb-2022	FRS Team	Process flow, Draft	- Cross Reference Module - Add Cross Reference	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda
2.5	22-Mar-2022	FRS Team	Process flow, Draft	- Overall Process Flow - Type of Document - Property Search - Party Information - Forgot Password - Account Creation - Document Summary – Applicant (Online) - SRO Confirmation - Application Review and Allocation to DEO by SR - Properties outside e-Aasthi and e-Swathu - Document Registration - Configuration Module - Section liability Module - Filling Document Module	Bhojya Naik, Saurabh Bhattacharya, Naveen Gowda

Version	Date of Revision	Modules (Affected Sections)
1.0	16-Nov-2021	1. Fee calculation: Updated payable amount 2. Document Summary: a. Process Flow Updated b. Uploading Deed document in process flow and keep optional process, added 3. Department Login & Dashboard: Added validation table 4. SRO Confirmation: a. Process flow updated b. Validation table added 5. SRO not approved Doc -Applicant: Added 6. Registration: Party details (Added the module) 7. Registration: Market valuation and fee calculation (Added the module)
1.1	18-Nov-2021	1. Registration: Payment Details a. Process flow and Draft added 2. Document Registration: Endorsement generation & Print a. Process flow and Draft added 3. Document Registration- DEO-Scan & upload a. Process flow and Draft added
1.2	20-Nov-2021	1. Document Registration: Endorsement generation & Print a. Process flow and Draft updated 2. Document Registration: Document summary & Print a. Process flow and Draft added 3. Document Registration: Acknowledgement slip and Registration complete a. Process flow and Draft added 4. Document Registration: Encumbrance Certificate & Print a. Process flow and Draft added 5. SRO Confirmation: Updated a. SRO Dashboard: Application Pending for Approval b. SRO Document Approval: Review - SRO Document Not Approved: Applicant
1.3	10-Dec-2021	1. EC Property Search 2. EC Payment 3. EC Document Summary 4. EC Generation 5. Movable Property a. Property Description b. Stamp Duty and Fee Calculation c. Party Information d. Document Summary – Applicant (Online)
1.4	15-Dec-2021	1. CC Property Search 2. CC Payment 3. CC Document Summary 4. CC Generation
1.5	18-Dec-2021	1. Court Order Entry Module 2. Search and Add Court Order 3. Edit Court Order 4. Cancel Court Order
1.6	20-Dec-2021	1. Court Order Entry Module 2. Market Valuation Database Tables and Columns

Version	Date of Revision	Modules (Affected Sections)
1.7	02-Feb-2022	1. Liability Module 2. Search Liability 3. Add Liability 4. Liability Report 5. Market Valuation
1.8	03-Feb-2022	1. Cross Reference Module 2. Add Cross Reference 3. Fee Calculation
1.9	22-March-2022	1. Overall Process Flow 2. Type of Document 3. Property Search 4. Party Information 5. Forgot Password 6. Account Creation 7. Document Summary – Applicant (Online) 8. SRO Confirmation 9. Application Review and Allocation to DEO by SR 10. Properties outside e-Aasthi and e-Swathu 11. Document Registration 12. Configuration Module 13. Section 68(2) Correction Module 14. Filling Document Module
2.0	12-April-2022	1. Filling Document Module 2.
2.1		3.

Table of Contents

1	USER REGISTRATION.....	15
1.1	Account Creation	16
1.2	User Login	19
1.3	Forgot Password	20
2	TYPE OF DOCUMENT	23
2.1	Nature of Document.....	25
3	SELECTION OF NATURE OF DOCUMENT, ARTICLE SUB-ARTICLE AND BOOK NUMBER	26
3.1	Selection of Nature of Document.....	26
3.2	Selection of Article.....	27
3.3	Selection of Sub-article.....	28
3.4	Selection of Book Number.....	31
4	PROPERTY SEARCH	33
4.1	Search property in Bhoomi, e-Swathu, e-Aasthi, and Aligned databases.....	37
4.2	Properties outside e-Aasthi and e-Swathu.....	43
4.3	GIS.....	53
4.3.1	GIS Search	53
4.3.2	GIS Mapping	56
5	PROPERTY SCHEDULE	58
6	ADDITION OF PROPERTIES.....	60
6.1	Add Property.....	60
7	MARKET VALUATION	61
8	FEE CALCULATION.....	81
8.1	EXEMPTION of Stamp Duty & Registration Fee.....	86
8.2	Use Case No.1 (Agriculture + Agriculture).....	89
8.2.1	Example 1: Agriculture (Bhoomi) & Agriculture (Bhoomi)	89
8.3	Use Case No.2 (Non-Agriculture + Non-Agriculture).....	92
8.3.1	Example 1: Non-Agriculture (e-Swathu) & Non-Agriculture (e-Swathu)	92
8.3.2	Example 2: Non-Agriculture (e-Aasthi) & Non-Agriculture (e-Aasthi)	94
8.3.3	Example 3: Non-Agriculture (e-Swathu) & Non-Agriculture (e-Aasthi)	96
8.3.4	Example 4: Non-Agriculture (e-Aasthi) & Non-Agriculture (e-Swathu)	98
8.4	Use Case No.3 (Agriculture + Non-Agriculture).....	101
8.4.1	Example 1: Agriculture (Bhoomi) & Non-Agriculture (either e-Swathu or e-Aasthi)	101


8.4.2	Example 2: Non-Agriculture (either e-Swathu or e-Aasthi) & Agriculture (Bhoomi)	103
8.5	DENOTATION of Stamp Duty	115
9	PARTY INFORMATION.....	134
10	DOCUMENT SUMMARY – Applicant (Online).....	144
11	DEPARTMENT LOGIN & DASHBOARD.....	146
12	SRO CONFIRMATION	150
13	PAYMENT	156
14	APPOINTMENT SCHEDULAR	159
14.1	Schedule Appointment to Visit SRO	159
14.2	Reschedule Appointment	161
14.3	Cancel Appointment	163
15	APPLICATION REVIEW AND ALLOCATION TO DEO BY SR	165
15.1	Application Re-Allocation to DEO	169
16	DOCUMENT REGISTRATION.....	170
16.1	Registration: Party Details	171
16.2	Registration: Document Summary & Print	175
16.3	Registration: Endorsement & Print	182
16.4	Registration: Scan & Upload.....	186
16.5	Registration: Digital Signature by SR	189
16.6	Registration: Encumbrance Certificate & Print	190
16.7	Registration: Acknowledgement slip and Registration complete	192
17	ENCUMBRANCE CERTIFICATE (EC) SEARCH.....	194
17.1	EC Payment.....	197
17.2	EC Online Application Summary.....	199
17.3	EC Generation.....	200
18	MISCELLANEOUS DOCUMENT	202
18.1	Property Description.....	202
18.2	Stamp Duty and Fee Calculation.....	203
18.3	Party Information	205
18.4	Document Summary – Applicant (Online).....	214
19	CERTIFIED COPY (CC) SEARCH.....	217
19.1	CC Payment.....	218
19.2	CC Online Application Summary.....	220
19.3	CC Generation.....	221
20	COURT ORDER ENTRY MODULE	224
20.1	Search and Add Court Order	224

20.2	Edit Court Order	226
20.3	Cancel Court Order	228
21	LIABILITY MODULE.....	232
21.1	Search Liability.....	232
21.2	Add Liability	234
21.3	Liability Report.....	235
22	CROSS REFERENCE MODULE	237
22.1	Add Cross Reference.....	237
23	CONFIGURATION MODULE.....	242
23.1	Transfer Management.....	242
23.2	Leave Management	247
24	SECTION 68 (2) CORRECTION MODULE	252
24.1	Correction Request Sent by SR	252
24.2	Correction Order Submit by DR	256
24.3	Correction Note U/S 68(2) Submit by SR.....	257
25	FILING DOCUMENT MODULE	262
	SUPPLEMENT TO REGISTER BOOK NO. 1 AND FILE OF COPIES AND TRANSLATION	262
25.1	(i) Supplements to register book no. 1 shall be kept as follows.....	262
25.1.1	Book 1 Filing Part I - For the purposes of Sections 64, 65, 66 and 67 (Memos from the other Offices).....	262
25.1.2	Book 1 Filing Part II - For copies of maps or plans mentioned in Section 21	271
25.1.3	Book 1 Filing Part III	273
25.1.3.1	(a) For copies of certificates of sale of immovable property granted by Civil Courts and Revenue officers	273
25.1.3.2	(b) For statement regarding land acquired under the Land Acquisition Act, 1894, received from the Deputy Commissioner	273
25.1.4	Book 1 Filing Part IV - Copies of the instruments and collateral securities executed Under the Karnataka Land Improvement Loans Act, 1963 (Karnataka Act 16 of 1963) and the Karnataka Agriculturists Loans Act, 1963 (Karnataka Act 17 of 1963), received from Revenue officers	276
25.1.4.1	Filing of Form 3 for Agriculture Loan through FRUITS.....	286
25.1.4.2	Filing of Form 3 if there is a Court Order on the property	292
25.1.4.3	Mortgage Deed through FRUITS.....	293
25.1.5	Book 1 Filing Part V - Copies of instruments received from the Land Development Banks under Section 85-A of the Karnataka Co-operative Societies Act, 1959 (Mortgage Deed).....	294
25.1.6	Book 1 Filing Part VI – Copies of the court order directing the concern Sub Registrar to make a note of charge or encumbrance of the party or surety and its extinguishment on the immovable property, concerning the amount due or the surety amount, in the indices prescribed under the act	295

25.2	(ii) A separate file shall also be opened for filing copies translations presented under sections 19 and 62 of the act or under rule 12(1). The copies and translation placed in this file shall be connected by a cross reference with the entry in the register	298
25.3	(iii) A separate file shall also be maintained for communications received from officers of other departments intimating the cancellation, modification or rectification of transactions evidenced by papers previously filed or registered	298
26	EXCEPTIONAL CASES	299
26.1	Attendance at Private Residences (Private Attendance)	299
26.2	Under-valuation	304
26.3	Impound	309
26.4	Condonation of Delay (Delay Condone)	315
26.5	Power of Attorney Authentication/ Attestation	319
26.6	Late Appearance (or Parties Appearing at Different Times)	325
27	Abstract for 7 Special Articles	331
27.1	Partition	331
27.1.1	Brief Description	331
27.1.2	User Input	331
27.1.3	Process Abstract	332
27.2	Joint Development Agreement	335
27.2.1	Brief Description	335
27.2.2	User Input	335
27.2.3	Process Abstract	336
27.3	Power of Autonomy (PoA) with JDA (Joint Development Agreement)	338
27.3.1	Brief Description	338
27.3.2	User Input	338
27.3.3	Process Abstract	339
27.4	EXCHANGE	341
27.4.1	Brief Description	341
27.4.2	User Input	341
27.4.3	Process Abstract	342
27.5	SETTLEMENT	344
27.5.1	Brief Description	344
27.5.2	User Input	344
27.5.3	Process Abstract	345
27.6	APARTMENT	347
27.6.1	Brief Description	347
27.6.2	User Input	347

27.6.3	Process Abstract	348
27.7	LEASE	350
27.7.1	Brief Description	350
27.7.2	User Input	350
27.7.3	Process Abstract	351
28	ENDORSEMENT.....	358
28.1	Contents in the Endorsement.....	358
28.2	Endorsement for PENDING DOCUMENTS	362
28.2.1	Pending for determination of undervaluation, referred to District Registrar under section 45A of Karnataka Stamp Act 1957	362
28.2.2	Pending for short levy of Stamp Duty, impounded under section 33 of Karnataka Stamp Act, 1957	368
28.2.3	Pending for Condonation of Delay under section 25 of Registration Act, 1908, document exceeding 4 months from the date of last execution read with Rule 52 of Karnataka Registration Rules, 1965	374
28.2.4	Pending for Appearance of the Parties under section 34 of Registration Act, 1908....	380
28.2.4.1	SCENARIO 1.....	380
28.2.4.2	SCENARIO 2.....	384
28.2.5	Pending for Private Attendance under section 31 of Registration Act, 1908	392
28.2.5.1	SCENARIO 1.....	392
28.2.5.2	SCENARIO 2.....	398
28.2.5.3	SCENARIO 3.....	405
28.3	Endorsement for DOCUMENT REFUSED for REGISTRATION	409
28.4	Stamp Duty on DUPLICATE DOCUMENT presented along with the original document	413
29	CANCELLATION DEED	418
29.1	Brief Description	418
29.2	Functional Step by step Approach.....	418
30	REGISTRATION AND CANCELLATION OF WILL.....	429
30.1	Registration of Will	429
30.1.1	Brief Description	429
30.1.2	SCENARIO 1.....	429
	The Testator gets his Will Registered	429
27.1.2.1	Brief Description	429
27.1.2.2	Process Flow	429
27.1.2.3	Functional Step by Step Process.....	430
30.1.3	SCENARIO 2.....	432
	The Will Registration after the death of the Testator	432


27.1.3.1 Brief Description	432
27.1.3.2 Process Flow Diagram.....	432
27.1.3.3 Functional Step by Step Process.....	433
30.2 Will including Cancellation	435
27.1.2.1 Brief Description	435
27.1.2.2 Process Flow	435
27.1.2.3 Functional Step by Step Process.....	435



30.3		439
30.4 Cancellation of Will.....		440
30.4.1 Brief Description		440
30.4.2 Process Flow		440

30.4.3	Functional Step by Step Process	440
31	MARRIAGE REGISTRATION MODULE	443
31.1	Brief Description	443
31.2	Stakeholder – Role & Responsibilities	444
31.3	Types of Marriage.....	448
31.3.1	Hindu Marriage.....	449
31.3.2	Special Marriage (Intended Marriage Notice)	472
31.3.3	Special Marriage of Other Forms.....	503
31.4	Validations and Controls.....	532
32	FIRM REGISTRATION MODULE	533
32.1	Brief Description	533
32.2	Stakeholder – Role and Responsibilities.....	534
32.3	Types of Firm Registration.....	537
32.3.1	New Firm Registration	540
32.3.2	Amendment to the Constitution of firm	546
32.3.3	Re-constitution of Firm	556
32.3.4	Dissolution of Firm	560
32.4	Validations and Controls.....	585
33	ADDITIONS to the FRS – UPDATION REQUIRED	586

Kaveri Master Process flow



Proposed 'To-Be' Processes

The Kaveri online services shall be streamlined to improve the processes of the Document Registration, Marriage Registration, Encumbrance Certificate, Certified Copy, Registration of Firms and Property Valuation services under the Stamps & Registration Department. Following are the proposed modules for the Document Registration:

1. User Registration
2. Type of Document
3. Property Search
4. Property Schedule
5. Market Valuation
6. Fee Calculation
7. Party Information
8. Document Summary – Applicant (Online)
9. SRO Confirmation
10. Payment
11. Appointment Scheduler
12. Department Login & dashboard
13. Application Allocation to DEO
14. Document Registration

Bi-Lingual Requirements

The Kaveri 2.0 software developed (input, storage, output) shall have bilingual provision (Kannada & English), The system shall be compliant with Unicode standard. The Forms to be developed shall be available in both English and Kannada Language. User shall be given the option of choosing the desired language for the purpose of filling up the application.

The numerical values maybe kept out of the purview of bi-lingual requirements, and the system shall ensure that user input is possible in both languages. Also, the error messages thrown to the user by the system shall be in the language selected by the user for filling up the form.

1 USER REGISTRATION


The User registration shall allow a new applicant to avail the online services offered by the Department of Stamps and Registration. The applicant shall enter all the required information for registering on the Kaveri portal.

The applicant visits the Kaveri portal and select User Registration button on the top right corner of the home page. In response to the applicant's request, the system display a data entry form that contains required fields for user registration. The applicant fills the required details along with the mobile number and email id which shall be verified through OTP. The system registers the user with unique username which would be the Email ID entered by the applicant. Applicant receives notification through E-Mail/ SMS along with the login credentials. Only registered user would be able to avail all types of registration services under Kaveri at Stamps & Registration Department.

1.1 Account Creation

i. Brief Description

The user is required to create an account on the Kaveri portal which shall act as an interface for the applicant to track the status of the application and raise queries to the department. The account creation shall be required to apply for all types of registration under Kaveri online services at Stamps & Registration department.



ii. Functional Step by Step Process

- i. **Visit Kaveri Portal:** The user shall open the Kaveri portal managed by the Department of Stamps and Registration (DSR). The Department is responsible for the registration of documents relating to movable, immovable assets and other type of registrations
- ii. **User Registration:** The user shall register in the Kaveri Portal to avail the services provided by the Department i.e., Property Registration, Marriage Registration, Apply for Encumbrance Certificate, etc. To start the process the user shall select the User Registration option available on the homepage of the Kaveri portal. After selecting the User Registration option, three options shall be displayed Login, Account creation and Forgot Password
- iii. **Registration form:** After selecting the Account Creation option, the System shall display the registration form in which the User will submit all the required details
- iv. **User Details:** Under the Registration form, the user shall enter the following details Name, Gender, Email ID, and Mobile Number and submit the registration form
- v. **Validate User Details:** The validation of the E-mail id and Mobile Number shall be based on the below criteria.

Step 1. Email id

- a. In the Email id, the prefix should be left of the @ symbol and the domain name should be right of the @ symbol
- b. Top level domains (TLDs) should be to the right side of the dot symbol (.)
- c. The Email id should be unique to each account and the system shall check for the duplicity in the database

Step 2. Mobile Number

- a. The first digit should contain number between 6 to 9
- b. The rest 9 digit can contain any number between 0 to 9
- c. The mobile number shall contain country code and 10-digit number
- d. The mobile number shall have total 10-digit number

Validation Process for Email ID and Mobile Number

- a. In case details entered by the User in the Registration form satisfies the above-mentioned condition, then in the next step the User's Mobile Number and E-mail id will be verified
 - b. In case details entered by the User in the Registration form does not satisfy the condition, then the User shall be asked to enter the details again in the registration form
-
- vi. **Already Registered:** The system shall check the email id and mobile number in the database of existing users. In case, it is found that user already exist in the system then system shall ask the user to enter new email id or mobile no. to complete registration process

vii. **Security Question:** The user shall be required to select the security question from the given dropdown list and enter the answer to the selected question in the given space. The information will be saved and shall be utilised at the time of password recovery.

viii. **Captcha Verification:** The Captcha shall be autogenerated by the system and will be displayed to the user

Case 1 – Verify Captcha

- The user shall enter the alphanumeric text in the given space, similar to the Captcha generated by the system
- If Captcha is successfully verified, then the New Login credentials shall be sent to the registered mobile and email id of the user

Case 2 – Captcha not verified

- If Captcha does not get verified, then the User shall be asked to enter the captcha again or generate new captcha

ix. **Login Credentials Sent to User:** After completing all the verification in the system, the user will click on the “Register” button and the registration process is completed. The login credentials will be shared on the registered Mobile number and Email ID of the user

x. **Login Credentials Received:** The User will receive the login credentials through by E-Mail as well as through SMS

User Interface (UI)

Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka

Register Log In

Create Account

First Name*

Value

Middle Name

Value

Last Name

Value

Gender*

Select

Email ID*

Value

Mobile Number*

Value

Security Question*

Select

Answer*

Select

Enter the text you see in the image below

CAPTCHA

Value


Register

Already a User? [Log In](#)

1.2 User Login

i. Brief Description

The User shall access the portal and will enter the username and password to login in the system. If User enters invalid username and password, then the system will prompt the User to enter valid username and password.



ii. Functional Step by Step Process

- i. **Visit Kaveri Portal:** The user shall open the Kaveri portal; the system will display the login page in which the User will enter the login credentials already shared over SMS and E-mail

User Validation Check: The system will check the authenticity of the user


Case 1: Valid Login Credential

- In case the username and password entered by the user is valid the user will successfully be logged in to the system

Case 2: Invalid Login Credential

- In case the username and password entered by the user is invalid the system will redirect the user to enter the username and password again

User Interface (UI)




The image shows a web form titled "Applicant Login". On the left side, there is a large text prompt: "Please **Log In** to continue". On the right side, there are four input fields and a button. The first field is labeled "Username" and contains the placeholder text "Value". The second field is labeled "Password" and also contains the placeholder text "Value". The third field is labeled "Enter the text you see in the image below" and contains a CAPTCHA image showing the text "W6 8HP" with a refresh icon. The fourth field is another input field with the placeholder text "Value". Below these fields is a blue "Log In" button. At the bottom of the form, there are two links: "Forgot Password? [Click Here](#)" and "New User? [Register Account](#)".

1.3Forgot Password

i. Brief Description

In case the user lost the login credentials of the account then the recover then the user will be required to select the forgot password option on the Kaveri portal.



ii. Functional Step by Step Process

- i. **Visit Kaveri Portal:** The user shall open the Kaveri portal; the system will display the login page in which the User will select the Recover password option
- ii. **Password Recovery:** After selecting the Forgot Password option, the System shall prompt the User to enter the registered E-mail id and mobile number
- iii. **Captcha Verification:** The Captcha shall be auto-generated by the system and will be displayed to the user

Case 1 – Verify Captcha

- The user shall enter the alphanumeric text in the given space, similar to the Captcha generated by the system
- If Captcha is successfully verified, then the New Login credentials shall be sent to the registered mobile and email id of the user

Case 2 – Captcha not verified

- If Captcha does not get verified, then the User shall be asked to enter the captcha again or generate new captcha

- iv. **Update Password:** After successful verification of the OTP the user shall be asked to enter new password. After the confirmation from the user the updated password will be sent to the user through SMS and E-mail

User Interface (UI)


Forgot Password

Don't worry!
Enter your details and we will
send you a new password

Email*

Mobile Number*

Enter the text you see in the image below




2 TYPE OF DOCUMENT

In type of services, the user shall be required to select the service for which the user would like to apply in the Kaveri portal. The type of services shall be as follows:

- a. **Document Registration:** The user shall select document registration option. Document registration occurs for Movable/Miscellaneous property in jurisdiction of SRO. There are different nature of documents such as: Sale deed, mortgage deed, lease deed, deposit of title deed, reconveyance deed, partition deed, release deed, gift deed, exchange deed, settlement deed, Agreement, GPA etc.
- b. **Encumbrance Certificate:** The user shall select the Encumbrance certificate option. Encumbrance certificate is a record showing registered transactions over a property. For Obtaining EC applicant shall submit application form no. 22
- c. **Certified Copy:** The user shall select the certified copy option. Agencies like banks refer to certified copies of registered sales deed before giving loan on a mortgaged property to verify the ownership. IT department may also refer to a certified copy to ascertain value of transaction and assess the income of the property buyer or seller. CC of registered documents relating to immovable properties is obtained to verify the legality of transaction of property effected through it
- d. **Marriage Registration:** The user shall select marriage registration option. The user shall submit document as per below scenario:
 - For Hindu marriage, the bride and groom shall submit declaration of marriage in the form of Form Number I (Rule 4 of Hindu marriage rules). Declaration will be from bride and groom having married outside the marriage officer in presence of witnesses
 - For Special marriage, Bride and groom shall submit notice for intended marriage after completion of 30 days from date of notice after that marriage will be solemnize by Marriage officer
 - Under rule 13 special marriage in other forms, the notice will be served by the married couple to get their marriage registered from date of their original marriage took place
- e. **Firm:** The applicant shall submit deed along with declaration to Registrar of firms (District Registrar). The user shall select the firm option. Any two or more major citizen can enter into partnership and register the partnership firm. The firm is registered in the office of District Registrar (Registrar of firms) of the concerned jurisdiction
- f. **Authentication/Attestation of POA:** The user shall select power of attorney (POA) option. POA is delegation of power to a person by the author to act on his behalf by attorney. There are two types of Power of Attorney:
 - Power of Attorney (General means multiple functions)
 - Special Power of Attorney (Single or specific purpose)

- g. **Will:** The user shall select will option. Will is the testamentary document executed by testator which will come in effect after demise of the testator. Type of deeds of will are as:
- Will
 - Codicil (further will)
 - Will Cancellation

User Interface (UI)2



2.1 Nature of Document

- a. **Deeds of Property Registration:** There is different nature of documents such as: Sale deed, mortgage deed, lease deed, deposit of title deed, re-conveyance deed, partition deed, release deed, gift deed, exchange deed, settlement deed, etc.
- b. **Marriage Registration:** The user shall submit document as per below scenario:
 - For Hindu marriage, the bride and groom shall submit declaration of marriage in the form of Form Number I (Rule 4 of Hindu marriage rules). Declaration will be from bride and groom having married outside the marriage officer in presence of witnesses
 - For Special marriage, Bride and groom shall submit notice for intended marriage after completion of 30 days from date of notice after that marriage will be solemnize by SRO
 - Under rule 13 special marriage in other forms, the notice will be served by the married couple to get their marriage registered from date of their original marriage
- c. **Firm:** The applicant shall submit deed along with Form I (Rule 3) declaration to registrar of firms (District Registrar)

Note: All the applications created by the user shall be archived and stored in the user account and no application information shall be deleted from the database.

3 SELECTION OF NATURE OF DOCUMENT, ARTICLE SUB-ARTICLE AND BOOK NUMBER

i. **Brief Description**

The user shall select the Nature of Document, Article and Sub-article as per his requirements. The system shall auto-fetch the corresponding Book Number. The user shall refer the Reference Manual for selection of Nature of Document, Article and Sub-article for ease of understanding.

3.1|Selection of Nature of Document

The user shall select the Nature of Document from among the below mentioned ones:

1. DTD Deposition of Title Deed
2. Adoption Deed
3. Affidavit
4. Lease cum sale agreement
5. Agreement with Possession
6. Agreement without Possession
7. JDA
8. Agreement for Movable Property
9. Deed of Company
10. Award
11. Cancellation Deed
12. Certificate of Sale
13. Trust Deed
14. Exchange Deed
15. Mortgage
16. Mortgage
17. Gift Deed
18. Rent/Lease Agreement
19. Lease/Licence Agreement
20. Mortgage Deed
21. Partition Deed
22. Partnership
23. Power of Attorney
24. Power of Attorney with Consideration
25. GPA for JDA
26. GPA with Sale Clause
27. GPA for TDR
28. GPA for Stock Marketing
29. GPA for Demat Account
30. GPA

31. Release of Mortgage
32. Rectification Deed
33. Release Not within family members
34. Release within family members
35. Release of Mortgage
36. Sale Deed
37. Counterpart or Duplicate
38. Settlement Not within family members
39. Settlement within family members
40. Revocation of Settlement
41. Surrender of Lease
42. Will
43. Will including Cancellation

The user after selecting the Nature of Document shall proceed for the selection of Article.

3.2 Selection of Article

The user shall select the Article from among the below mentioned ones:

1. Memorandum of deposit of title deeds
2. Adoption Deed
3. Affidavit
4. Agreement
5. Articles of Association of a company
6. Award
7. Cancellation Deed
8. Certificate of Sale
9. Declaration of Trust - With Property
10. Exchange of Property
11. Mortgage with Further charge
12. Filing of declaration by Bankers under KACOMP Act
13. Gift Deed
14. Lease/Licence of Immovable Property
15. Mortgage Deed
16. Partition of Non Agriculture Land
17. Partition of Agriculture Land
18. Partition of Movable Property
19. Partition of any Property
20. Partnership
21. Power of Attorney
22. Reconveyance
23. Rectification Deed
24. Release Deed
25. Conveyance (Sale)

26. Counterpart or Duplicate
27. Settlement
28. Surrender of Lease
29. Will
30. Will including Cancellation

The user shall select the Article based on the options available after selecting the nature of Document. The user after selecting the Article shall proceed for the selection of Sub-article.

3.3 Selection of Sub-article

The user shall select the Article from among the below mentioned ones:

1. 6(1)(i) - The pawn or pledge of immovable property, Loan or Debt amount does not exceed rupees 10 lakhs
2. 6(1)(ii) - The pawn or pledge of immovable property, Loan or Debt amount exceeds rupees 10 lakhs
3. 5(d) Lease cum sale agreement with BDA, KHB and other Development Authorities
4. 5(e)(i) Agreement of Sale of Immovable Property (Possession given/agree to be given)
5. 5(e)(ii) Agreement of Sale of Immovable Property (Possession not given)
6. 5(f) Joint Development Agreement
7. 5(g)(i) Agreement of sale of Movable property (Possession delivered/agreed to be given)
8. 11(a) If the property, which is the subject matter of award, is immovable property
9. 14(a) Any instrument previously executed on which stamp duty has been paid
10. 14(b) - any instrument executed by or on behalf of the central government or a local authority or other authority
11. 14(c) In any other case
12. 14(d) Cancellation of Sale Deed
13. 15(a) Purchase money does not exceed Rs. 10
14. 15(b) Purchase money exceed Rs. 10 but does not exceed Rs 25
15. 15(c) In any other case
16. 54(i) Trust is made exclusively for public religious and charitable purpose
17. 54(ii) Trust is made for the management and custody of properties
18. 54(iii) Trust involves the transfer/disposition of property
19. 27(b)(i) if at the time of execution of the instrument of further charge, possession of the property is given or agreed to be given under such instrument
20. 28(a) donee is not a family member
21. 28(b)(i) donee is a family member (BBMP limits)
22. 28(b)(ii) donee is a family member (TMC limits)
23. 28(b)(iii) any other limits
24. 30(1)(i) - where the lease purports to be for a term not exceeding one year in case of residential property
25. 30(1)(ii) - where the lease purports to be for a term not exceeding one year in case of commercial or industrial property

26. 30(1)(iii) - where the lease purports to be for a term exceeding one year and not exceeding ten years
27. 30(1)(iv) - where the lease purports to be for a term exceeding ten years and not exceeding twenty years
28. 30(1)(v) - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years
29. 30(1)(vi) - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term
30. "30(4)(i) Lease/Licence of Immovable Property with in Family Members - If the property is situated within the limits of
31. BBMP or City Corporation"
32. 30(4)(ii) Lease/Licence of Immovable Property with in Family Members - If the property is situated within the limits of City or Town Municipal Council or Town Panchayat area
33. "30(4)(iii) Lease/Licence of Immovable Property with in Family Members - If the property is situated within the limits other than the limits specified in items
(i) and (ii)"
34. 30(3)(a)(i) Mining Lease through Auction - where the lease purports to be for a term exceeding one year and not exceeding ten years.
35. 30(3)(a)(ii) Mining Lease through Auction - where the lease purports to be for a term exceeding ten years and not exceeding twenty years.
36. 30(3)(a)(iii) Mining Lease through Auction - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years.
37. 30(3)(a)(iv) Mining Lease through Auction - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term.
38. 30(3)(b)(i) Mining Lease through Grant - where the lease purports to be for a term exceeding one year and not exceeding ten years.
39. 30(3)(b)(ii) Mining Lease through Grant - where the lease purports to be for a term exceeding ten years and not exceeding twenty years.
40. 30(3)(b)(iii) Mining Lease through Grant - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years.
41. 30(3)(b)(iv) Mining Lease through Grant - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term.
42. 34(a) Mortgage with Possession
43. 34(b) Mortgage with out Possession
44. 39(1) Partition for Non Agricultural use (for the Properties other than Municipal/Urban/Town Panchayat)
45. 39(2) Partition for Non Agricultural use (Situated in Municipal/Urban/Town Panchayat)
46. 40(A) Instrument of Constitution
47. 40(B)(a)Reconstitution where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner or partners on reconstitution of such partnership firm.
48. 40(B)(b) Reconstitution in any other case
49. 40(C)(a) Dissolution of the property which belonged to one partner or partners when the partnership commenced is distributed or allotted or given to another partner or partners

50. 40(C)(b) Dissolution in any other case
51. 41(a) - when executed for the sole purpose of procuring the registration of one or more documents in relation to a single transaction or for admitting execution of one or more such documents; (Special Power of Attorney)
52. 41(b) - when authorizing one person or more to act in a single transaction other than the case mentioned in clause (a);
53. 41(c) - when authorizing not more than five persons to act jointly and severally in more than one transaction or generally;
54. 41(d) - when authorizing more than five but not more than ten persons to act jointly and severally in more than one transaction or generally;
55. 41(e) - when given for consideration and or when coupled with interest and authorizing the attorney to sell any immovable property;
56. 41(ea) - If relating to construction or development of an immovable property, including a multi-unit house or building or unit of apartment or flat or portion of a multi-storied building by a developer or builder or promotor or by whatever name called having a stipulation that, for such construction or development, the property shall be held jointly by the developer or builder or promoter or by whatever name called and the owner or lessee, as the case may be, of such property, or that it shall be sold jointly by them or that a part of it shall be held jointly by them and the remaining part thereof shall be sold jointly by them
57. 41(eb) - when given to person other than the father, mother, wife or husband, sons, daughters, brothers, sisters in relation to the executant authorizing such person to sell immovable property situated in Karnataka State.
58. 41(ec) - when given to person other than the father, mother, wife or husband, sons, daughters, brothers, sisters in relation to the executant authorizing such person to sell TDR
59. 41(f) - when executed by a principal or client for the sole purpose of authorizing the agent or broker to carry out all lawful acts and deeds relating to his / her trading operations including sale/purchase of marketable securities, transfer of securities towards stock exchange, receiving/releasing funds and securities from/to other parties on behalf of the principal or client.
60. 41(g) - when executed by a principal or client for the sole purpose of authorizing the depository participant to carry out all lawful acts and deeds relating to his/her demat account as per the bye-laws of the depositories/ regulations governing such operations.
61. 41(h) - in any other case
62. 44(a) - The amount/consideration of the Property does not exceed 1000
63. 44(b) - The amount/consideration of the Property exceeds 1000
64. 45(a) - Release not between family members
65. 45(b)(i) - Release between family members (BBMP limits)
66. 45(b)(ii) - Release between family members (TMC/CMC limits)
67. 45(b)(iii) - Release between family members other than (TMC/CMC limits)
68. 45(c)(i) Discharge Deed under KACOMP Act - Release of mortgage rights or lien for the amount or value secured does not exceed Rs. 1000

69. 45(c)(ii) Discharge Deed under KACOMP Act - Release of mortgage rights or lien for the amount or value secured exceeds Rs. 1000
70. 20(3) Sale by BDA/KHB of Flat Flat/Apartment
71. 20(1)(a) Sale of Agriculture Land
72. 20(1)(b) Sale of Building
73. 20(1)(c) Sale of Flat
74. 20(1)(d) Sale of Vacant Site or Plot
75. 20(2A)(i) where an instrument of Conveyance relating to the first sale of Flat/Apartment - Where the market value of which is Rs 2000000 or less than 2000000
76. 20(2A)(ii) where an instrument of Conveyance relating to the first sale of Flat/Apartment - Where the market value of which is above Rs 2500000 but up to and inclusive of 3500000
77. 20(7) Sale of Transfer of Development Rights
78. 20(5)(ii) Conveyance relating to industrial machinery - When industrial machinery is treated as immoveable property
79. Certificate of Denoting of the original duty on the counter part paid on the original (Same Duty as on the original instrument/Latest Transaction Data will be fetched from the Database)
80. 48A(i) - the disposition is not for the purpose of distributing the property of the settlor among his family
81. 48A(ii) - the disposition is for the purpose of distributing the property of the settlor among the members of his family BBMP limits
82. 48A(iii) - the disposition is for the purpose of distributing the property of the settlor among the members of his family TMC/CMClimits
83. 48A(iv) - the disposition is for the purpose of distributing the property of the settlor among the members of his family other limits
84. 48B Revocation
85. Will
86. Will including CancellationThe user shall select the Article based on the options available after selecting the nature of Document.

The user shall select the Sub-article based on the options available after selecting the nature of Document and Article.

3.4 Selection of Book Number

The system shall display the Book Number based on the Nature of Document, Article and Sub-article as selected by the user.

The user has the option to re-select the Nature of Document, Article and Sub-article if needed. The shall click on 'Continue' button to select the Type of Document.

4 PROPERTY SEARCH


In the Property Search module, the user could search property in the Master database such as Bhoomi, e-Swathu, e-Aasthi, other civic bodies and authorities. The property search will be based on the property description i.e., in case of agriculture land: Village Name, Hubli, Taluka, Survey Number and for Non-Agriculture Area Name, Ward Name, Town/City, PID or Property Number, Boundary and Extent.

Following are the sub modules:


- Search in Bhoomi, e-Swathu, e-Aasthi, and other Aligned Databases

#	Functions	Description
1	Search in Bhoomi, e-Swathu, e-Aasthi, and Aligned databases	Property located in the Bhoomi, e-Swathu, e-Aasthi and aligned databases shall be available as per the unique property identifiers mentioned in the draft deed document

User Interface (UI)



Overall Process Flow



i. Functional Step by Step Process

- i. **Document Registration:** The user shall select the Document Registration option to select type of document and then search the registered property in the Bhoomi, e-Swathu (Gram panchayat area property), e-Aasthi (Urban area properties), and other aligned databases
- ii. **Type of Document:** The user is required to select the type of the document for which the registration is required, the system will prompt the user to select any of the below options:
 - a. **Agricultural Document:** Registration of property, which is cultivable for the purpose of food production, animal husbandry, dairy, poultry etc which is related to farming activities
 - b. **Non-Agricultural Document:** Registration of Land/Building/Flat/Apartment, which used for any purpose other than agricultural activity shall be registered under this category
 - c. **Will/Miscellaneous Document:**
 1. **Will:** The user shall select Will option. Will is the testamentary document executed by testator which will come in effect after demise of the testator. Type of deeds of Will are as:
 - I. Will
 - II. Codicil (further will)
 - III. Will Cancellation
 2. **Miscellaneous Document:** Miscellaneous document refers to tangible property that can be moved from one place to another which includes title documents, transfer of rights, ownership/possession document and property of every other description, except immovable property
- iii. **Search in aligned databases:** As per the details selected by the user of the property, the system will redirect the search to the aligned databases. In case the user has selected agricultural option, the system will search the property in Bhoomi database based on the Village and Survey No. In case the user has selected Non-agricultural option, the system will search in aligned databases such as e-Swathu, e-Aasthi, other civic bodies and authorities databases based on the Location and PID Number
- iv. **Property Search:** After the property search in aligned databases, the system will prompt below cases to user:

Case 1 – Property found

- In case the system finds the property in the aligned database, the system will display the description of the property and allow the user to continue

Case 2 – Property not found

- In case the user does not find the property in any of the databases, then the user won't be allowed to proceed further

- v. **Court Module:** After the user confirms the property details, the system shall verify the property for any litigation, or any other issues submitted against the property

Case 1 – Property Verified

- In case the property details are successfully verified in the court module and no issues were found against the property. The user shall be asked for confirmation to proceed to the next module

Case 2 – Litigation/order found against the property

- In case any litigation/court order is found against the property, then the application won't proceed further until the litigation/order gets cleared against the property in the court and subsequently gets updated in the court entry module by the Sub registrar

- vi. **Liability Search:** After the user confirms the property details, the system shall verify the property for any litigations submitted in the Kaveri database by the Sub-Registrar Office

Case 1 – Litigation Found

- In case the litigation details found against the property then liability details along with order no., amount, issue date and issuing authority details will be displayed

Case 2 – Litigation Not Found

- In case the no litigation information is found against a property then the user shall be able to continue to the next process

User Interface (UI)

Property 1 of 1

DISTRICT : BENGALURU (RURAL)

TALUKA: DEVANAHALLI

HOBLI/ TOWN:VIJAYAPURA

INDEX II: VILLAGE: KOMMASANDRA

Results

S.No.	Survey No.	Hissa No.	Owner Name	Relationship	Relative Name	Available Extent		
						Acre	Gunta	Fraction of Gunta
1	56	1	Owner Name	Father	Name	2	3	45

Court Order Details

S.No.	SRO	Court Order No.	Injunction or Stay against the Property	Order Details	Survey No.	Current Number	Old Number	Boundaries		
								East	West	North
1	209	5631/2010	No	5631/2010	0	41	38	Road	Road	Private Pro

Liability Details


S.No.	SRO	Order No.	Liability Details	Amount	Issued Date	Issued By
1	209	5631/2010	5631/2010	0	41	38

4.1 Search property in Bhoomi, e-Swathu, e-Aasthi, and Aligned databases

i. **Brief Description**

In this function, based on the type of the property to be registered, the database is selected for locating the property particulars in the system. The Village/Area, Survey No./Property ID shall be entered in the system to get the property details, which shall be auto filled in the document registration application.

Property Search – Bhoomi, e-Swathu, e-Aasthi and Aligned Databases



ii. Functional Step by Step Process

- i. **Re-directed to Aligned Database:** Based on the type of document selected by the user, the system shall redirect to the aligned database
- ii. **Database Integration (Agricultural Property):** In case the user has selected agricultural property, the system will redirect the search in Bhoomi database. The search in Bhoomi database will be as per below process:
 - a. **Select District:** The user shall select the District from the list of Districts drop down in the system
 - b. **Select Taluka:** Based on the District selection, the Taluka list shall be populated, and user is required to select the Taluka from the drop down
 - c. **Select Hobli:** Based on the Taluka selection, the Hobli list shall be populated, and user is required to select the Hobli from the dropdown
 - d. **Select Village:** Based on the Hobli selection, the Village list shall be populated, and user is required to select the Village from the dropdown

***Note:** These dropdowns should come as per the Bhoomi database*

- e. **Survey Number:** After the selecting the jurisdiction of the property, the user shall enter unique survey number specific to the village allotted to the land by the authority
- f. **Hissa Number:** If the property found against the survey number is a divided land, then the user will enter hissa number of the property
- g. **Extent:** After the property search in Bhoomi is complete then the user shall be able to find the property in the database. The applicant shall have an option to select the transaction of the property which shall be carried out in part extent or full extent.

Case 1: Part extent

- a. In case of part extent or property owned by more than one owner, the user shall be required to enter the 11E Sketch Number of the property as per the below condition:
 - If the PyKi = No and Restriction = No and Number of owners = 1 and user selected 'full extent', then 11E sketch number not required
 - If the PyKi = Yes or Number of owners = more than 1 or user selected 'part extent', then 11E sketch number required
 - If Restriction = Yes, then the system won't allow the user to proceed further

SI No	Survey Number	Hissa Number	Whether PyKi	Restriction	No. of owners	Part Extent	Full Extent
1	56	1	No	No	1	○	●
2	56	2	Yes	No	2	○	○
3	56	3	No	Yes	2	○	○

Case 2: Full extent

- a. **Pyki/ No of owners Check:** The survey number along with the property attributes shall be checked in the Bhoomi database and if the property found against the survey number is a divided land then the hissa number of the property shall be displayed. In case, a sketch number is assigned against the divided land then Pyki entry shall return “Yes” value and user shall be required to enter the 11 E Sketch Number. If the value returned against the Pyki is “No” then 11E Sketch No. is not required
- h. **11E Sketch Number:** 11E sketch number is prepared by survey or land revenue department through tahsildar of the taluka when portion of the survey number property is transacted, and it will give sub number or Pyki number for divided portion of the land along with boundaries
- i. **Restriction Check:** In case, if there is any restriction put against a property by the department/authority then the Restriction value will return “Yes” and in that scenario the property registration could not proceed further. Otherwise, if the return value from the Bhoomi database against the Restriction is “No” then the system shall allow the user to proceed further

For PyKi and Restriction check, condition shall be followed as per the below table:

API (Bhoomi)		
Restriction	Restriction Type	Restriction Description
Y	PY	PyKi RTC
N	null	null
Y	null	null

- iii. **Database Integration (Non-Agricultural Property):** In case the user has selected non-agricultural property, the system will redirect the search to e-Swathu (gram panchayat area property) and e-Aasthi (Urban area properties) database. The search in e-Swathu, e-Aasthi database will be as per below process:
 - a. **Select District:** The user shall select the District from the list of Districts drop down in the system
 - b. **Select Taluka:** Based on the District selection, the Taluka list shall be populated, and user is required to select the Taluka from the drop down

- c. **Select Hobli:** Based on the Taluka selection, the Hobli list shall be populated, and user is required to select the Hobli from the dropdown
- d. **Select Village:** Based on the Hobli selection, the Village list shall be populated, and user is required to select the Village from the dropdown
- e. **PID Number:** The system will prompt the user to enter the Property ID number allotted by the authority
- f. **Property number details:** The user shall enter below property number details. User will be able to add multiple property number types
 - **Property number types:** The user will select property number type such as house number, door number, flat number, plot number, KHB number, city survey number etc from the dropdown
 - **Present Property number details:** After selecting property number types, user shall enter respective property number
- g. **Add more details:** The user if click on add more details then the user can again add more property number types otherwise user will continue with the process
- h. **Find my property:**

Case 1 – Property found

- In case the system finds the property in the database, then the property description shall be displayed along with the PDF document (in case of e-Swathu and e-Aasthi)

Case 2 – Property not found

- In case the user couldn't find the property in the Bhoomi, e-Swathu, e-Aasthi, and Aligned databases, then the system will prompt the user to check details/enter district, taluka, hobli, village/town and PID number again. Without the correct property details the system would not allow the user to proceed with the registration application
- i. **Display Property Document:** The property document shall be fetched in PDF format against the PID number entered by the user and the document shall be displayed on screen which shall allow the user to match property details against the draft deed document. The user will receive the message "Successfully found the property" from the system. Data will be sent for auto search in court module

- iv. **Article Selection:** The user will be required to select Stamp article, Stamp Sub article and Registration Fee article from the dropdown. Based on article selection, Book number will be auto fetched and displayed by the system. These details will be used to calculate market valuation and fee calculation for the selected property.

Note: The articles shall be selected only once for a document registration

User Interface (UI)

BHOOMI Search



Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka

Hello, Applicant


[Logout](#)



Awesome, We are so close to finding your property
Enter the Survey Number to find your property

DISTRICT

TALUKA

HOBLI

INDEX II: VILLAGE

SURVEY NO.

HISSA NO.

EXTENT

11 E SKETCH NUMBER

[Search](#)

Results								
S.No.	Survey No.	Hissa No.	Owner Name	Relationship	Relative Name	Available Extent		
						Acre	Gunta	Fraction of Gunta
1	56	1	Owner Name	Father	Name	2	3	45

e-Aasthi and e-Swathu Search



Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka

Hello, Applicant


[Logout](#)

[Home](#)
[About Department](#)
[Resources](#)
[External Links](#)
[Right to Information](#)
[Help](#)



Awesome, We are so close to finding your property
Enter the PID No. to continue

DISTRICT

TALUKA

HOBLI

VILLAGE/ TOWN

PID NO.

PROPERTY NUMBER DETAILS
Enter one or more details to further improve your search

PROPERTY NUMBER TYPE

PRESENT PROPERTY NUMBER DETAILS

Article Selection

SELECT STAMP ARTICLE

SELECT STAMP SUB-ARTICLE

SELECT REGISTRATION FEE ARTICLE

BOOK NUMBER

[+ Add a new Property](#)

4.2 Properties outside e-Aasthi and e-Swathu

i. **Brief Description**


For the registration of the document which involves the non-agricultural properties which lies outside the e-Aasthi and e-Swathu database, a separate provision is given for the document registration in Kaveri 2.0. Currently, there are 4 different types of property type:

- I. BBMP
- II. UPOR
- III. BDA
- IV. Others

I. **BBMP**

The Bruhat Bengaluru Mahanagara Palike (BBMP) is the administrative body responsible for the civic amenities and infrastructural assets of the Greater Bangalore Metropolitan Area. As per the status, there are 198 wards in the BBMP out of which 15 wards are integrated with the e-Aasthi and the properties lies under the 15 wards the user shall directly search the property in e-Aasthi section.

For the remaining properties which lies under 183 wards, the provision of manual entry shall be given and there won't be any property search function involve for the same.




i. Functional Step by Step Process

- The user shall select the Document type as Non-Agricultural and then select the BBMP option to enter the property details
- The property details shall be entered by the user, the district of the property shall be auto fetched as BBMP
- After which user shall select the Taluka, Hobli and Village and it shall be cascading dropdowns for all the three selections

- d. Also, the user shall be required to enter the Ward No. and PID number of the property
- e. **Property number details:** The user shall enter below property number details. User will be able to add multiple property number types
 - **Property number types:** The user will select property number type such as house number, door number, flat number, plot number, KHB number, city survey number etc from the dropdown
 - **Present Property number details:** After selecting property number types, user shall enter respective property number
- f. The user shall manually verify all the property details entered in the form and then submit the information for the Liability and Court Order Search in the Kaveri database
- g. If user decided to continue with the property, then in last section the Article, Sub-Article and Registration Fee article needs to be selected based on which the Book No. shall auto populate and displayed to the user

II. UPOR

The Urban Property Ownership Records (UPOR) is given by the urban development authorities in the State of Karnataka for the properties falling under Municipal Corporation, City Municipal Corporation (CMC), Town Municipal Corporation (TMC), and Town Panchayats.



i. Functional Step by Step Process

- a. The user shall select the Document type as Non-Agricultural and then select the UPOR option to enter the property details


- b. The property details shall be entered by the user, the district of the property shall be selected first
- c. After which user shall select the Taluka, Hobli and Village and it shall be cascading dropdowns for all the three selections
- d. Also, the user shall be required to enter the Road Name and UPOR number of the property, according to which the property shall be searched in the UPOR database

Note: Currently only 2 offices are integrated with the system and the search shall be made for those 2 offices only. For other UPOR properties, the user could continue with the data entry in the application

- e. **Property number details:** The user shall enter below property number details. User will be able to add multiple property number types
 - **Property number types:** The user will select property number type such as house number, door number, flat number, plot number, KHB number, city survey number etc from the dropdown
 - **Present Property number details:** After selecting property number types, user shall enter respective property number
- f. The user shall manually verify all the property details entered in the form and then submit the information for the Liability and Court Order Search in the Kaveri database
- g. If user decided to continue with the property, then in last section the Article, Sub-Article and Registration Fee article needs to be selected based on which the Book No. shall auto populate and displayed to the user

III. BDA

The Bangalore Development Authority is a regulatory body required “to prepare in the prescribed manner a Comprehensive Development Plan” for the Bangalore Metropolitan Region. It is a governmental organisation and the principal planning authority for Bangalore. It functions, under the Karnataka Town and Country Planning Act of 1961.




i. Functional Step by Step Process

- The user shall select the Document type as Non-Agricultural and then select the BDA option to enter the property details
- The property details shall be entered by the user, the district of the property shall be selected first
- After which user shall select the Taluka, Hobli and Village and it shall be cascading dropdowns for all the three selections

- d. Also, the user shall be required to enter the Road Name and BDA number of the property
- e. **Property number details:** The user shall enter below property number details. User will be able to add multiple property number types
 - **Property number types:** The user will select property number type such as house number, door number, flat number, plot number, KHB number, city survey number etc from the dropdown
 - **Present Property number details:** After selecting property number types, user shall enter respective property number
- f. The user shall manually verify all the property details entered in the form and then submit the information for the Liability and Court Order Search in the Kaveri database
- g. If user decided to continue with the property, then in last section the Article, Sub-Article and Registration Fee article needs to be selected based on which the Book No. shall auto populate and displayed to the user

IV. Others

All the non-agricultural properties which lie under the State of Karnataka and doesn't get covered under aligned database (e-Aasthi, e-Swathu) or BBMP, BDA and UPOR, all these properties shall be registered under the Others property section.



i. Functional Step by Step Process

- The user shall select the Document type as Non-Agricultural and then select the Others option to enter the property details
- The property details shall be entered by the user, the Zone/Jurisdiction of the property shall be selected from the three options TMC, CMC and Development Authorities

- c. After which user shall select the District, Taluka, Hobli and Village and it shall be cascading dropdowns for all the four selections
- d. Also, the user shall be required to enter the Road Name and PID number of the property
- e. **Property number details:** The user shall enter below property number details. User will be able to add multiple property number types
 - **Property number types:** The user will select property number type such as house number, door number, flat number, plot number, KHB number, city survey number etc from the dropdown
 - **Present Property number details:** After selecting property number types, user shall enter respective property number
- f. The user shall manually verify all the property details entered in the form and then submit the information for the Liability and Court Order Search in the Kaveri database
- g. If user decided to continue with the property, then in last section the Article, Sub-Article and Registration Fee article needs to be selected based on which the Book No. shall auto populate and displayed to the user

User Interface



Awesome, So Do you know where was it registered?

Select the Jurisdiction to continue

Select one to Continue



BBMP

The Bruhat Bengaluru Mahanagara Palike is the administrative body responsible for civic amenities and some infrastructural assets of the Greater Bangalore metropolitan area.



e-Swathu

It is the unique number given by the RDPR department for the properties following under the Gram Panchayat jurisdiction.



UPOR

Urban Property Ownership Records given by the urban development authorities for the properties falling under Municipal Corporation, City Municipal Council (CMC), Town Municipal Council (TMC) and Town Panchayats.



e-Aasthi

It is an unique number given by the urban development authorities for the properties falling under Municipal Corporation, City Municipal Council (CMC), Town Municipal Council (TMC) and Town Panchayats.



BDA

The Bangalore Development Authority of Bangalore, India, is a governmental organization and the principal planning authority for Bangalore.



Others

Select this option if your property does not lie in any of the previous option.

BBMP

DISTRICT

Value ▾

TALUKA

Value ▾

HOBLI

Value ▾

VILLAGE/ TOWN

Value ▾

ROAD NAME

Value

WARD NUMBER

Value ▾

PID NO.

Value

PROPERTY NUMBER DETAILS

Enter one or more details to further improve your search

PROPERTY NUMBER TYPE

Value ▾

PRESENT PROPERTY NUMBER DETAILS

Value

[Add more details](#)

Continue

UPOR



Awesome, We are so close to finding your property

Enter the PID No. to continue

DISTRICT

Value

▼

TALUKA

Value

▼

HOBLI

Value

▼

VILLAGE/ TOWN

Value

▼

ROAD NAME

Value

UPOR NUMBER

Value

PROPERTY NUMBER DETAILS

Enter one or more details to further improve your search

PROPERTY NUMBER TYPE

Value

▼

PRESENT PROPERTY NUMBER DETAILS

Value

[Add more details](#)

BDA



Awesome, We are so close to finding your property

Enter the PID No. to continue

DISTRICT

Value

▼

TALUKA

Value

▼

HOBLI

Value

▼

VILLAGE/ TOWN

Value

▼

ROAD NAME

Value

BDA NUMBER

Value

PROPERTY NUMBER DETAILS

Enter one or more details to further improve your search

PROPERTY NUMBER TYPE

Value

▼

PRESENT PROPERTY NUMBER DETAILS

Value

[Add more details](#)

Other Properties

ZONE Value	DISTRICT Value	TALUKA Value
HOBLI Value	VILLAGE/ TOWN Value	ROAD NAME Value
PID NUMBER Value		
PROPERTY NUMBER DETAILS Enter one or more details to further improve your search		
PROPERTY NUMBER TYPE Value	PRESENT PROPERTY NUMBER DETAILS Value	

[Add more details](#)

[Continue](#)


4.3GIS

A geographic information system is a conceptualized framework that provides the ability to capture and analyse spatial and geographic data.

4.3.1 GIS Search

i. Brief Description

In the GIS Search, the user shall be able to find the property by the dropping pin on the Map and the property details shall be auto fetched from the system with Latitude and Longitude of the property. In case of an apartment/flat, the coordinates of the building shall be selected.



ii. Functional Step by Step Process


- i. **Property mapped in GIS:** As applicant selects property search, system will check if the property is mapped in GIS as per below process. In case the property is mapped in GIS then the system will redirect to the map and in case the property is not mapped in GIS then the process will end
- ii. **Re-directed to the Map:** Based on the property mapped on GIS
 - a. **Select District:** The user shall select the District from the interactive Map

- b. **Select Taluka:** Based on the District selection, the Taluka boundaries shall be populated, and user is required to select the Taluka in the Map
 - c. **Select Hobli:** Based on the Taluka selection, the Hobli boundaries shall be populated, and user is required to select the Hobli in the Map
 - d. **Select Village:** Based on the Hobli selection, the Village boundaries shall be populated, and user is required to select the Village in the Map
- iii. **Drop pin in Map:** Based on the user selection, the map of the village/area shall be displayed to the user, and it will allow user to locate the property and drop a pin on the GIS map
 - iv. **Display Property Details:** After user drop a pin on the map, the property mapped against the latitude and longitude shall appear on the screen with the complete property details.
 - v. **Select Property:** In case, multiple property is registered against the same latitude and longitude or there is a multi-storey building then based on the pin drop by the user, user shall be required to select the property from the list

4.3.2 GIS Mapping

i. Brief Description

In the GIS Mapping, the user shall be able to locate and add the property by the dropping pin of the property on the Map and the Latitude and Longitude of the property shall be auto fetched from the system.




ii. Functional Step by Step Process

- i. **Select Property:** Based on the user selection of the property. The system shall check if the property is mapped in GIS. In case the property is not mapped in GIS then the user shall locate the property in the map and system will store the coordinate of the property as Hash in Blockchain
- ii. **Pin the location of property in the map:** Based on the area selected by the user, the map of the area shall be displayed to the user, and it will allow user to locate the property and drop a pin of the property on the GIS map
- iii. **Auto fetch latitude and longitude of the location:** After user drop a pin on the map, the property mapped against the latitude and longitude shall appear on the screen with the complete property details. The coordinates of the property shall be stored in Kaveri database

5 PROPERTY SCHEDULE

i. Brief Description

Property information and description will be described in the property schedule. Based on the description, nature, type and unit of measurement of property along with boundaries for identification of the property the valuation of the property is determined. On the basis of market value or consideration amount whichever is higher, stamp duty and registration fees are calculated.



ii. Functional Step by Step Process

- i. Based on user selection of Property schedule, the system shall auto fetch and display property details such as district, taluka, hobli, village, total area, east to west and north to south
- ii. Agricultural Property:

Case 1: Agricultural Property

In case the property is agricultural type then the user shall enter total land area, boundaries i.e., east, west, north & south and description of the property.

Case 2: Non-Agricultural Property

In case the property is non-agricultural type then the user shall enter details as per below conditions.

- For vacant site and building, the user shall enter total land area, North to south and East to west, boundaries i.e., east, west, north & south and description of the property.
 - For building, the user shall also enter site area, built up area and floor area
 - For Flat/Apartment, the user shall enter total land area, undivided share in total land area, super built up or carpet area, common amenities, boundaries i.e., east, west, north & south and description of the property
- iii. In case the schedule is complete for all the properties, the details will be saved in the system and user shall continue with the next process. In case the schedule is not complete for all properties then the system shall redirect the user to enter the details

User Interface (UI)

< PROPERTY 1 OF 3 >

DISTRICT : BENGALURU (RURAL)	TALUKA: DEVANAHALLI	HOBLI/ TOWN:VIJAYAPURA	INDEX II: VILLAGE: KOMMASANDRA
Schedule Type	Total Area	East to West	North to South
Schedule A	2.59 Acres	3000 ft	3000 ft
BOUNDARIES			
East	West	North	South
Road	Road	Private Property	Venkatraman..
Description of Property			
Value			

6 ADDITION OF PROPERTIES

6.1 Add Property

The user shall add another property by clicking 'Add Property' button.

Now, the system shall request the user to select only the Article and Sub-article keeping the Nature of Document frozen as selected earlier and can't be changed. Only the available articles and sub-articles for the frozen nature of document can be chosen from among the dropdown option. Once the user selects the Article and Sub-article, the clicks on 'Continue' button, the system shall take the user through the usual process of Property Search and Property Schedule.

The user shall add multiple properties following the above said process.

7 MARKET VALUATION

i. Brief Description

In addition to the information below, please find a detailed requirements document attached:

<https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/GIS%20based%20valuation%20FRS%20v%201.7.docx?d=wffbbc4a8e1c04ccf997115e23e2d6fbf&csf=1&web=1&e=8bYPcH>

Please use the above link to access GIS based market valuation detailed FRS.

Market valuation in relation to any property which is the subject matter of instrument means the price which such property would have fetched in the opinion of the deputy commissioner or the appellate authority or the chief controlling revenue authority, if sold in open market on the date of execution of such instrument or the consideration stated in the instrument whichever is higher.

Market Valuation

Applicant | **System**

```

graph TD
    subgraph Applicant
        Start(( )) --> Submit[Submit Property Schedule]
        Submit --> SelectUnit[Select Unit]
        EnterArea[Enter Total Area] --> SelectUnit
        SelectUnit --> Valuate1[Valuate]
        Valuate1 --> Confirm1[Confirm and Continue]
        Confirm1 --> End1(( ))
    end

    subgraph System
        Redirect[Redirect to Market Valuation]
        Display[Display District, Taluka, Hubli, Village and Property Usage]
        TypeProp{Type of Property}
        Agri[Calculate Market Value based on the selection]
        NonAgri[Calculate Market Value based on the selection]
        SelectAgr[Select Agricultural Rate Details]
        SelectAnnexure1[Select Annexure Rules]
        Confirm2[Confirm and Continue]
        SelectPropType[Select Property Type]
        EnterGFA[Enter Ground Floor Area]
        EnterAGA[Enter Above Ground Floor Area]
        SelectRate1[Select Rate Details]
        SelectConst[Select Construction Type Details]
        SelectCarP1[Select Covered Car Parking]
        SelectCarP2[Select Open Car Parking]
        SelectAnnexure2[Select Annexure Rules]
        SelectAmenities[Select Apartment Special Amenities]
        SelectCarP3[Select Covered Car Parking]
        SelectCarP4[Select Open Car Parking]
        SelectRate2[Select Rate Details]
        SelectAnnexure3[Select Annexure Rules]
        SelectFloor[Select Floor Dropdown]
        Valuate2[Valuate]
        SelectRate3[Select Rate Details]
        SelectAnnexure4[Select Annexure Rules]
        Valuate3[Valuate]
        CalculateFinal[Calculate Market Value based on the selection]
    end

    Submit --> Redirect
    EnterArea --> Redirect
    Redirect --> Display
    Display --> TypeProp
    TypeProp -- Agricultural --> SelectAgr
    TypeProp -- Non-Agricultural --> NonAgri
    SelectAgr --> SelectAnnexure1
    SelectAnnexure1 --> Confirm2
    Confirm2 --> SelectPropType
    SelectPropType --> EnterGFA
    EnterGFA --> EnterAGA
    EnterAGA --> SelectRate1
    SelectRate1 --> SelectConst
    SelectConst --> SelectCarP1
    SelectCarP1 --> SelectCarP2
    SelectCarP2 --> SelectAnnexure2
    SelectAnnexure2 --> SelectAmenities
    SelectAmenities --> SelectCarP3
    SelectCarP3 --> SelectCarP4
    SelectCarP4 --> SelectRate2
    SelectRate2 --> SelectAnnexure3
    SelectAnnexure3 --> SelectFloor
    SelectFloor --> Valuate2
    Valuate2 --> SelectRate3
    SelectRate3 --> SelectAnnexure4
    SelectAnnexure4 --> Valuate3
    Valuate3 --> CalculateFinal
    CalculateFinal --> End1
  
```

Submit Property Schedule (Applicant)

Redirect to Market Valuation (System)

Display District, Taluka, Hubli, Village and Property Usage (System)

Calculate Market Value based on the selection (System)

Type of Property (System)

Select Agricultural Rate Details (System)

Select Annexure Rules (System)

Confirm and Continue (System)

Select Property Type (System)

Enter Ground Floor Area (System)

Enter Above Ground Floor Area (System)

Select Rate Details (System)

Select Construction Type Details (System)

Select Covered Car Parking (System)

Select Open Car Parking (System)

Select Annexure Rules (System)

Select Apartment Special Amenities (System)

Select Covered Car Parking (System)

Select Open Car Parking (System)

Select Rate Details (System)

Select Annexure Rules (System)

Select Floor (Dropdown) (System)

Valuate (System)

Select Rate Details (System)

Select Annexure Rules (System)

Valuate (System)

Calculate Market Value based on the selection (System)

Confirm and Continue (Applicant)

ii. Functional Step by Step Process

Agricultural Property:

- i. As the user submits property schedule, the system will redirect the user to the 'market valuation' option
- ii. The system shall auto fetch and display user's district, taluka, hobli, village, and property usage

S.No.	Data Type	Table Name	Column Name
1	District	districtmaster	districtnamee
2	Taluka	talukmaster	talukname
3	Hobli	hoblimaster	hoblinamee
4	Village	villagemaster	villagenamee

- iii. The user shall select agriculture or non-agriculture in 'property usage type' dropdown and shall enter area and select 'measurement unit' from dropdown

S.No.	Data Type	Table Name	Column Name
1	Property usage type	propertytypemaster	propertytypenamee
2	Measurement Unit	measunitmaster	descriptionenglish

- iv. In case the user has selected 'Agricultural' in 'property usage type' then the user will be required to select agricultural rate details as per below option:

- a. Dry, No Source of Irrigation, Black Soil
- b. Bagayat, Wet
- c. Wet (Assured Water Supply from Government Tanks/Canals), One Crop

S.No.	Data Type	Table Name	Column Name
1	Dry, No Source of Irrigation, Black Soil	mas_val_agrilandtypes	description
2	Bagayat, Wet	mas_val_agrilandtypes	description
3	Wet (Assured Water Supply from Government Tanks/Canals), One Crop	mas_val_agrilandtypes	description

- v. The agricultural rate details are predetermined by the central valuation committee added by IGR. The rates are updated every year if they are revised as per the market valuation estimation rules
- vi. The agricultural rate details shall be auto fetched from the backend (Table Name: kaverival.rateagriculturaldetail) by the system as per user's selection of area, measurement unit and agricultural land type for rate details
- vii. After selection of 'agricultural rate', the user will be required to select 'annexure rules' as per below option:
 - a. **Corner Property** – Any property having two side road in the corner of the site will be known as corner property. The valuation for corner property will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Corner Property	kaveri.mas_val_annexurerules	description

- b. **Any Two side Roads** - Any property having two side road opposite each other will be known as corner property. The valuation for any Two side Roads will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Any Two side Roads	kaveri.mas_val_annexurerules	description

- c. **Industrial Purpose**- Properties converted for the purpose of industries or falling in the industrial area. The valuation for any Industrial Purpose will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Industrial Purpose	kaveri.mas_val_annexurerules	description

- d. **Property Abutting to NH** - Properties facing national highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to NH	kaveri.mas_val_annexurerules	description

- e. **Property Abutting to SH** - Properties facing state highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 25% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to SH	kaveri.mas_val_annexurerules	description

- f. **Converted Property for Residential Purpose (Undeveloped) 5 to 10 Guntas** – Agriculture land converted for use of non-agriculture purpose through appropriate authorities if they are undeveloped for the purpose for which it is converted and if area falls above 5 guntas and below 10 guntas are valued as residential sites but 50% less than the site rate

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Residential Purpose (Undeveloped) 5 to 10 Guntas	kaveri.mas_val_annexurerules	description

- g. **Converted Property for Commercial Purpose (Undeveloped) 5 to 10 Guntas** - Agriculture land converted for use of non-agriculture commercial purpose through appropriate authorities if they are undeveloped for the purpose for which it is converted and if area falls above 5 guntas and below 10 guntas are valued as commercial sites but 50% less than the commercial site rate

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Commercial Purpose (Undeveloped) 5 to 10 Guntas	kaveri.mas_val_annexurerules	description

- h. **Converted Property for Industrial Purpose (Undeveloped) 5 to 10 Guntas** - Agriculture land converted for use of non-agriculture industrial purpose through appropriate authorities if they are undeveloped for the purpose for which it is converted and if area falls above 5 guntas and below 10 guntas are valued as industrial sites but 50% less than the industrial site rate

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Industrial Purpose (Undeveloped) 5 to 10 Guntas	kaveri.mas_val_annexurerules	description

- i. **Converted Property for Residential Purpose (Undeveloped) more than 10 Guntas** - Agriculture land converted for use of non-agriculture purpose through appropriate authorities if they are undeveloped for the purpose for which it is converted and if area is more than 10 guntas, are for the purpose of estimation of market value 50% more than the agriculture property rate of the area

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Residential Purpose (Undeveloped) more than 10 Guntas	kaveri.mas_val_annexurerules	description

- j. **Converted Property for Commercial Purpose (Undeveloped) more than 10 Guntas** - Agriculture land converted for use of non-agriculture for the commercial purpose through appropriate authorities if they are undeveloped for the commercial purpose for which it is converted and if area is more than 10 guntas, are for the purpose of estimation of market value 60% more than the agriculture property rate of the area

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Commercial Purpose (Undeveloped) more than 10 Guntas	kaveri.mas_val_annexurerules	description

- k. **Converted Property for Industrial Purpose (Undeveloped) more than 10 Guntas** - Agriculture land converted for use of non-agriculture for the industrial purpose through appropriate authorities if they are undeveloped for the industrial purpose for which it is converted and if area is more than 10 guntas, are for the purpose of estimation of market value 25% more than the agriculture property rate of the area

S.No.	Data Type	Table Name	Column Name
1	Converted Property for Industrial Purpose (Undeveloped) more than 10 Guntas	kaveri.mas_val_annexurerules	description

SI No	Annexure Rule	Percentage
1	Corner Property	10%
2	Any Two side Roads	10%
3	Industrial Purpose	50%
4	Property Abutting to NH	50%
5	Property Abutting to SH	25%
6	Converted Property for Residential Purpose (Undeveloped) 5 to 10 Guntas	-50%
7	Converted Property for Commercial Purpose (Undeveloped) 5 to 10 Guntas	-50%
8	Converted Property for Industrial Purpose (Undeveloped) 5 to 10 Guntas	-50%
9	Converted Property for Residential Purpose (Undeveloped) more than 10 Guntas	50%
10	Converted Property for Commercial Purpose (Undeveloped) more than 10 Guntas	60%
11	Converted Property for Industrial Purpose (Undeveloped) more than 10 Guntas	25%

- viii. In the annexure rules, the user will be able to select either corner property or any two sides roads but not both simultaneously. The user will be required to select 'Yes' or 'No' for each annexure rule options
- ix. As per selection of various 'annexure rules' option, the valuation of agricultural property shall vary for the user as per below calculation:
- **Annexure Rules Value = Sum of percentage of Rates (as per user selection)**
 - **Total Valuation Amount = Estimated Guidance Rate + Annexure Rule value**
- x. The user shall confirm the total valuation amount and continue with the process

Scenario 1

Total Area = 100-acre, Base Rate = 5000 per acre, the attributes of the property selected under the annexure rules are as follows:

- Two-sided property (Extra 10% rate)
- Property Abutting to National Highway (Extra 50% rate)

Calculation:

Total Base Rate Valuation = Total Area * Base Rate = 100*5000 = 5,00,000 Rs.

Annexure Rules:

- Two-sided property (Extra 10% rate) = 10% of 5,00,000 = 50,000 Rs
- Property Abutting to National Highway (Extra 50% rate) = 2,50,000 Rs

Therefore, Total Annexure Valuation = 3,00,000 Rs

Total Market Valuation = 8,00,000 Rs

Non-Agricultural Property: Building

- i. In case the user has selected 'Non-Agricultural' in 'property usage type' then the user will be required to select property type from the below dropdown option:
 - a. Building
 - b. Flat/ Apartment
 - c. Vacant Site

S.No.	Data Type	Table Name	Column Name
1	Building	propertytypemaster	propertytypenamee
2	Flat/ Apartment	propertytypemaster	propertytypenamee
3	Vacant Site	propertytypemaster	propertytypenamee

- ii. In case the user selects 'Building' option in 'property type' the user will be required 'select rate details' from the below dropdown options:
 - a. Residential
 - b. Commercial
 - c. Industrial

S.No.	Data Type	Table Name	Property Type ID	Column Name
1	Residential	propertytypemaster	4	propertytypenamee
2	Commercial	propertytypemaster	5	propertytypenamee
3	Industrial	propertytypemaster	6	propertytypenamee

- iii. The Non-Agricultural rate details are predetermined by the central valuation committee added by IGR. The rates are updated every year if they are revised as per the market valuation estimation rules
- iv. The Non-Agricultural rate details shall be auto fetched from the backend (Table: kaveri.mas_val_openbuilrates) by the system as per user's selection of area, measurement unit and property type for non-agriculture rate details

S.No	Data Type	Table Name	Column Name
1	Total Area	propertyschedules	totalarea
2	Measurement unit	measurementunitmaster	descriptionenglish
3	Property type	propertytypemaster	propertytypenamee

- v. As per rate details selected, the user will be required to select 'construction type details' as per below option:

Construction Type Details		Property Type ID	Table Name	Column Name
Sl No	Construction Type			
1	RCC Granite flooring, Teak wood	1	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
2	RCC Marble flooring, Teak wood	2	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
3	RCC Mosaic/Vitrified/ Ceramic flooring, Teak wood	3	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
4	RCC Mosaic/Polished Kadapa/ShahBad/Betam Jelli flooring, Honne wood, Steel Window	4	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
5	RCC Red Oxide flooring Any Wood or Steel Window	5	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
6	Madras Roofing, Mangalore Tiles, A C Sheet Red Oxide flooring, Jungle Wood, Cement Wall	6	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
7	Madras Roofing, Mangalore Tiles, A C Sheet	7	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description
8	Black Tiles, Mud Roofing, Kadapa, Mud Wall, jungle Wood, Hut	8	kaveri.mas_val_constructiontypes kaveri.mas_val_constructionrates	description

- vi. The user shall be required to enter ground floor area and above ground floor area as per selection of construction type. As per user selection of 'construction type details and value entered for the 'ground floor area' and 'above ground floor area', the system shall auto fetch the value from the backend database

SI No	Data Type	Floor ID	Table Name	Column Name
1	Ground Floor	1	kaveri.mas_val_buildingfloors	description
2	Above Ground Floor	2	kaveri.mas_val_buildingfloors	description

- vii. The user shall be required to select annexure rules as per below option:

- a. **Corner Property** – Any property having two side road in the corner of the site will be known as corner property. The valuation for corner property will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Corner Property	kaveri.mas_val_annexurerules	description

- b. **Any Two side Roads** - Any property having two side road opposite each other will be known as corner property. The valuation for any Two side Roads will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Any Two side Roads	kaveri.mas_val_annexurerules	description

- c. **Industrial Purpose** - Properties converted for the purpose of industries or falling in the industrial area. The valuation for any Industrial Purpose will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Industrial Purpose	kaveri.mas_val_annexurerules	description

- d. **Property Abutting to NH** - Properties facing national highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to NH	kaveri.mas_val_annexurerules	description

- e. **Property Abutting to SH** - Properties facing state highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 25% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to SH	kaveri.mas_val_annexurerules	description

Sl No	Annexure Rule	Percentage
1	Corner Property	10%
2	Any Two side Roads	10%
3	Industrial Purpose	50%
4	Property Abutting to NH	50%
5	Property Abutting to SH	25%

- viii. In the annexure rules, the user will be able to select either corner property or any two sides roads but not both simultaneously. The user will be required to select 'Yes' or 'No' for each annexure rule options. As per user's selection of annexure rules, the system shall calculate and auto fetch the value from the backend
- ix. The user shall select covered car parking and enter total number of covered car parking

S.No.	Data Type	Table Name	Column Name
1	Covered Car Parking	kaveri.mas_val_parkingtypes kaveri.mas_val_parkingrates	description

- x. The user shall select open car parking and enter total number of open car parking

S.No.	Data Type	Table Name	Column Name
1	Open Car Parking	kaveri.mas_val_parkingtypes kaveri.mas_val_parkingrates	description

- xi. The system shall auto fetch the building rate, construction type details, annexure rules & parking type as per user's selection. The system shall calculate conversion of measurement unit to square meter (Nonagricultural property)
- **Annexure Rules Value = Sum of percentage of Rates (as per user selection)**
 - **Total Valuation Amount = Estimated Guidance Rate + Annexure Rule value (as per user selection) + Construction type value (as per user selection) + Parking Type (as per user selection)**
- xii. The system shall calculate market value based on user's selection and will display Annexure rules and total valuation amount. The user will confirm and continue with the process

Non-Agricultural Property: Flat/Apartment

- i. In case the user has selected 'Non-Agricultural' in 'property usage type' and 'Flat/Apartment' option in 'property type' then user will be required to select floors: Ground floor, first floor, second floor in rate details option

Table: kaveri.mas_val_flatrates

S.No.	Data Type	Table Name	Column Name
1	Floor	mas_val_apartmentfloorrates	floorfrom; floorto
2	Property Type	propertytypemaster	propertytypename
3	Amenities	kaveri.mas_val_apartmentspecialameneties kaveri.mas_val_apartmentspecialamenetyrules	namewithamenities

- ii. As per rate details selected, the user will be required to select 'apartment special amenities' details as per below table:

Apartment Special Amenities	
Sl. No.	Apartment Amenity
1	Club house, Community hall, Conference hall, party hall, Card room, Reading room, library, Banquet hall, party area, party lawn and similar types of amenities
2	Jogging track, cycling track, Walking track, Pebble pathway, Reflexology path and similar types of amenities.
3	Children play area, tot cot, children game area, Garden, Water body, Decorative pool Plantation Garden, Barbeque pits, crèche, landscape area, fountain and similar types of amenities.
4	Canteen, Mall, Commercial space, ATM, Bank, Hopcom, Janatha Bazar, Nandini Milk outlet, Provision store, Parlor, Cafeteria, Supermarket, Plaza and similar types of amenities.
5	All type of outdoor play area, Badminton, Tennis, Basketball, Baseball, Cricket, Football, Hockey and similar types of amenities.
6	All type of indoor game area, squash, snooker, Table tennis, carom room, Indoor games area and similar types of amenities
7	Swimming pool indoor, Kid's pool, wading pool, aqua gym and similar types of amenities
8	Cargo lift, elevator, Mechanical lift for car park, High speed elevator and similar types of amenities
9	Surveillance of common area, manned security with video surveillance intelligent security, Motion sensor-based lighting multi camera security, CCTV, Gated community, Intercom, Wifi Internet parlor, Video conference facility, Generator, UPS, Kiosk, Visitor Tracking system and similar types of amenities
10	Helipad and Golf field
11	Outdoor Amphitheatre, Open air theatre, Open stage and similar types of amenities

Apartment Special Amenities	
Sl. No.	Apartment Amenity
12	Health clinic, Ayurvedic parlor, Massage parlour, Beauty parlour, Spa, Aerobics, Yoga meditation, Unisex parlour, Steam & Sauna Jacuzzi, Gym, Day care center, Health club and similar types of amenities
13	Indoor Amphi theatre, Dance & Karaoke hall, Drama stage, Home theater hall
14	Home automation, smart home, IP door lock, prepaid power supply, piped cooking gas supply, gas bank, gas detector
15	Other Special Ameneties

As per selection of Apartment Amenity by the user, the system shall auto fetch the apartment base rate from the database.

S.No.	Data Type	Table Name	Column Name
1	Apartment Amenities	kaveri.mas_val_apartmentspecialameneties kaveri.mas_val_apartmentspecialamenetyrules	namewithamenities

iii. The user shall be required to select annexure rules as per below option:

- a. **Corner Property** – Any property having two side road in the corner of the site will be known as corner property. The valuation for corner property will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Corner Property	kaveri.mas_val_annexurerules	description

- b. **Any Two side Roads** - Any property having two side road opposite each other will be known as corner property. The valuation for any Two side Roads will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Any Two side Roads	kaveri.mas_val_annexurerules	description

- c. **Industrial Purpose** - Properties converted for the purpose of industries or falling in the industrial area. The valuation for any Industrial Purpose will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Industrial Purpose	kaveri.mas_val_annexurerules	description

- d. **Property Abutting to NH** - Properties facing national highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to NH	kaveri.mas_val_annexurerules	description

- e. **Property Abutting to SH** - Properties facing state highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 25% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to SH	kaveri.mas_val_annexurerules	description

- f. **Open Terrace** – After completion of flats/apartment, the right to use open terrace exclusively by any person then the valuation will be 50% of the super built up area enter by the user

S.No.	Data Type	Table Name	Column Name
1	Open Terrace	kaveri.mas_val_annexurerules	description

- g. **Garden Area** - After completion of flats/apartment, the right to use open garden area exclusively by any person then the valuation will be 50% of the super built up area enter by the user

S.No.	Data Type	Table Name	Column Name
1	Garden Area	kaveri.mas_val_annexurerules	description

- h. **Exclusive Area** - After completion of flats/apartment, the right to use exclusive area by any person then the valuation will be 25% of the super built up area enter by the user

S.No.	Data Type	Table Name	Column Name
1	Exclusive Area	kaveri.mas_val_annexurerules	description

SI No	Annexure Rule	Percentage
1	Corner Property	10%
2	Any Two side Roads	10%
3	Industrial Purpose	50%
4	Property Abutting to NH	50%
5	Property Abutting to SH	25%
6	Open Terrace	50%
7	Garden Area	50%
8	Exclusive Area	25%

- xiii. In the annexure rules, the user will be able to select either corner property or any two sides roads but not both simultaneously. The user will be required to select 'Yes' or 'No' for each annexure rule options. As per user's selection of annexure rules, the system shall calculate the value based on the flat rate auto-fetched from the backend database
- iv. For individual apartment/flat, if estimated guidance value (EGV) is fixed then Corner Property, Any Two side Roads, Industrial Purpose, Property Abutting to NH Property Abutting to SH annexure rules will not apply
- v. In the annexure rules if the user has selected Open Terrace, Garden Area or Exclusive Area then the user shall be required to enter their area, as per selection by the user, the system shall auto fetch the value from the backend database. Please refer scenario 2 as mentioned below:

SI No	Data Type	Table Name	Column Name
1	Open Terrace (Rate Details)	mas_val_apartmentfloorrates	floorfrom; floorto
2	Garden Area (Rate Details)	mas_val_apartmentfloorrates	floorfrom; floorto
3	Exclusive Usage Area (Rate Details)	mas_val_apartmentfloorrates	floorfrom; floorto

- vi. The user shall select covered car parking and enter total number of covered car parking

S.No.	Data Type	Table Name	Column Name
1	Covered Car Parking	kaveri.mas_val_parkingtypes kaveri.mas_val_parkingrates	description
2	Open Car Parking	kaveri.mas_val_parkingtypes kaveri.mas_val_parkingrates	description

- vii. The user shall select open car parking and enter total number of open car parking
As per selection of parking type by the user, the system shall auto fetch the rate value from the backend database
- viii. The user shall select floor from the dropdown as mentioned below:

0-5,6,7,8,9,10,11,12,13,14,15-200

Table: kaveri.mas_val_apartmentfloorrates

S.No.	From Floor	To Floor	Rate Value
1	0	5	0
2	6	6	0.5
3	7	7	1
4	8	8	1.5
5	9	9	2
6	10	10	2.5
7	11	11	3
8	12	12	3.5
9	13	13	4
10	14	14	4.5
11	15	200	5

- ix. The system shall calculate market value based on user's selection and shall display Annexure rules and total valuation amount. The system shall calculate conversion of measurement unit to square meter (Nonagricultural property). The user will confirm and continue with the process

- **Annexure Rules Value = Sum of percentage of Rates (as per user selection)**
Total Valuation Amount = Estimated Guidance Rate + Apartment special amenities + Annexure Rule value (as per user selection) + Parking Type (as per user selection) + Floor (as per user selection)

Scenario 2

The market valuation of the property in case of Open Terrace, Garden Area, and Exclusive Usage Area is selected under the Annexure Rules

Total Area = 100 sqm, Base Rate = 5000 per sqm, the attributes of the property selected under the annexure rules are as follows:

- Two-sided property (Extra 10% rate)
- Open Terrace (50% of the super built up area enter by the user) – 10 sqm
- Garden Area (50% of the super built up area enter by the user) – 20 sqm
- Exclusive Usage Area (25% of the super built up area enter by the user) – 10 sqm

Calculation:

Total Base Rate Valuation = Total Area * Base Rate = $100 \times 5000 = 5,00,000$ Rs.

Annexure Rules:

- Two-sided property (Extra 10% rate) = 10% of 5,00,000 = 50,000 Rs
- Open Terrace (50% of the 10 sqm super built-up area) = 50% of (10 sqm * Base Rate) = 50% of (10 * 5000) = 50% of 50,000 = 25,000 Rs
- Garden Area (50% of the 20 sqm super built-up area) = 50% of (20 sqm * Base Rate) = 50% of (20 * 5000) = 50% of 1,00,000 = 50,000 Rs
- Exclusive Usage Area (25% of the 10 sqm super built-up area) = 25% of (10 sqm * Base Rate) = 25% of (10 * 5000) = 25% of 50,000 = 12,500 Rs

Therefore, Total Annexure Valuation = $50,000 + 25,000 + 50,000 + 12,500 = 1,37,500$ Rs.

Total Market Valuation = 6,37,500 Rs.

Non-Agricultural Property: Vacant Site

- i. In case the user has selected 'Non-Agricultural' in 'property usage type' and 'Vacant Site' option in 'property type' then user will be required to select rate details as per below option:
- Residential
 - Commercial
 - Industrial

S.No.	Data Type	Table Name	Property Type ID	Column Name
1	Residential	propertytypemaster	4	propertytypenamee
2	Commercial	propertytypemaster	5	propertytypenamee
3	Industrial	propertytypemaster	6	propertytypenamee

- ii. The user shall be required to select annexure rules from as per below option:
- Corner Property** – Any property having two side road in the corner of the site will be known as corner property. The valuation for corner property will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Corner Property	kaveri.mas_val_annexurerules	description

- Any Two side Roads** - Any property having two side road opposite each other will be known as corner property. The valuation for any Two side Roads will be 10% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Any Two side Roads	kaveri.mas_val_annexurerules	description

- Industrial Purpose**- Properties converted for the purpose of industries or falling in the industrial area. The valuation for any Industrial Purpose will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Industrial Purpose	kaveri.mas_val_annexurerules	description

- Property Abutting to NH** - Properties facing national highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 50% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to NH	kaveri.mas_val_annexurerules	description

- Property Abutting to SH** - Properties facing state highway are mostly used for commercial purpose. The value will be high for property abutting to NH. The valuation for any Property Abutting to NH will be 25% higher than the selected property type

S.No.	Data Type	Table Name	Column Name
1	Property Abutting to SH	kaveri.mas_val_annexurerules	description

SI No	Annexure Rule	Percentage
1	Corner Property	10%
2	Any Two side Roads	10%
3	Industrial Purpose	50%
4	Property Abutting to NH	50%
5	Property Abutting to SH	25%

- iii. In the annexure rules, the user will be able to select either corner property or any two sides roads but not both simultaneously. The user will be required to select 'Yes' or 'No' for each annexure rule options. As per user's selection of annexure rules, the system shall calculate and auto fetch the base rate from the backend database
- iv. The system shall calculate market value based on user's selection and shall display Annexure rules and total valuation amount. The system shall calculate conversion of measurement unit to square meter (Nonagricultural property). The user will confirm and continue with the process.
 - **Annexure Rules Value = Sum of percentage of Rates (as per user selection)**
 - **Total Valuation Amount = Estimated Guidance Rate + Annexure Rule value (as per user selection)**

User Interface (UI)

Agricultural Property

AGRICULTURE RATE DETAILS			
S.No.	Property Type	Rate (₹/ Acres)	Select
01	Dry, No Source of Irrigation, Other	4,00,000.00	☐
02	Wet (Assured Water supply from Government Tanks/Canals, One Crop	5,00,000.00	☐
03	Bagayat, Wet	6,00,000.00	☐

ANNEXURE RULES

S.No.	Yes	No	Annexure Rule	Percentage	Amount (₹)
01	☒	☐	Corner Property	10.00	4,00,000.00
02	☐	☐	Any Two side Roads	10.00	0
03	☒	☐	Industrial Purpose	50.00	6,00,000.00
04	☒	☐	Property Abutting to NH	50.00	4,00,000.00
05	☐	☐	Property Abutting to SH	25.00	0
06	☐	☐	Converted Property for Residential Purpose (Undeveloped) 5 to 10 Guntas	-50.00	0
07	☐	☐	Converted Property for Commercial Purpose (Undeveloped) 5 to 10 Guntas	-50.00	0
08	☐	☐	Converted Property for Industrial Purpose (Undeveloped) 5 to 10 Guntas	-50.00	0
09	☐	☐	Converted Property for Residential Purpose (Undeveloped) more than 10 Guntas	50.00	0
10	☒	☐	Converted Property for Commercial Purpose (Undeveloped) more than 10 Guntas	60.00	5,00,000.00
11	☐	☐	Converted Property for Industrial Purpose (Undeveloped) more than 10 Guntas	25.00	0

Non-Agricultural Property (Vacant Site)

NON-AGRICULTURE RATE DETAILS

S.No.	Property Type	Rate (₹/ Acres)	Select
01	Residential	4,00,000.00	☐
02	Commercial	5,00,000.00	☐
03	Industrial	6,00,000.00	☐

ANNEXURE RULES

S.No.	Yes	No	Annexure Rule	Percentage	Amount (₹)
01	☐	☐	Corner Property	10.00	4,00,000.00
02	☐	☐	Any Two side Roads	10.00	0
03	☐	☐	Industrial Purpose	50.00	6,00,000.00
04	☐	☐	Property Abutting to NH	50.00	4,00,000.00
05	☐	☐	Property Abutting to SH	25.00	0

Non-Agricultural Property (Building)

BUILDING RATE DETAILS

S.No.	Property Type	Rate (₹/ Sq. M)	Select
01	Residential	4,00,000.00	☐
02	Commercial	5,00,000.00	☐
03	Industrial	6,00,000.00	☐

CONSTRUCTION TYPE DETAILS

S.No.	Select	Construction Type	Ground Floor Area (Sq.m)	Above Floor Area (Sq.m)	Amount (₹)
01	☐	RCC Granite flooring, Teak wood			
02	☐	RCC Marble flooring, Teak wood			
03	☐	RCC Mosaic/Vitrified/Ceramic flooring, Teak wood			
04	☐	RCC Mosaic/Polished Kadapa/ShahBad/Betam Jelli flooring, Honne wood, Steel Window			
05	☐	RCC Red Oxide flooring Any Wood or Steel Window			
06	☐	Madras Roofing, Mangalore Tiles, A C Sheet Red Oxide flooring, Jungle Wood, Cement Wall			
07	☐	Madras Roofing, Mangalore Tiles, A C Sheet			
08	☐	Black Tiles, Mud Roofing, Kadapa, Mud Wall, jungle Wood, Hut			

ANNEXURE RULES

S.No.	Yes	No	Annexure Rule	Percentage	Amount (₹)
01	☐	☐	Corner Property	10.00	4,00,000.00
02	☐	☐	Any Two side Roads	10.00	0
03	☐	☐	Industrial Purpose	50.00	6,00,000.00
04	☐	☐	Property Abutting to NH	50.00	4,00,000.00
05	☐	☐	Property Abutting to SH	25.00	0

S.No.	Select	Parking Type	Total Number of Parking
01	☐	Covered Car Parking	
02	☐	Open Car Parking	

Non-Agricultural Property (Flat/Apartment)

FLAT RATE DETAILS

S.No.	Floor	Property Type	Amenities	Rate (₹/ Sq.Metre.)	Select
01	Ground Floor	Commercial	Marble, Granite Vitrified tiles and Other flooring-Commercial	43,420.00	☐
02	Ground Floor	Residential	Marble, Granite Vitrified tiles and Other flooring-Residential	33,400.00	☐
03	Ground Floor	Commercial	Mosaic, Ceramic flooring and Others- Commercial	43,420.00	☐
03	Ground Floor	Residential	Mosaic, Ceramic flooring and Others- Residential	33,400.00	☐

S.No.	Apartment Amenities	Select
01	Club house, Community hall, Conference hall, party hall, Card room, Reading room, library, Banquet hall, party area, party lawn and similar types of amenities.	☐
02	Jogging track, Cycling track, Walking track, Pebble pathway, Reflexology path and similar types of amenities.	☐
03	Children play area, tot cot, children game area, Garden, Water body, Decorative pool Plantation Garden, Barbeque pits, crèche, landscape area, fountain and similar types of amenities.	☐
04	Canteen, Mall, Commercial space, ATM, Bank, Hopcom, Janatha Bazar, Nandini Milk outlet, Provision store, Parlor, Cafeteria, Super market, Plaza and similar types of amenities.	☐
05	All type of outdoor play area, Badminton, Tennis, Basket ball, Base ball, Cricket, Foot ball, Hockey and similar types of amenities.	☐
06	All type of indoor game area, squash, snooker, Table tennis, carom room, Indoor games area and similar types of amenities.	☐
07	Swimming pool indoor, Kids pool, wading pool, aqua gym and similar types of amenities.	☐
08	Cargo lift, elevator, Mechanical lift for car park, High speed elevator and similar types of amenities	☐
09	Surveillance of common area, manned security with video surveillance intelligent security, Motion sensor based lighting multi camera security, CCTV, Gated community, Intercom, Wifi Internet parlor, Video conference facility, Generator, UPS, Kiosk, Visitor Tracking system and similar types of amenities	☐
10	Helipad and Golf field	☐
11	Outdoor Amphitheatre, Open air theatre, Open stage and similar types of amenities	☐
12	Health clinic, Ayurvedic parlor, Massage parlour, Beauty parlour, Spa, Aerobics, Yoga meditation, Unisex parlour, Steam & Sauna Jacuzzi, Gym, Day care center, Health club and similar types of amenities	☐
13	Indoor Amphitheatre, Dance & Karaoke hall, Drama stage, Home theater hall.	☐
14	Home automation, smart home, IP door lock, prepaid power supply, piped cooking gas supply, gas bank, gas detector.	☐
15	Other Special Amenities	☐

PARKING DETAILS

S.No.	Select	Parking Type	Total Number of Parking
01	☐	Covered Car Parking	
02	☐	Open Car Parking	

FLOOR DETAILS


Floor Number

Value

8 FEE CALCULATION

i. Brief Description (Effect of Stamp duty)

No instrument chargeable with duty shall be admitted in evidence for any purpose by any person having by law or consent of the party's authority to receive evidence, or shall be acted upon, registered, or authenticated by any person or by any public officer, unless such instrument is duly stamped.



ii. Functional Step by Step Process

- i. The system shall auto fetch 'stamp duty articles', 'Region' and 'Market value' from the backend as per user details in the system
- ii. Consideration Amount: The user shall enter the consideration amount. Consideration amount is the total amount involved in any purchase/sale transaction agreed between two parties.
- iii. The system shall display government duty to the user
- iv. **Exempted for the duty:**

Case 1:

- a. In case the user selects 'exemption on stamp duty' then the user will be required to select 'duty exempted' in either 'Percentage (%)' or 'Rupees (₹)' and the value in 'Percentage (%)' or 'Rupees (₹)'
- b. The user will be required to upload exemption certificate issued by the competent authority and enter the certificate number, date, exemption description, denotation amount and Number of pages of draft deed documents and annexures
- c. Based on the details entered by the user, the system shall calculate all the duties after deducting the exemption amount and display the total payable amount

Case 2:

- a. In case the user selects Denotation, if he has paid stamp duty in earlier and subsequent instrument is employed for completion of transaction then duty already paid is denoted and the difference of duty will be calculated by the system automatically
- b. In case the user does not select 'exemption on stamp duty' then the user will be required to enter the denotation amount (if any) and Number of pages of draft deed documents and annexures, based on that the system shall calculate all the duties and will display the total payable amount

User Interface (UI)

Stamp Duty Selection	Region Type	Market Value (₹)	Consideration Amount (₹)
Value	Value	Value	Value

Exemption Details

Government Duty	☒ Exemption for this duty	In Percentage	Upload Exemption Certificate
Value		Value	Value Upload
	☒ in Percentage ☐ in ₹	Exemption Description	
		Value	

Denotation of Stamp Duty

Value

Denotation Description

Value



Upload

Number of Pages

Value

Government Duty after Exemption (A)	₹ 50,000.00
Surcharge Value (B)	₹ 1,000.00
Cess Value (C)	₹ 5,000.00
Denotation of Stamp duty (D)	₹ 5,000.00
Total Stamp Duty (E)=(A)+(B)+(C)-(D)	₹ 51,000.00
Total Registration Fees (F)	₹ 10,000.00
Mutation Fees (G)	₹ 350.00
Scanning Fees (H)	₹ 45.00
Total Payable Amount (I)=(E)+(F)+(G)+(H)	₹ 61395.00

Existing SD:

Stamp (Govt) Duty - (variable)
Exemption Duty on SD - (variable)
Govt Duty after Exemption - (variable)
Cess - (variable)
Surcharge - (variable)
Duplicate SD – Rs.500 (fixed)
Denotation of SD - (variable)

Things to be ADDED to SD:

Deficit SD - (variable)
Affidavit SD – Rs.20 (fixed)
Preemption SD – Rs.100 (fixed)
Certified Copy SD – Rs.10 (per copy) (variable)

Existing RF:

Registration Fee (RF) - (variable)
Duplicate RF – Rs.200 (fixed)

Things to be ADDED to RF:

Exemption (Concession) Duty on RF - (variable)
RF after Exemption - (variable)
RF after Set Off – (variable between Rs.100 and Rs.500)
RF u/s 30 (in DR Office) – Rs.2000 (fixed)
Consenting Fee – Rs.100 (fixed)
Map Filing Fee – Rs.100 (fixed)
Memo Fee – Rs.100 (fixed)
Private Attendance Fee – Rs.1000 (fixed)
Delay Condonation Fee – Rs.200 (fixed)
Delay Condonation Fine – (variable)
Holiday RF – Rs.2000 (fixed)
Authentication or Attestation POA Fee – Rs.100 (fixed)

Others:

Mutation Fee – Rs.45 (fixed)
Service Charge (Scanning Fee) - Rs.35 per page

Things to be ADDED to Others:

Appeal Fee – Rs.1000 (fixed)
Document Withdrawal Fee – Rs.200 (fixed)
Will Deposit Fee – Rs.1000 (fixed)
Filing of Translation Fee – Rs.50 (fixed)
Safe Custody Fee– Rs.10 per 15 days (Maximum of Rs.100)
Protest Application Fee – Rs.200 (fixed)

8.1 EXEMPTION of Stamp Duty & Registration Fee

Brief Description

Exemption means Reduction or Remission of Stamp Duty for certain class of documents for the promotion of Industries, and in cases of Land Acquisition, Compensation and such other activities.

Exemption of Stamp Duty and Registration Fee are given under the Provision of Section 9 of Karnataka Stamp Act, 1957 and Section 78 of Registration Act, 1908.

The screenshot displays the Kaveri Online Services web application interface. The browser window shows the URL: <https://xd.adobe.com/view/7a658e7f-1e86-4614-99da-c6aa954fe07f-2f36/screen/2432e426-1549-4149-a089-47d24e3794fb/7fullscr...>. The application header includes the Kaveri Online Services logo, the text "Department of Stamps and Registration, Government of Karnataka", and a user greeting "Hello, Applicant" with a "Logout" button.

The main form is titled "Exemption Details" and contains the following sections:

- Government Duty:** A text input field labeled "Value" and a checkbox labeled "Exemption for this duty".
- Denotation of Stamp Duty:** A text input field labeled "Value", a text input field labeled "Denotation Description", and an "Upload" button.
- Number of Pages:** A text input field labeled "Value".

Below the form is a "Calculate" button. The footer of the application includes links for "Accessibility Statement", "Terms & Conditions", "Website Policies", "Help", "Feedback", "Contact Us", "Web Information Manager", "FAQ", "Sitemap", and "Visitors Analytics". The footer also displays the copyright notice "©2021, Department of Stamps and Registration, Karnataka".

The screenshot also shows the Windows taskbar at the bottom, displaying the date and time as 16:38 on 08-08-2022, and the system tray showing the temperature as 25°C and the weather as Cloudy.

Document nature flow change s... x
Kaveri Online Services x
+

Not secure | csgkaveriwebapp.centralindia.cloudapp.azure.com:9080/#/fee-calculation


Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka
Hello, Karun  [Logout](#)

Home About Department Resources **LINKS** External Links Help

Exemption Details

☐ Exemption for this duty

Denotation

☐ Denotation of Stamp Duty
☐ E-Stamp Fee
☐ Adjudication Fee
Upload Denotation Certificate
No file uploaded yet 

Number of Pages

No. of Duplicate Copies

*Total number of pages is number of pages + 2 = NaN

80°F Raining now

ENG IN 18:39 06-09-2022

Document nature flow change s... x
Kaveri Online Services x
+

Not secure | csgkaveriwebapp.centralindia.cloudapp.azure.com:9080/#/fee-calculation


Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka
Hello, Karun  [Logout](#)

Home About Department Resources **LINKS** External Links Help

Exemption Details

☒ Exemption for this duty

For Stamp duty(₹) ☐ in Percentage ☐ in ₹ Amount in Rupees

For Registration Fees(₹) ☐ in Percentage ☐ in ₹ Amount in Rupees

Upload Exemption Certificate
No file uploaded yet 

Exemption Description

Denotation

☐ Denotation of Stamp Duty
☐ E-Stamp Fee
☐ Adjudication Fee
Upload Denotation Certificate

Number of Pages

No. of Duplicate Copies

*Total number of pages is number of pages + 2 = NaN

80°F Raining now

ENG IN 18:39 06-09-2022

Fields to be Created for Exemption:

1. **Government Duty (GD)**
 - a. **Exemption for GD** - provide a **checkbox**
 - b. If the checkbox is checked, then give the following **radio buttons** - (i) **in Percentage**, (ii) **in Lump sum Amount of SD** and (iii) **in Lump sum Amount of MV**
 - c. For **Each** of the radio button selection, **create the field to manually Enter the Details** (may be Percentage, Lump sum Amount of SD and Lump sum Amount of MV)
2. **Registration Fee (RF)**
 - a. **Exemption for RF** - provide a **checkbox**
 - b. If the checkbox is checked, then give the following **radio buttons** - (i) **in Percentage**, (ii) **in ppm (1:1000)** and (iii) **in Lump sum Amount of RF**
 - c. For **Each** of the radio button selection, **create the field to manually Enter the Details** (may be Percentage, ppm (1:1000) and Lump sum Amount of RF)
3. **Upload Exemption Certificate** - generally SAME Certificate to be uploaded for both Govt Duty (GD) and RF
4. **Exemption Description** - manually enter the exemption description for both Govt Duty (GD) and RF

NOTE: Please refer the Below Mentioned USE CASES for Calculation Purpose (ie., the FORMULAE to be incorporated for each of the following – 1. Govt Duty - (i) in Percentage, (ii) in Lump sum Amount of SD and (iii) in Lump sum Amount of MV and 2. Registration Fee - (i) in Percentage, (ii) in ppm (1:1000) and (iii) in Lump sum Amount of RF

List of Use Cases for Document Registration involving Multiple Properties for the purpose of Exemption of Stamp Duty and Registration Fee:

8.2 Use Case No.1 (Agriculture + Agriculture)

Property 1 = Agriculture

Property 2 = Agriculture

MV, SD & RF Calculation:

1. Calculate MV, SD and RF for BOTH the Properties 1 & 2
2. From the sum total of SD & RF, the Reduction or Remission (ie., Exemption) must be Deducted
3. The Surcharge and Cess are calculated on the Difference of SD & Exemption
4. Total SD to be paid is calculated
5. Total RF to be paid is calculated

8.2.1 Example 1: Agriculture (Bhoomi) & Agriculture (Bhoomi)

	Property 1	Property 2
	Agriculture (Bhoomi)	Agriculture (Bhoomi)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	563 (because 562.5 has to be rounded off to the Next Higher Integer Only (=3% of SD paid After Exemption = 3% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,188 (=18,750+563+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,188 = 21,188	
Case 2: Exemption as Lump sum Amount of SD		
c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	
d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)

e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	450 (=3% of SD paid After Exemption = 3% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,950 (=15,000+450+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,950 = 16,950	
Case 3: Exemption as Lump sum Amount of MV		
c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 =5% of MV11 =5% of 0 = 0	SD22 =5% of MV22 =5% of 1 lakh = 5,000
g''. Surcharge	0 (=3% of SD11 =3% of SD paid After Exemption =3% of 0)	150 (=3% of SD22 =3% of SD paid After Exemption =3% of 5,000)
h''. Cess	0 (=10% of SD11 =10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption =10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,650 (=5,000+150+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,650 = 5,650	
i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
Case 1: Exemption as % of Total RF (say 50%, 100%)		
j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	
Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)		
j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1 per Rs.1,000 of MV = 1/1,000*100 = 0.1% (0.1% on Total MV = MV1 + MV2)	Here, MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000 RF to be paid After Exemption = 15,00,000*1/1,000= 1,500 OR RF to be paid After Exemption = 0.1% of 15,00,000 = 1,500 (SHOULD be Rounded off to the NEXT HIGHER INTEGER ONLY)	

	ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l'. RF to be paid After Exemption (=k'-j')	= 15,000 – 1,500 = 13,500
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j". Exemption on RF	Rs.100 (say)
k". Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l". RF to be paid After Exemption (=k"-j")	= 15,000 – 100 = 14,900
y". Total RF to be paid	RF for Properties 1 & 2 = 14,900

8.3 Use Case No.2 (Non-Agriculture + Non-Agriculture)

Property 1 = Non-Agriculture

Property 2 = Non-Agriculture

MV, SD & RF Calculation:

1. Calculate MV, SD and RF for BOTH the Properties 1 & 2
2. From the sum total of SD & RF, the Reduction or Remission (ie., Exemption) must be Deducted (as in Example 1 and Example 2)

OR From the SD & RF calculated for EACH Property, the Amount of Exemption must be Deducted from the Property which is having HIGHER SD (ie., HIGHER MV); If still, the Exemption Amount of SD exceeds the Higher SD, then Balance must be Deducted from the 2nd Property (as in Example 3 and Example 4)

3. The Surcharge and Cess are calculated on the Difference of SD & Exemption
4. Total SD to be paid is calculated
5. Total RF to be paid is calculated

Normal case – follow Usual Process

8.3.1 Example 1: Non-Agriculture (e-Swathu) & Non-Agriculture (e-Swathu)

	Property 1	Property 2
	Non-Agriculture (e-Swathu)	Non-Agriculture (e-Swathu)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	563 (because 562.5 has to be rounded off to the Next Higher Integer Only (=3% of SD paid After Exemption = 3% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,188 (=18,750+563+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,188 = 21,188	

Case 2: Exemption as Lump sum Amount of SD		
c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	
d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	450 (=3% of SD paid After Exemption = 3% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,950 (=15,000+450+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,950 = 16,950	
Case 3: Exemption as Lump sum Amount of MV		
c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 =5% of MV11 =5% of 0 = 0	SD22 =5% of MV22 =5% of 1 lakh = 5,000
g''. Surcharge	0 (=3% of SD11 =3% of SD paid After Exemption =3% of 0)	150 (=3% of SD22 =3% of SD paid After Exemption =2% of 5,000)
h''. Cess	0 (=10% of SD11 =10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption =10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,650 (=5,000+150+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,650 = 5,650	
i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
Case 1: Exemption as % of Total RF (say 50%, 100%)		
j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	

Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)	
j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1 per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	Here, $MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000$ RF to be paid After Exemption = $15,00,000 \times 1/1,000 = 1,500$ OR RF to be paid After Exemption = 0.1% of $15,00,000 = 1,500$ (SHOULD be Rounded off to the NEXT HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l'. RF to be paid After Exemption (=k'-j')	= $15,000 - 1,500 = 13,500$
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j''. Exemption on RF	Rs.100 (say)
k''. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l''. RF to be paid After Exemption (=k''-j'')	= $15,000 - 100 = 14,900$
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900

8.3.2 Example 2: Non-Agriculture (e-Aasthi) & Non-Agriculture (e-Aasthi)

	Property 1	Property 2
	Non-Agriculture (e-Aasthi)	Non-Agriculture (e-Aasthi)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	375 (=2% of SD paid After Exemption = 2% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,000 (=18,750+375+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,000 = 21,000	
Case 2: Exemption as Lump sum Amount of SD		

c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	
d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	300 (=2% of SD paid After Exemption = 2% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,800 (=15,000+300+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,800 = 16,800	
Case 3: Exemption as Lump sum Amount of MV		
c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 =5% of MV11 =5% of 0 = 0	SD22 =5% of MV22 =5% of 1 lakh = 5,000
g''. Surcharge	0 (=2% of SD11 =2% of SD paid After Exemption =2% of 0)	100 (=2% of SD22 =2% of SD paid After Exemption =2% of 5,000)
h''. Cess	0 (=10% of SD11 =10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption =10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,600 (=5,000+100+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,600 = 5,600	
i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
Case 1: Exemption as % of Total RF (say 50%, 100%)		
j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	
Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1.000)		

j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1 per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	Here, $MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000$ RF to be paid After Exemption = $15,00,000 \times 1/1,000 = 1,500$ OR RF to be paid After Exemption = 0.1% of $15,00,000 = 1,500$ (SHOULD be Rounded off to the NEXT HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l'. RF to be paid After Exemption (=k'-j')	= $15,000 - 1,500 = 13,500$
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j''. Exemption on RF	Rs.100 (say)
k''. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l''. RF to be paid After Exemption (=k''-j'')	= $15,000 - 100 = 14,900$
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900

Special Case – e-Swathu (rural) and e-Aasthi (urban) – Similar to Use Case No.3

8.3.3 Example 3: Non-Agriculture (e-Swathu) & Non-Agriculture (e-Aasthi)

	Property 1	Property 2
	Non-Agriculture (e-Swathu)	Non-Agriculture (e-Aasthi)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	375 (=2% of SD paid After Exemption = 2% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,000 (=18,750+375+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,000 = 21,000	
Case 2: Exemption as Lump sum Amount of SD		
c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	

d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	300 (=2% of SD paid After Exemption = 2% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,800 (=15,000+300+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,800 = 16,800	

Case 3: Exemption as Lump sum Amount of MV

c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 = 5% of MV11 = 5% of 0 = 0	SD22 = 5% of MV22 = 5% of 1 lakh = 5,000
g''. Surcharge	0 (=3% of SD11 = 3% of SD paid After Exemption = 3% of 0)	100 (=2% of SD22 = 2% of SD paid After Exemption = 2% of 5,000)
h''. Cess	0 (=10% of SD11 = 10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption = 10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,600 (=5,000+100+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,600 = 5,600	

i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
--------------------------	--------------------------	-------------------------

Case 1: Exemption as % of Total RF (say 50%, 100%)

j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	

Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)

j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1	Here, MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000 RF to be paid After Exemption = 15,00,000*1/1,000= 1,500	
--	--	--

per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	OR RF to be paid After Exemption = 0.1% of 15,00,000 = 1,500 (SHOULD be Rounded off to the NEXT HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l'. RF to be paid After Exemption (=k'-j')	= 15,000 – 1,500 = 13,500
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j''. Exemption on RF	Rs.100 (say)
k''. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l''. RF to be paid After Exemption (=k''-j'')	= 15,000 – 100 = 14,900
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900

8.3.4 Example 4: Non-Agriculture (e-Aasthi) & Non-Agriculture (e-Swathu)

	Property 1	Property 2
	Non-Agriculture (e-Aasthi)	Non-Agriculture (e- Swathu)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	563 (because 562.5 has to be rounded off to the Next Higher Integer Only (=3% of SD paid After Exemption = 3% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,188 (=18,750+563+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,188 = 21,188	
Case 2: Exemption as Lump sum Amount of SD		
c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	

d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	450 (=3% of SD paid After Exemption = 3% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,950 (=15,000+450+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,950 = 16,950	

Case 3: Exemption as Lump sum Amount of MV

c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 =5% of MV11 =5% of 0 = 0	SD22 =5% of MV22 =5% of 1 lakh = 5,000
g''. Surcharge	0 (=2% of SD11 =2% of SD paid After Exemption =2% of 0)	150 (=3% of SD22 =3% of SD paid After Exemption =3% of 5,000)
h''. Cess	0 (=10% of SD11 =10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption =10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,650 (=5,000+150+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,650 = 5,650	

i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
--------------------------	--------------------------	-------------------------

Case 1: Exemption as % of Total RF (say 50%, 100%)

j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	

Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)

j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1	Here, MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000 RF to be paid After Exemption = 15,00,000*1/1,000= 1,500	
--	--	--

per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	OR RF to be paid After Exemption = 0.1% of 15,00,000 = 1,500 (SHOULD be Rounded off to the HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l'. RF to be paid After Exemption (=k'-j')	= 15,000 – 1,500 = 13,500
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j". Exemption on RF	Rs.100 (say)
k''. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000
l''. RF to be paid After Exemption (=k''-j'')	= 15,000 – 100 = 14,900
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900

8.4 Use Case No.3 (Agriculture + Non-Agriculture)

Property 1 = Agriculture

Property 2 = Non-Agriculture

MV, SD & RF Calculation:

1. Calculate MV, SD and RF for BOTH the Properties 1 & 2
2. From the SD & RF calculated for EACH Property, the Amount of Exemption must be Deducted from the Property which is having HIGHER SD (ie., HIGHER MV)
3. If still, the Exemption Amount of SD exceeds the Higher SD, then Balance must be Deducted from the 2nd Property
4. The Surcharge and Cess are calculated on the Difference of SD & Exemption
5. Total SD to be paid is calculated
6. Total RF to be paid is calculated

8.4.1 Example 1: Agriculture (Bhoomi) & Non-Agriculture (either e-Swathu or e-Aasthi)

	Property 1	Property 2
	Agriculture	Non-Agriculture (Can be either e-Swathu or e-Aasthi) Note: Only change in Surcharge has to be accounted for ie., Surcharge = 3% (e-Swathu) & 2% (e-Aasthi)
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 75% of 75,000 = 56,250	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., 56,250-50,000)
e. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-6,250 = 18,750
f. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	375 (=2% of SD paid After Exemption = 2% of 18,750)
g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,000 (=18,750+375+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,000 = 21,000	
Case 2: Exemption as Lump sum Amount of SD		

c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	
d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=3% of SD paid After Exemption = 3% of 0)	300 (=2% of SD paid After Exemption = 2% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,800 (=15,000+300+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,800 = 16,800	

Case 3: Exemption as Lump sum Amount of MV

c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 = 5% of MV11 = 5% of 0 = 0	SD22 = 5% of MV22 = 5% of 1 lakh = 5,000
g''. Surcharge	0 (=3% of SD11 = 3% of SD paid After Exemption = 3% of 0)	100 (=2% of SD22 = 2% of SD paid After Exemption = 2% of 5,000)
h''. Cess	0 (=10% of SD11 = 10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption = 10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,600 (=5,000+100+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,600 = 5,600	

i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
--------------------------	--------------------------	-------------------------

Case 1: Exemption as % of Total RF (say 50%, 100%)

j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	
k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	

Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)

j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1 per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	Here, $MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000$ RF to be paid After Exemption = $15,00,000 \times 1/1,000 = 1,500$ OR RF to be paid After Exemption = 0.1% of $15,00,000 = 1,500$ (any decimal appearing SHOULD be Rounded off to the Next HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501
k'. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l'. RF to be paid After Exemption (=k'-j')	= $15,000 - 1,500 = 13,500$
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)	
j''. Exemption on RF	Rs.100 (say)
k''. Total RF = RF1 + RF2	= $10,000 + 5,000 = 15,000$
l''. RF to be paid After Exemption (=k''-j'')	= $15,000 - 100 = 14,900$
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900

8.4.2 Example 2: Non-Agriculture (either e-Swathu or e-Aasthi) & Agriculture (Bhoomi)

	Property 1 Non-Agriculture (Can be either e-Swathu or e-Aasthi) Note: Only change in Surcharge has to be accounted for ie., Surcharge = 3% (e-Swathu) & 2% (e-Aasthi)	Property 2 Agriculture
a. MV (Market Valuation)	10 lakh = MV1	5 lakh = MV2
b. SD (Stamp Duty)	50,000 (=5% of MV) = SD1	25,000 (=5% of MV) = SD2
Case 1: Exemption as % of Total SD		
c. Exemption on SD = 75% (say) (ie., 75% on Total SD = SD1 + SD2)	Here, $SD1 + SD2 = 50,000 + 25,000 = 75,000$ Exemption = 75% of $75,000 = 56,250$	
d. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 6,250 (Remaining Exemption on SD ie., $56,250 - 50,000$)
e. SD to be paid After Exemption (=b-d)	= $50,000 - 50,000 = 0$	= $25,000 - 6,250 = 18,750$
f. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	563 (because 562.5 has to be rounded off to the Next Higher Integer Only (=3% of SD paid After Exemption = 3% of 18,750)

g. Cess	0 (=10% of SD paid After Exemption)	1,875 (=10% of SD paid After Exemption = 10% of 18,750)
h. Total SD (=e+f+g)	0 (=0+0+0)	21,188 (=18,750+563+1,875)
x. Total SD to be paid	Total SD for Properties 1 & 2 = 0+21,188 = 21,188	
Case 2: Exemption as Lump sum Amount of SD		
c'. Exemption on SD = 60,000 (say)	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Exemption = 60,000 (say)	
d'. Exemption of Split SD (Refer step 2)	= 50,000 (to make property with Higher SD as less as possible)	= 10,000 (Remaining Exemption on SD ie., 60,000-50,000)
e'. SD to be paid After Exemption (=b-d)	= 50,000-50,000 = 0	= 25,000-10,000 = 15,000
f'. Surcharge	0 (=2% of SD paid After Exemption = 2% of 0)	450 (=3% of SD paid After Exemption = 3% of 15,000)
g'. Cess	0 (=10% of SD paid After Exemption)	1,500 (=10% of SD paid After Exemption = 10% of 15,000)
h'. Total SD (=e'+f'+g')	0 (=0+0+0)	16,950 (=15,000+450+1,500)
x'. Total SD to be paid	Total SD for Properties 1 & 2 = 0+16,950 = 16,950	
Case 3: Exemption as Lump sum Amount of MV		
c''. Exemption on SD = 14 lakh on MV	Here, SD1 + SD2 = 50,000 + 25,000 = 75,000 Here, MV1 + MV2 = 10 lakh + 5 lakh = 15 lakh Exemption = 14 lakh on MV	
d''. Exemption of Split SD on MV (Refer step 2)	= 10 lakh (to make property with Higher SD as less as possible)	= 4 lakh (Remaining Exemption of SD on MV ie., 14 lakh-10 lakh)
e''. SD to be paid After Exemption on MV (=a-d'')	MV11 = 10 lakh – 10 lakh = 0	MV22 = 5 lakh – 4 lakh = 1 lakh
f''. SD to be paid After Exemption	SD11 =5% of MV11 =5% of 0 = 0	SD22 =5% of MV22 =5% of 1 lakh = 5,000
g''. Surcharge	0 (=2% of SD11 =2% of SD paid After Exemption =2% of 0)	150 (=3% of SD22 =3% of SD paid After Exemption =3% of 5,000)
h''. Cess	0 (=10% of SD11 =10% of SD paid After Exemption)	500 (=10% of SD paid After Exemption =10% of 5,000)
i''. Total SD (=f''+g''+h'')	0 (=0+0+0)	5,650 (=5,000+150+500)
x''. Total SD to be paid	Total SD for Properties 1 & 2 = 0+5,650 = 5,650	
i. RF (Registration Fee)	10,000 (=1% of MV) = RF1	5,000 (=1% of MV) = RF2
Case 1: Exemption as % of Total RF (say 50%, 100%)		
j. Exemption on RF = 75% (say) (ie., 75% on Total RF = RF1 + RF2)	Here, RF1 + RF2 = 10,000 + 5,000 = 15,000 Exemption = 75% of 15,000 = 11,250	

k. Exemption of Split RF (Refer step 2)	= 10,000 (to make property with Higher RF as less as possible)	= 1,250 (Remaining Exemption on RF ie., 11,250-10,000)
l. RF to be paid After Exemption (=i-k)	= 10,000-10,000 = 0	= 5,000-1,250 = 3,750
y. Total RF to be paid	RF for Properties 1 & 2 = 0+3,750 = 3,750	
Case 2: Exemption as 1:1000 (ie., Rs.1 per Rs.1,000)		
j'. Exemption on RF = 1 per 1,000 (of MV) = means Rs.1 per Rs.1,000 of MV = $1/1,000 \times 100 = 0.1\%$ (0.1% on Total MV = MV1 + MV2)	Here, MV1 + MV2 = 10,00,000 + 5,00,000 = 15,00,000 RF to be paid After Exemption = $15,00,000 \times 1/1,000 = 1,500$ OR RF to be paid After Exemption = 0.1% of 15,00,000 = 1,500 (SHOULD be Rounded off to the HIGHER INTEGER ONLY) ie., Example: 1,500.8 should be taken as 1,501 1,500.2 should be taken as 1,501	
k'. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000	
l'. RF to be paid After Exemption (=k'-j')	= 15,000 – 1,500 = 13,500	
y'. Total RF to be paid	RF for Properties 1 & 2 = 13,500	
Case 3: Exemption as Lump sum Amount of RF (say Rs.100)		
j''. Exemption on RF	Rs.100 (say)	
k''. Total RF = RF1 + RF2	= 10,000 + 5,000 = 15,000	
l''. RF to be paid After Exemption (=k''-j'')	= 15,000 – 100 = 14,900	
y''. Total RF to be paid	RF for Properties 1 & 2 = 14,900	

The Table for Exemption (Concession) for Stamp Duty (SD):

ಅನುಬಂಧ

ಸರ್ಕಾರಿ ಅಧಿಸೂಚನೆ ಸಂಖ್ಯೆ ಕಂಇ 144 ಮುನೋಮು 2003, ದಿನಾಂಕ 23-4-2003

ಇದಕ್ಕೆ ಅನುಬಂಧ

Serial No.	ಸರ್ಕಾರಿ ಆದೇಶ ಸಂಖ್ಯೆ	ವಿಷಯ	ವಿನಾಯಿತಿ
1.	RD 33 GST 62, dated 15/16th February, 1969	Letter which a person depositing money in District Savings Bank as a security to Government or a Local Authority, for the due execution of an office as required by the rules of the Savings Bank is required to address the Secretary of the District Savings Bank, agreeing to special conditions to the application and withdrawal of the money	Full
2.	RD 33 GST 62, dated 15/16th February, 1969	Transfer deeds executed in respect of Defence Deposit Certificate and Treasury Savings Deposit Certificates	Full
3.	RD 33 GST 62, dated 15/16th February, 1969	Gifts, settlements, trust or transfer of Full property executed in favour of State Government	Full
4.	RD 186 EST 77, dated 5/12-1-1978	Affidavits required to be filed in response to the notices issued by any commission of enquiry appointed by the Central Government or the State Government under the Commission of Inquiry Act, 1952	Full
5.	RD EST 70, dated 3rd February, 1973	Sale deeds the Central Government obtains either from the State Government or from others	Full
6.	RD 33 GST 62, dated 15/16th February, 1969	Mortgage deeds, agreement and surety bonds executed by the State or Central Government in respect of the following advances granted to them by the State or Central Government; Motor-car, Motor-cycle and Bicycle purchase advance	Full
7.	RD 33 GST 62, dated 15/16th February, 1969	Reconveyance executed on behalf of Government in respect of property executed by an officer of Government or his surety for due execution of an office or due accounting of money or other property received by virtue thereof	Full
8.	RD 319 ESR 90, dated 30-9-1992	Mortgage deeds executed in favour of President of India by the Central Government Employees in respect of house building, cent house purchase or house repair advance, granted by the Central Government in the State of Karnataka	Reduced by Fifty per Cent
9.	RD 612 MUNOMU 98, dated 16-12-1998	Mortgage deeds, agreement and surety bonds, executed by State Government Employees (including officers borne of All India Services) or their spouses in favour of State Government in respect of house building, house purchase or house repair advance, obtained by such Government Employees will be borne by the State Government.	Full

10.	RD 21 EST 72, dated 3-3-1972	Instruments executed in connection with loans granted by the Karnataka Housing Board under the Village (Rural) Housing Project Scheme.	Full
11.	RD 24 EST 72, dated 29-3-1972	Instruments executed by the Karnataka Full Housing Board in respect of subsidized industrial /subsidized rental housing/slum clearance/Rental Housing Schemes for Government employees	Full
12.	RD 130 EST 73, dated 19-2-1974	Mortgage deeds executed by the beneficiaries to draw loan from the Government under the Peoples Housing Scheme	Full
13.	RD 126 ESR 83, dated 8-1-1990	Mortgage deeds executed by the beneficiaries to draw loans from the Government/Municipalities/City Corporations under the The low cost houses and improvement of houses in urban areas for economically weaker sections (Bhagyamandira Scheme)	Full
14.	RD 55 EAM 86, dated 25-4-1994 read with G.O. No. RD 130 EST 74	Mortgage deeds executed by the beneficiaries to draw loan from the Government or Taluk Development Board (TDB), Block Development Officer (BDO), Chief Executive Officer (CEO) and Taluk Panchayats/Zilla 19-2-1974 Parishads under the Peoples Housing Scheme or any other allied schemes	Full
15.	RD 37 ESR 94, dated 25-2-1994	ಆಶ್ರಯ ಯೋಜನೆ ಹಾಗೂ ಡಾ ಬಿ.ಆರ್. ಅಂಬೇಡ್ಕರ್ ಜನ್ಮಶತಾಬ್ದಿ ಕಾರ್ಯಕ್ರಮಗಳಡಿ ಕೈಗೊಳ್ಳುವ ವಸತಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮನೆಗಳ ದಾಖಲಾವೇಜುಗಳು	Full
16.	RD 190 MUNOMU 2001, 28-5-2001	Mortgage deeds executed by the beneficiaries in favour of Rajiv Gandhi Housing Corporation programme for the economically weaker sections and special occupational categories both in rural and urban areas, except in Indira Aavaj Yojana for the purpose of providing residential facilities with capital investment by the State Government and also for instruments executed by Rajiv Gandhi Housing Corporation in favour of Urban Development Corporation for obtaining loans for the said purpose	Full
17.	RD 33 GST 62, dated 15/16th February, 1969	Instrument of Gifts executed in favour of Taluk Development Boards and Village Panchayats	Full
18.	RD 33 GST 62, dated 15/16th February, 1969	Bonds executed by a Village Panchayat in favour of Government for execution of works sponsored under National Extension Service and Community Development Programme	Duty reduced to rupee one and paise fifty
19.	RD 33 GST 62, dated 15/16th February, 1969	Bonds executed by all Municipalities in the State in favour of Government except those executed under the Housing Schemes	Full Exemption
20.	RD 229 EST 89, dated 2-9-1982	Instruments of Gifts of Land, Buildings and other moveable and immoveable properties executed by private individuals in favour of local bodies or Government Department for	Full Exemption

		public purpose	
21.	RD 153 EST 77, dated 18-8-1977	Affidavits sworn to or declarations made by persons belonging to Scheduled Castes and Scheduled Tribes in connection with applications made for award of scholarship, admission to educational institutions, grant of caste certificates or for purpose of employment	Full Exemption
22.	RD 142 EST 75, dated 23-3-1978	Documents executed for the loans upto Rs. 10,000 sanctioned to individuals by Scheduled Castes and Scheduled Tribes Development Corporation Limited and upto Rs. 50,000 sanctioned by the same Development Corporation Limited to the registered bodies, societies and organizations which are registered under law and whose accounts are subject to annual audit	Full
23.	RD 79 ESR 82, dated 15-12-1982	Instruments to be executed by the small and marginal farmers and farmers belonging to Scheduled Castes and Scheduled Tribes for obtaining loans from the department of sericulture under the Dutch Assistance/Credit Programme for construction of industrial sheds/ development of industrial flats	Full
24.	RD 12 EST 83, dated 16-6-1983	Declarations/Affidavits required to be made or sworn to by the small borrowers viz., small or marginal farmers agricultural labourers or Scheduled Castes and Scheduled Tribes, Backward Tribes and families whose annual income does not exceed Rs. 2,400 for the purpose of the Oaths Act, 1969 (Central Act 44 of 1966) in connection with sanction of advances or loans to them	Full
25.	RD 271 EST 81, dated 11-1-1985	Instruments of conveyance executed by or on Duty on the behalf of the Municipal Council, Constituted value set under the Karnataka Municipalities Act, 1964 in respect of sites allotted to the Scheduled Castes and Scheduled Tribes and economically Backward Classes, as specified by the Government from time to time, to the duty payable on the amount or value of property consideration for such conveyance as set forth in the instrument	Duty on the value set forth in the instrument but not on the market value of the Property
26.	RD 47 ESR 91, dated 1-1-1994	ಪರಿಶಿಷ್ಟ ಜಾತಿ ಮತ್ತು ಪರಿಶಿಷ್ಟ ವರ್ಗಗಳ ಅಭಿವೃದ್ಧಿ ನಿಗಮ ನಿಯಮಿತದ ಹಣಕಾಸು ನೆರವು ಮೂಲಕ ಭೂಒಡೆತನ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಪರಿಶಿಷ್ಟ ಜಾತಿ, ಪರಿಶಿಷ್ಟ ಪಂಗಡ ಮತ್ತು ದೇವದಾಸಿ ಫಲಾನುಭವಿಗಳು ಭೂಮಿ ಖರೀದಿಸುವ ಸಂಬಂಧದಲ್ಲಿ ಸಾರ್ವಜನಿಕರು ಫಲಾನುಭವಿಗಳಿಗೆ ಬರೆದುಕೊಡುವ ಕ್ರಯ ಪತ್ರಗಳಿಗೆ ಮತ್ತು ಸದರಿ ಫಲಾನುಭವಿಗಳು ಕರ್ನಾಟಕ ಪರಿಶಿಷ್ಟ ಜಾತಿ ಮತ್ತು ಪರಿಶಿಷ್ಟ ವರ್ಗಗಳ ಅಭಿವೃದ್ಧಿ ನಿಗಮ ನಿಯಮಿತಕ್ಕೆ ಬರೆದುಕೊಡುವ ದಾಸ್ತಾವೇಜುಗಳಿಗೆ (ಅಡಮಾನ ಪತ್ರಗಳು)	Full
27.	ಕಂಇ 523 ಮುನೋಮು 98, ದಿನಾಂಕ 23-4-1999	ಕರ್ನಾಟಕ ರಾಜ್ಯ ಪರಿಶಿಷ್ಟ ಜಾತಿ ಮತ್ತು ಪರಿಶಿಷ್ಟ ವರ್ಗಗಳ ಅಭಿವೃದ್ಧಿ ನಿಗಮದಿಂದ ನೀಡುವ ನೇರ ಯೋಜನೆಗಳಿಗೆ ಬರೆದು ಕೊಡುವ ದಾಸ್ತಾವೇಜುಗಳಿಗೆ	Fifty per cent
28.	RD 457	ಕೃಷ್ಣಾ ಮೇಲ್ಕಂಡ ಯೋಜನೆಯಿಂದಾಗಿ ಮುಳುಗಡೆಯಾದ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ಕಳೆದುಕೊಂಡ ಸಂತ್ರಸ್ತ ಕುಟುಂಬದವರಿಗೆ ದೊರೆಯಬಹುದಾದ ಪರಿಹಾರಧನ ಮತ್ತು ಸಹಾಯಧನದ	Full

	MUNOMU 96, dated 7-2-1997, 2-11-1999 and RD 197 MUNOMU 2001, dated 9-10-2001	ಮೊತ್ತದಲ್ಲಿ ಖರೀದಿಸುವ ಸ್ಥಿರಾಸ್ತಿಗಳಿಗೆ ಪುನರ್ವಸತಿ ಅಧಿಕಾರಿಗಳು ನೀಡಿರುವ ಪ್ರಮಾಣ ಪತ್ರದ ಆಧಾರದ ಮೇಲೆ ನೋಂದಣಿ ಮಾಡಿಸುವಾಗ ಬರೆದುಕೊಡುವ ಪತ್ರಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮಾತ್ರ ತಗಲುವ ಮುದ್ರಾಂಕ ಶುಲ್ಕ ವಿನಾಯಿತಿ ನೀಡಲಾಗಿದೆ.	
		ಪರಂತು, ವಿನಾಯಿತಿ ಪರಿಹಾರಧನ ಮತ್ತು ಸಹಾಯಧನವನ್ನು ಸ್ವೀಕರಿಸಿದ ದಿನಾಂಕದಿಂದ 4 ವರ್ಷದ ಅವಧಿಗೆ ಮಾತ್ರ ಅನ್ವಯಿಸತಕ್ಕದ್ದು.	
29.	RD 457 MUNOMU 1996, dated 17-4-1998	ಕೃಷ್ಣಾ ಮೇಲ್ವಂಡೆ ಯೋಜನೆಯಿಂದಾಗಿ ಮುಳುಗಡೆಯಾದ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ಕಳೆದುಕೊಂಡ ಸಂತ್ರಸ್ತ ಕುಟುಂಬದವರಿಗೆ ಬಾಗಲಕೋಟೆ ನಗರಾಭಿವೃದ್ಧಿ. (ನಿವೇಶನ ಹಂಚಿಕೆ) ನಿಯಮಾವಳಿಗಳು, 1993ರಡಿಯಲ್ಲಿ ಬಾಗಲಕೋಟೆ ಹೊಸನಗರದಲ್ಲಿ 8 x 9: = 72 ಚದರ ಮೀಟರ್ ಅಳತೆಯ ಉಚಿತ ನಿವೇಶನಗಳನ್ನು ಹಂಚಿಕೆ ಮಾಡುವ ಸಂಬಂಧದಲ್ಲಿ ಯೋಜನಾಧಿತ ಕುಟುಂಬದವರಿಗೆ ನಿವೇಶನ ನೋಂದಣಿಗಾಗಿ ತಗಲುವ ಮುದ್ರಾಂಕ ಶುಲ್ಕದಿಂದ ವಿನಾಯಿತಿ ನೀಡಲಾಗಿದೆ	Full
30.	RD 246 MUNOMU 1998(SA), dated 29-12-1998	ನೌಕನೆಲೆ ಯೋಜನೆಯಿಂದ ಮುಳುಗಡೆಯಾದ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ಕಳೆದುಕೊಂಡ ಸಂತ್ರಸ್ತ ಕುಟುಂಬದವರಿಗೆ ದೊರೆಯಬಹುದಾದ ಪರಿಹಾರ ಧನದ ಮೇರೆಗೆ ಸೀಮಿತಗೊಂಡಂತೆ ಸಿದ್ಧಾಸ್ತಿಗಳನ್ನು ನೋಂದಣಿ ಮಾಡಿಸುವಾಗ ತಗಲುವ ಮುದ್ರಾಂಕ ಶುಲ್ಕದ ಶೇಕಡಾ 50ರಷ್ಟು ವಿನಾಯಿತಿ ನೀಡಲಾಗಿದೆ.	Fifty per Cent
31.	RD 38 EST 76, dated 30-3-1976	Affidavits when made for the immediate purpose of being filled before a Tribunal constituted under Section 48 of the Karnataka Land Reforms Act, 1961	Full
32.	RD 640MUNOMU 1997, dated 6-6-1998	ಭಾಗ್ಯಜ್ಯೋತಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳು ಕರ್ನಾಟಕ ವಿದ್ಯುಚ್ಛಕ್ತಿ ಮಂಡಳಿಗೆ ಬರೆದುಕೊಡುವ ಕರಾರು ಪತ್ರಕ್ಕೆ ಮುದ್ರಾಂಕ ಶುಲ್ಕ ವಿನಾಯಿತಿ ನೀಡಲಾಗಿದೆ.	Full

Note:

'Others' option must be provided in the dropdown menu

The applicant shall manually enter the data in the below mentioned format:

ಸರಕಾರಿ ಆದೇಶ ಸಂಖ್ಯೆ:	RD 640 MUNOMU 1997, dated 6-6-1998
ವಿಷಯ:	ಭಾಗ್ಯಜ್ಯೋತಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳು ಕರ್ನಾಟಕ ವಿದ್ಯುಚ್ಛಕ್ತಿ ಮಂಡಳಿಗೆ ಬರೆದುಕೊಡುವ ಕರಾರು ಪತ್ರಕ್ಕೆ ಮುದ್ರಾಂಕ ಶುಲ್ಕ ವಿನಾಯಿತಿ ನೀಡಲಾಗಿದೆ.
ವಿನಾಯಿತಿ:	Full

The Table for Exemption (Concession) for **Registration Fee (RF)**:

ಅನುಬಂಧ

ಸರ್ಕಾರಿ ಅಧಿಸೂಚನೆ ಸಂಖ್ಯೆ ಕಂ 144 ಮುನೋಮು 2003, ದಿನಾಂಕ 23-4-2003

ಇದಕ್ಕೆ ಅನುಬಂಧ

Serial No.	ಸರ್ಕಾರಿ ಆದೇಶ ಸಂಖ್ಯೆ	ವಿಷಯ	ವಿನಾಯಿತಿ
1.	RD 403 ESR 85, Dated 27-5-1986	Instrument of gift, settlement, trust or any transfer of property executed in favour of the State Government	Full Exemption
2.	RD 403 ESR 85, Dated 27-5-1986	Instruments relating to transfer property otherwise than public auction, under the Displaced Persons (Compensation and Rehabilitation) Rules, 1955	Full Exemption
3.	RD 403 ESR 85, Dated 27-5-1986	For registration of documents to be executed by the schools in respect of scholarships, study leave concession, fellow ships, and deputation, concessions granted to them by the Government under any of the technical aid programme	Full Exemption
4.	RD 403 ESR 85, Dated 27-5-1986	Certificate of transfer granted by the Tahsildar under the Tenacy law	Full Exemption
5.	RD 403 ESR 85, Dated 27-5-1986	Instruments executed in respect of transfer of immovable property belonging to foreign machine in India in favour of Indian machines	Full Exemption
6.	RD 403 ESR 85, Dated 27-5-1986	Instruments executed in favour of Karnataka Housing Board by persons Exemption granted loans under the Village Housing Project Scheme	Full Exemption
7.	RD 403 ESR 85, Dated 27-5-1986	Instruments executed by victims of all criminal riots for purpose of drawing interest free loans sanctioned by Government	Full Exemption
8.	RD 105 EST 73, Dated 31-12-1973	Instruments executed by Educational Full Institutions in Karnataka State to draw loan from Government of Karnataka	Full Exemption
9.	RD 403 ESR 85, Dated 27-5-1986	Agreement to be executed by Karnataka Khadi and Village Industries Board in favour of Khadi and Village Industries Commission	Full Exemption
10.	RD 142 EST 75, Dated 23-3-1978	Documents executed for the loans upto Full Rs. 10,000 sanctioned to individuals by Scheduled Castes and Scheduled Tribes Development Corporation Limited and upto Rs. 50,000 sanctioned by the same Development Corporation Limited to the registered bodies, societies and organisations which are registered under law and whose accounts are subject to annual audit.	Full Exemption
11.	RD 79 ESR 82, Dated 15-12-1982	Instruments to be executed by the small and marginal farmers and farmers belonging to Scheduled Castes and Scheduled Tribes for obtaining loans from the department of sericulture under the	Full Exemption

		Dutch Assistance/Credit Programme for construction of industrial sheds/development of industrial flats	
12.	RD 47 ESR 91, Dated: 1-1-1994	ಪರಿಶಿಷ್ಟ ಜಾತಿ ಮತ್ತು ಪರಿಶಿಷ್ಟ ವರ್ಗಗಳ ಅಭಿವೃದ್ಧಿ ನಿಗಮ ನಿಯಮಿತದ ಹಣಕಾಸು ನೆರವು ಮೂಲಕ ಭೂ ಒಡೆತನ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಪರಿಶಿಷ್ಟ ಜಾತಿ, ಪರಿಶಿಷ್ಟ ಪಂಗಡ ಮತ್ತು ದೇವದಾಸಿ ಫಲಾನುಭವಿಗಳು ಭೂಮಿ ಖರೀದಿಸುವ ಸಂಬಂಧದಲ್ಲಿ ಸಾರ್ವಜನಿಕರು ಫಲಾನುಭವಿಗಳಿಗೆ ಬರೆದುಕೊಡುವ ಕ್ರಯ ಪತ್ರಗಳಿಗೆ ಮತ್ತು ಸದರಿ ಫಲಾನುಭವಿಗಳು ಕರ್ನಾಟಕ ಪರಿಶಿಷ್ಟ ಜಾತಿ ಮತ್ತು ಪರಿಶಿಷ್ಟ ವರ್ಗಗಳ ಅಭಿವೃದ್ಧಿ ನಿಗಮ ನಿಯಮಿತಕ್ಕೆ ಬರೆದುಕೊಡುವ ದಾಸ್ತಾವೇಜುಗಳಿಗೆ (ಅಡಮಾನ ಪತ್ರಗಳು)	Full Exemption
13.	RD 457 MUNOMU 96, Dated 7-2-1997	ಕೃಷ್ಣಾ ಮೇಲ್ದಂಡೆ ಯೋಜನೆಯಿಂದಾಗಿ ಮುಳುಗಡೆಯಾದ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ಕಳೆದುಕೊಂಡ ಸಂತ್ರಸ್ತ ಕುಟುಂಬದವರಿಗೆ ದೊರೆಯಬಹುದಾದ ಪರಿಹಾರ ಧನದ ಮಿತಿಗೆ ಸೀಮಿತಗೊಂಡಂತೆ ಖರೀದಿಸುವ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ನೋಂದಣಿ ಮಾಡಿಸುವಾಗ ಬರೆದುಕೊಡುವ ಪತ್ರಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮಾತ್ರ ತಗಲುವ ನೋಂದಣಿ ಶುಲ್ಕ:	Full Exemption
14.	RD 457 MUNOMU 1996, Dated 17-4-1998	ಕೃಷ್ಣಾ ಮೇಲ್ದಂಡೆ ಯೋಜನೆಯಿಂದಾಗಿ ಮುಳುಗಡೆಯಾದ ಸ್ಥಿರಾಸ್ತಿಗಳನ್ನು ಕಳೆದುಕೊಂಡ ಸಂತ್ರಸ್ತ ಕುಟುಂಬದವರಿಗೆ ಬಾಗಲಕೋಟೆ ನಗರಾಭಿವೃದ್ಧಿ (ನಿವೇಶನ ಹಂಚಿಕೆ) ನಿಯಮಾವಳಿಗಳು, 1993ರಡಿಯಲ್ಲಿ ಬಾಗಲಕೋಟೆ-ಹೊಸ ನಗರದಲ್ಲಿ 89 = 72 ಚದರ ಮೀಟರ್ ಅಳತೆಯ ಉಚಿತ ನಿವೇಶನಗಳನ್ನು ಹಂಚಿಕೆ ಮಾಡುವ ಸಂಬಂಧದಲ್ಲಿ ಯೋಜನಾಬಾಧಿತ ಕುಟುಂಬದವರಿಗೆ ನಿವೇಶನ ಬರೆದುಕೊಡುವ ದಾಸ್ತಾವೇಜುಗಳು	Full Exemption
15.	RD 190 MUNOMU 2001, Dated 24-5-2001	ರಾಜೀವ್ ಗಾಂಧಿ ಗ್ರಾಮೀಣ ವಸತಿ ನಿಗಮ ನಿಯಮಿತದ ಮೂಲಕ ಅನುಷ್ಠಾನಗೊಳಿಸುವ ವಸತಿ ಯೋಜನೆಗಳಾದ ಆಶ್ರಯ ಯೋಜನೆ, ಡಾ. ಬಿ.ಆರ್.ಅಂಬೇಡ್ಕರ್, ಯೋಜನೆ ಮತ್ತು ಕರ್ನಾಟಕ ಸರ್ಕಾರ ಹಾಗೂ ಭಾರತ ಸರ್ಕಾರದ ಕೇಂದ್ರ ವಲಯ/ ಪುರಸ್ಕೃತ ವಸತಿ ಯೋಜನೆಗಳಡಿಯಲ್ಲಿ ರೂಪಿಸಿದ ಕಾರ್ಯಕ್ರಮಗಳ ಅಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮನೆಗಳ ದಾಸ್ತಾವೇಜುಗಳ ನೋಂದಣಿ	Full Exemption
16.	RD 319 ESR 90, Dated 30-9-1992	Mortgage deeds executed in favour of President of India by the Central Government Employees in respect of house building, house purchase or house repair advance, granted by the Central Government in the State of Karnataka	Half the registration fee payable in respect of such instrument
17.	RD 612 MUNOMU 98, Dated 15-12-1998	Mortgage deeds, agreement and surety bonds, executed by State Government Employees (including officers borne of All India Services) or their spouses in of house building, house purchase and house repair advance, obtained by such Government employees	Rs. 100.00 is payable in respect of such Instrument
18.	RD EST 73, Dated 9-5-1974	Instruments for the purchase of sites to Full execute subsidies industrial housing/ subsidies rental housing/slum clearance/rental housing scheme for Government employees by the Karnataka Housing Board	Full Exemption
19.	RD 130 EST 73, Dated 19-2-1974 read with	Mortgage deed executed by the beneficiaries to draw loan from the Government under the Peoples	Full Exemption

	RD 328 EST 79, Dated 11-1-1980	Housing Scheme and the HUDCO assisted People Housing Scheme	
20.	RD 126 ESR 83, Dated 8-1-1990	Mortgage deeds executed by the Full beneficiaries to draw loans from the Government/ Municipalities/City Corporations under the "The Low Cost Houses and Improvement of Houses in urban areas for economically weaker sections" (Bhagyamandira Scheme)	Full Exemption
21.	RD 37 ESR 94, Dated 25-2-1974	ಆಶ್ರಯ ಯೋಜನೆ ಹಾಗೂ ಡಾ. ಬಿ.ಆರ್. ಅಂಬೇಡ್ಕರ್, ಜನ್ಮಶತಾಬ್ದಿ ಕಾರ್ಯಕ್ರಮಗಳಡಿ ಕೈಗೊಳ್ಳುವ ವಸತಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮನೆಗಳ ದಾಸ್ತಾವೇಜುಗಳು	Full Exemption

Note:

'Others' option must be provided in the dropdown menu

The applicant shall manually enter the data in the below mentioned format:

ಸರಕಾರಿ ಆದೇಶ ಸಂಖ್ಯೆ:	RD 37 ESR 94, Dated 25-2-1974
ವಿಷಯ:	ಆಶ್ರಯ ಯೋಜನೆ ಹಾಗೂ ಡಾ. ಬಿ.ಆರ್. ಅಂಬೇಡ್ಕರ್, ಜನ್ಮಶತಾಬ್ದಿ ಕಾರ್ಯಕ್ರಮಗಳಡಿ ಕೈಗೊಳ್ಳುವ ವಸತಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಫಲಾನುಭವಿಗಳಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ ಮನೆಗಳ ದಾಸ್ತಾವೇಜುಗಳು
ವಿನಾಯಿತಿ:	Full Exemption

The Table for Exemption (Concession) for **Search of EC:**

Exemption on Search Fee for EC

22.	RD 180 EST 79, Dated 15-2-1979	Encumbrance Certificate required by Public Officer- (a) In respect of property offered as security by public servant for due performance office duties (b) To test property qualification required by an extra departmental post master whether at the time office appointment or subsequently	Rs. 6.00 Rs. 6.00 (to be paid)
23.	RD 180 EST 79, Dated 15-2-1979	In respect of encumbrance required for drawing loan granted under the Village Housing Project Scheme	Full Exemption
24.	RD 7 ERG 65, Dated 5-6-1956	Encumbrance certificate required by Revenue Officer in connection with grant of loans for relief of inhabitation of areas affected by floods, storms, heavy rains and other natural calamities	Full Exemption

The Table for Exemption (Concession) for **Search of CC:**

Exemption on Search Fee for CC

Serial No.	ಸರಕಾರಿ ಆದೇಶ ಸಂಖ್ಯೆ	ವಿಷಯ	ವಿನಾಯಿತಿ
1.	Proviso 1	(1) any instrument, executed by, or on behalf of, or in favour of, the [State Government] in cases where, but for this exemption, the [State Government] would be liable to pay the duty chargeable in respect of such instrument;	Full Exemption
2.	Proviso 2	(2) any instrument for sale, transfer or other disposition, either absolutely or by way of mortgage or otherwise, of any ship or vessel, or any part, interest, share or property of or in any ship or vessel registered under [the Merchant Shipping Act, 1958].	Full Exemption

8.5 DENOTATION of Stamp Duty

Brief Description

Denotation means Reduction or Remission of Stamp Duty for certain class of documents for the promotion of Industries, and in cases of Land Acquisition, Compensation and such other activities.

Exemption of Stamp Duty and Registration Fee are given under the Provision of Section 9 of Karnataka Stamp Act, 1957 and Section 78 of Registration Act, 1908.

CHANGE IT ??

The screenshot shows a web browser window with the URL `cskaveriwebapp.centralindia.cloudapp.azure.com:9080/#/fee-calculation`. The page is titled "Kaveri Online Services" and is part of the "Department of Stamps and Registration, Government of Karnataka". The user is logged in as "Hello, Karun".

The main content area is divided into two columns. The left column is titled "Denotation" and contains three checkboxes: "Denotation of Stamp Duty", "E-Stamp Fee", and "Adjudication Fee". Below these is an "Upload Denotation Certificate" section with a "No file uploaded yet" message and a file upload icon. The right column is titled "Number of Pages" and contains a text input field. To the right of this field is a "No. of Duplicate Copies" section with another text input field. Below the "Number of Pages" input field, there is a note: "*Total number of pages is number of pages + 2 = NaN".

At the bottom of the page, there is a footer with links for "Accessibility Statement", "Terms & Conditions", "Website Policies", "Help", "Feedback", "Contact Us", "Web Information Manager", "FAQ", "Sitemap", and "Visitors Analytics". The copyright notice is "©2021, Department of Stamps and Registration, Karnataka".

The Windows taskbar at the bottom shows the date and time as "18:40 06-09-2022" and the weather as "80°F Raining now".

Document nature flow change s... x Kaveri Online Services x +

Not secure | csgkaveriwebapp.centralindia.cloudapp.azure.com:9080/#/fee-calculation

Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka

Hello, Karun [Logout](#)

Home About Department Resources Links External Links Help

No file uploaded yet

Denotation

☒ Denotation of Stamp Duty

Final Registration Number:

Amount:

☒ E-Stamp Fee

E-Stamp Number:

Amount:

☒ Adjudication Fee

DR Reference Number:

Amount:

Upload Denotation Certificate

No file uploaded yet

Total Amount:

Number of Pages

No. of Duplicate Copies:

*Total number of pages is number of pages + 2 = NaN

80°F Raining now

Windows Taskbar: ENG IN 18:40 06-09-2022

Explain in detail – HW (at home)

The user will select Article and Sub article for Stamp Duty calculation as per below table:

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
6	Memorandum of deposit of title deeds	6 (1-i) - The pawn or pledge of immovable property, Loan or Debt amount does not exceed rupees 10 lakhs		0.10%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	0.1% * Consideration (Multiple of 25000) with Max 25000
		6 (1-ii) - The pawn or pledge of immovable property, Loan or Debt amount exceeds rupees 10 lakhs		0.20%	Max 1000000	(Rate * Consideration) Max 1000000	0	0	Government Duty + Surcharge Value + Cess Value	0.1% * Consideration Max 25000
3	Adoption Deed		500			500	0	0	500	200
4	Affidavit		20			20	0	0	20	0
5	Agreement	5(d) Lease cum sale agreement with BDA, KHB and other Development Authorities		5%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	1% * Consideration
		5(e) (i) Agreement of Sale of Immovable Property (Possession given/agree to be given)		5%		Rate * Highest (Market Value, Consideration Value)	If urban property 2% on Stamp Duty If Rural Property 3% Stamp Duty	10% on Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		5(e) (ii) Agreement of Sale of Immovable Property (Possession not given)		0.10%	Max 20000 on Consideration	Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	200
		5(f) Joint Development Agreement		2%		Rate * Value of the Higher share of the Property	0	0	Government Duty + Surcharge Value + Cess Value	1% * Value of the Higher share
		5(g) (i) Agreement of sale of Movable property (Possession delivered/agreed to be given)		3%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	Max 200
10	Articles of Association of a company			0.10%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	1% * Consideration
11	Award	(a) If the property, which is the subject matter of award, is immovable property		5.00%		Rate * Award Amount	0	0	Government Duty + Surcharge Value + Cess Value	1% * Award Amount

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
14	Cancellation Deed	14 (a) Any instrument previously executed on which stamp duty has been paid	Same Duty as on the original instrument (Latest Transaction Data will be fetched from the Database)			Same Duty as on the original instrument	0	0	Government Duty + Surcharge Value + Cess Value	200
		14 (b) - any instrument executed by or on behalf of the central government or a local authority or other authority	100			100	0	0	100	200
		14 (c) In any other case	100			100	0	0	100	200
		14(d) Cancellation of Sale Deed		5%		Rate * Market Value	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * market value
15	Certificate of Sale	15 (a) Purchase money does not exceed Rs. 10	1			1	0	0	1	200
		15 (b) Purchase money exceed Rs. 10 but does not exceed Rs 25	1.5			1.5	0	0	1.5	200
		15 (C) In any other case		5%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	1% * Consideration
54	Declaration of Trust - With Property	54 (i) Trust is made exclusively for public religious and charitable purpose	1000			1000	0	0	1000	200
		54 (ii) Trust is made for the management and custody of properties	1000			1000	0	0	1000	1% * market value
		54 (iii) Trust involves the transfer/disposition of property		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	0	Government Duty + Surcharge Value + Cess Value	1% * market value
45	Discharge Deed under KACOMP Act	45 (c) (i)- Release of mortgage rights or lien for the amount or value secured does not exceed Rs. 1000	Exemption under Agriculture loan to the Farmers is exempted Max Duty Rs 10			Rate * Consideration			Government Duty + Surcharge Value + Cess Value	
		45 (c) (ii) - Release of mortgage rights or lien for the amount or value secured exceeds Rs. 1000	Exemption under Agriculture loan to the Farmers is exempted Stamp Duty 200			Rate * Consideration			Government Duty + Surcharge Value + Cess Value	

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
26	Exchange of Property		Lesser value property is exempted from Stamp Duty & Fees	5%		Rate * Highest value of the property which is the e subject matter of exchange	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * market value
27	Mortgage with Further charge	b (i) if at the time of execution of the instrument of further charge, possession of the property is given or agreed to be given under such instrument		5%		Rate * Loan Amount	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Loan Amount
Rule 17	Filing of declaration by Bankers under KACOMP Act		Exemption under Agriculture loan to the Farmers is exempted	0.5%		Rate * Consideration			Government Duty + Surcharge Value + Cess Value	Rs 5 for every 25000 with Max of 25000
28	Gift Deed	28 (a) donee is not a family member		5%		Rate * Market Value	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * market value
		28 (b) (i) donee is a family member (BBMP limits)	5000			5000	urban Property 2% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000
		28 (b) (ii) donee is a family member (TMC limits)	3000			3000	urban Property 2% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000
		28 (b) (iii) any other limits	1000			1000	Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
30	Lease/License of Immovable Property	30 (1) (i) - where the lease purports to be for a term not exceeding one year in case of residential property		0.50%	Max 500	Rate * Consideration Max 500	0	0	Government Duty + Surcharge Value + Cess Value	0.5% with Max of 200
		30 (1) (ii) - where the lease purports to be for a term not exceeding one year in case of commercial or industrial property		0.50%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	0.5% with Min of 200
		30 (1) (iii) - where the lease purports to be for a term exceeding one year and not exceeding ten years		1%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	0.5% with Min of 200
		30 (1) (iv) - where the lease purports to be for a term exceeding ten years and not exceeding twenty years		2%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	0.5% with Min of 200
		30 (1) (v) - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years		3%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	0.5% with Min of 200
		30 (1) (vi) - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term		5%		Rate * Highest (Market Value/Annual avg rent, Fine, Premium & Money advanced)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value/Annual avg rent, Fine, Premium & Money advanced)
		30 (4) (i) Lease/License of Immovable Property with in Family Members - If the property is situated within the limits of BBMP or City Corporation	5000			5000	0	0	5000	1000

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
30		30 (4) (ii) Lease/License of Immovable Property within Family Members - If the property is situated within the limits of City or Town Municipal Council or Town Panchayat area	3000			3000	0	0	3000	1000
		30 (4) (iii) Lease/License of Immovable Property within Family Members - If the property is situated within the limits other than the limits specified in items (i) and (ii)	1000			1000	0	0	1000	1000
30	Lease/Licence of Immovable Property	30 (3) (a) (i) Mining Lease through Auction - where the lease purports to be for a term exceeding one year and not exceeding ten years.		1%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (a) (ii) Mining Lease through Auction - where the lease purports to be for a term exceeding ten years and not exceeding twenty years.		2%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (a) (iii) Mining Lease through Auction - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years.		3%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (a) (iv) Mining Lease through Auction - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term.		5%		Rate * Royalty + Estimated Annual Avg Production	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (b) (i) Mining Lease through Grant - where the lease purports to be for a term exceeding one year and not exceeding ten years.		1%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (b) (ii) Mining Lease through Grant - where the lease purports to be for a term exceeding ten years and not exceeding twenty years.		2%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (b) (iii) Mining Lease through Grant - where the lease purports to be for a term exceeding twenty years and not exceeding thirty years.		3%		Rate * Royalty + Estimated Annual Avg Production	0	0	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production
		30 (3) (b) (iv) Mining Lease through Grant - where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term.		5%		Rate * Royalty + Estimated Annual Avg Production	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Royalty + Estimate Annual Avg Production

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
34	Mortgage Deed	(a) Mortgage with Possession		5%		Rate * Market Value	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	0	Government Duty + Surcharge Value + Cess Value	1% * Market Value
		(b) Mortgage without Possession		0.50%		Rate * Consideration	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	0	Government Duty + Surcharge Value + Cess Value	Rs 5 for every 1000 with Max of 25000
39	(a) Partition of Non-Agriculture Land	(1) Partition for Non-Agricultural use (for the Properties other than Municipal/Urban/Town Panchayat)	500 per Share			500	0	0	500	500
		(2) Partition for Non-Agricultural use (Situated in Municipal/Urban/Town Panchayat)	1000 per Share			1000	0	0	1000	1000
	(b) Partition of Agriculture Land		250 per Share			250	0	0	250	200
	(c) Partition of Movable Property		250 per Share			250	0	0	250	300
	(d) Partition of any Property		Highest of combination of all the three	0	0	Highest of combination of all the three	0	0	Government Duty + Surcharge Value + Cess Value	1000
40	Partnership	40(A) Instrument of Constitution		3%	Min 200	3% * Market Value	0	0	Government Duty + Surcharge Value + Cess Value	1% * Market Value
		40(B)(a) Reconstitution where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner or partners on reconstitution of such partnership firm.		3%		3% * Value of immovable Property remaining with the Firm	0	0	Government Duty + Surcharge Value + Cess Value	1% * Value of immovable Property remaining with the Firm
		40(B)(b) Reconstitution in any other case	1000			1000	0	0	1000	200
		40(C)(a) Dissolution of the property which belonged to one partner or partners when the partnership commenced is distributed or allotted or given to another partner or partners		3%		3% * Market Value of the Property Distributed among the Partners	0	0	Government Duty + Surcharge Value + Cess Value	1% * Market Value of the Property Distributed among the Partners
		40(C)(b) Dissolution in any other case	1000			1000	0	0	1000	200

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
41	Power of Attorney	41 (a) - when executed for the sole purpose of procuring the registration of one or more documents in relation to a single transaction or for admitting execution of one or more such documents; (Special Power of Attorney)	100			100	0	0	100	200
		41 (b) - when authorizing one person or more to act in a single transaction other than the case mentioned in clause (a);	100			100	0	0	100	200
		41 (c) - when authorizing not more than five persons to act jointly and severally in more than one transaction or generally;	100			100	0	0	100	200
		41 (d) - when authorizing more than five but not more than ten persons to act jointly and severally in more than one transaction or generally;	200			200	0	0	200	200
		41 (e) - when given for consideration and or when coupled with interest and authorizing the attorney to sell any immovable property;		5%		Rate * Highest (Market Value, Consideration Value)	0	0	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		41 (ea) - If relating to construction or development of an immovable property, including a multi-unit house or building or unit of apartment or flat or portion of a multi-storied building by a developer or builder or promotor or by whatever name called having a stipulation that, for such construction or development, the property shall be held jointly by the developer or builder or promotor or by whatever name called and the owner or lessee, as the case may be, of such property, or that it shall be sold jointly by them or that a part of it shall be held jointly by them and the remaining part thereof shall be sold jointly by them		2%	Max 1500000	Rate * Highest (Market Value, Consideration Value)	0	0	Government Duty + Surcharge Value + Cess Value	2% * Highest (Market Value, Consideration Value)

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
		41 (eb) - when given to person other than the father, mother, wife or husband, sons, daughters, brothers, sisters in relation to the executant authorizing such person to sell immovable property situated in Karnataka State.		5%		Rate * Market Value	0	0	Government Duty + Surcharge Value + Cess Value	1% * Market Value
		41 (ec) - when given to person other than the father, mother, wife or husband, sons, daughters, brothers, sisters in relation to the executant authorizing such person to sell TDR		3%		Rate * Market Value	0	0	Government Duty + Surcharge Value + Cess Value	1% * Market Value
		41 (f) - when executed by a principal or client for the sole purpose of authorizing the agent or broker to carry out all lawful acts and deeds relating to his / her trading operations including sale/purchase of marketable securities, transfer of securities towards stock exchange, receiving/releasing funds and securities from/to other parties on behalf of the principal or client.	50			50	0	0	50	200
		41 (g) - when executed by a principal or client for the sole purpose of authorizing the depository participant to carry out all lawful acts and deeds relating to his/her demat account as per the byelaws of the depositories/ regulations governing such operations.	50			50	0	0	50	200
		41 (h) - in any other case	200			200	0	0	200	200
44	Reconveyance	44(a) - The amount/consideration of the Property does not exceed 1000		5%		Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	1% * Consideration
		44(b) - The amount/consideration of the Property exceeds 1000	100			100	0	0	100	200

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
Section 4	Rectification Deed		100			100	0	0	100	200
45	Release Deed	45(a) - Release not between family members		5%		Rate * Highest (Market Value, Consideration Value)	0	0	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		45(b)(i) - Release between family members (BBMP limits)	5000			5000	0	0	5000	1000
		45(b)(ii) - Release between family members (TMC/CMC limits)	3000			3000	0	0	3000	1000
		45(b)(iii) - Release between family members other than (TMC/CMC limits)	1000			1000	0	0	1000	1000
		45(c)(i) - Release of mortgage rights or lien for the amount or value secured does not exceed Rs. 1000		0.50%	Max Rs. 5	Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	200
		45(c)(ii) - Release of mortgage rights or lien for the amount or value secured exceeds Rs. 1000		0.50%	Max 100	Rate * Consideration	0	0	Government Duty + Surcharge Value + Cess Value	200
20	Conveyance (Sale)	20 (3) Sale by BDA/KHB of Flat Flat/Apartment		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (1) (a) Sale of Agriculture Land		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (1) (b) Sale of Building		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
		20 (1) (c) Sale of Flat = 20(2)		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (1) (d) Sale of Vacant Site or Plot		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (2A) (i) where an instrument of Conveyance relating to the first sale of Flat/Apartment - Where the market value of which is Rs 2000000 or less than 2000000		2%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (2A) (ii) where an instrument of Conveyance relating to the first sale of Flat/Apartment - Where the market value of which is above Rs 2500000 but up to and inclusive of 3500000		3%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20 (7) Sale of Transfer of Development Rights		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
		20(5)(ii) Conveyance relating to industrial machinery - When industrial machinery is treated as immoveable property		5%		Rate * Highest (Market Value, Consideration Value)	If urban Property 2% * Stamp Duty If Rural Property 3% * Stamp Duty	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Highest (Market Value, Consideration Value)
22	Counterpart or Duplicate	Certificate of Denoting of the original duty on the counterpart paid on the original (Same Duty as on the original instrument/Latest Transaction Data will be fetched from the Database)	500			500	0	0	500	200

Article Number	Articles related to Immovable Property	Sub Article	Fixed Stamp Duty	Rate of Stamp Duty	Cap Amount	Government Duty	Surcharge Value	Cess Value	Total Stamp Duty	Total Registration Fees
48	Settlement	48 A (i) - the disposition is not for the purpose of distributing the property of the settlor among his family		5%		Rate * Market Value	0	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1% * Market Value
		48 A (ii) - the disposition is for the purpose of distributing the property of the settlor among the members of his family BBMP limits		5000		5000	0	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000
		48 A (iii) - the disposition is for the purpose of distributing the property of the settlor among the members of his family TMC/CMC limits		3000		3000	0	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000
		48 A (iv) - the disposition is for the purpose of distributing the property of the settlor among the members of his family other limits		1000		1000	0	10% * Stamp Duty	Government Duty + Surcharge Value + Cess Value	1000
		48 B Revocation		5%	Max 200	Rate * Market Value	0	0	Government Duty + Surcharge Value + Cess Value	200
51	Surrender of Lease			100		100	0	0	100	200
52	Will	NA		0		0	0	0	0	200
53	Will including Cancellation	14(c) – In any other case		100		100	0	0	100	200

- i. **Fixed Stamp Duty (Rs.):** Fixed Stamp duty will be definite amount fixed by the department for few identified instruments. As per selection of article, the user will get fixed stamp duty that shall be auto fetched by the system from the backend
- ii. **Rate of Stamp Duty:** Rate of stamp duty is also fixed by the department either in percentage or on the fixed amount. So as per the articles selection rate of stamp duty fixed by the department shall be auto fetched to calculate the total stamp duty to be paid
- iii. **Cap Amount:** Maximum or Minimum amount specified for the stamp duty as per selection of the article by the user. The upper cap or lower cap amount shall be auto fetched by the system from the backend
- iv. **Government Duty (A):** Duty defined for each article as per the stamp act. Stamp duty will be calculated based on the market value and consideration amount. For certain instruments there will be exemption on paying stamp duty given by the government, hence for such instruments government duty will be calculated exempting the rate of exemption.
- v. **Surcharge Value (B):** Surcharge is an additional charge or tax that user will be required to pay based on the stamp duty. Based on the type of the property the surcharge Duty will be calculated as mentioned below:
 - **If urban property 2% on Stamp Duty**
 - **If Rural Property 3% on Stamp Duty**

As per the selection of article, the user will get either fixed stamp duty or rate of stamp duty

As per the user selection of article, surcharge value shall be auto fetched by the system from the backend

- vi. **Cess Duty (C):** Cess is an additional charge or tax that user will be required to pay based on the stamp duty

Cess Duty = 10% on Stamp Duty

As per the user selection of article, Cess Duty shall be auto fetched by the system from the backend

- vii. **Scanning Fee (D):** Scanning fee is the fee for scanning the pages of the instrument which is registered and is a service charge for the purpose of preservation of registered instruments

➤ **Scanning fee = total number of pages to be scanned + two pages by default (In case the number of persons is more than five then additional one page shall be required by default) * scanning amount per page (fixed by the government)**

- viii. **Mutation Fee (E):** Mutation is the fee collected in case of agricultural land for changing of names of the party in the records of land revenue department. It is fixed amount declared by the government


- ix. **Denotation of stamp duty (F):** If more than one instrument is implied for the purpose of completing the transaction then the stamp duty paid on the earlier instrument is to be denoted on the subsequent instrument and the difference of stamp duty is to be paid on the final instrument. If the difference of duty is less than INR 200 minimum stamp duty shall be INR 200

➤ **Total stamp duty = Stamp duty denoted + Difference of total duty**

- x. **Total Stamp Duty:** It is the addition of Government duty, Surcharge duty & Cess duty. As per the user selection of article, Total Stamp Duty shall be auto calculated by the system
- **Total Stamp Duty:** Government Duty (A) + Surcharge Value (B) + Cess Duty (C) + Scanning Fee (D) + Mutation Fee (E) - Denotation of stamp duty (F)
- xi. **Total Registration Fees (H):** Registration Fees will be determined by the department. Registration Fees will be calculated based on the market value, consideration amount and cap amount. Registration fee shall be auto calculated as per user's selection by the system
- xii. **Total Payable Amount:** Government Duty (A) + Surcharge Value (B) + Cess Duty (C) + Scanning Fee (D) + Mutation Fee (E) - Denotation of stamp duty (F) + Total Registration Fees (H)
- xiii. **Royalty:** Royalty is the amount in lieu of the ore or minerals extracted from mines or quarry in an annum
- xiv. **Estimated Annual Avg Production:** The quantity of ore or mineral extracted on daily basis and average of the extract is the annual average production
- **Estimated Annual Avg Production:** Annual average production in cubic meter or ton *Rate of cost of minerals/ore

Scenario 1: Fee Calculation for Multiple Properties

This section will be scrollable for the use to enter consideration amount for multiple properties

< Back


Now, let's do the stamp duty and fee calculation

< PROPERTY 1 OF 3 >

DISTRICT : BENGALURU (RURAL)

TALUKA: DEVANAHALLI

HOBLI/ TOWN:VIJAYAPURA

INDEX II: VILLAGE: KOMMASANDRA

Stamp Duty Selection

Region Type

Market Value (₹)

Consideration Amount (₹)

Value ▾

Value

Value

Value

This below mentioned section will be displayed only once in the fee calculation section for registration of a single document

Exemption Details

Government Duty

Value

☐ Exemption for this duty

Denotation of Stamp Duty

Value
Denotation Description
Value

Number of Pages

Value

Scenario 1:

The user wont able to calculate the fees until the consideration amount for all the properties and No. of pages is entered

S.No.	Property	Article	Rate	Market Valuation	Consideration
1	Property 1	Conveyance-1	5%	1,20,000	1,10,000
2	Property 2	Conveyance-1	5%	1,00,000	1,25,000
3	Property 3	Gift	3%	0	10,000

- I. In the case mentioned above, the final amount to be considered will be calculated separately based on the article selection as the rate is different for each article:
 - a. M.V. for property 1 & 2 = 1,20,000 + 1,00,000 = 2,20,000 /-
 - b. Cons. for property 1& 2 = 1,10,000 + 1,25,000 = 2,35,000 /-
- II. The highest amount will be taken both which is 2,35,000 /-
- III. For property 3, as there is no M.V. therefore 10,000 /- will be considered final amount

Property	Amount to be Considered	Rate	Total
Case I – Property 1&2	2,35,000	5%	11,750
Case II – Property 3	10,000	3%	300
		Total Payable	12,050

Existing SD:

Stamp (Govt) Duty - (variable)
Exemption Duty on SD - (variable)
Govt Duty after Exemption - (variable)
Cess - (variable)
Surcharge - (variable)
Duplicate SD – Rs.500 (fixed)
Denotation of SD - (variable)

Things to be ADDED to SD:

Deficit SD - (variable)
Affidavit SD – Rs.20 (fixed)
Preemption SD – Rs.100 (fixed)
Certified Copy SD – Rs.10 (per copy) (variable)

Existing RF:

Registration Fee (RF) - (variable)
Duplicate RF – Rs.200 (fixed)

Things to be ADDED to RF:

Exemption (Concession) Duty on RF - (variable)
RF after Exemption - (variable)
RF after Set Off – (variable between Rs.100 and Rs.500)
RF u/s 30 (in DR Office) – Rs.2000 (fixed)
Consenting Fee – Rs.100 (fixed)
Map Filing Fee – Rs.100 (fixed)
Memo Fee – Rs.100 (fixed)
Private Attendance Fee – Rs.1000 (fixed)
Delay Condonation Fee – Rs.200 (fixed)
Delay Condonation Fine – (variable)
Holiday RF – Rs.2000 (fixed)
Authentication or Attestation POA Fee – Rs.100 (fixed)

Others:

Mutation Fee – Rs.45 (fixed)
Service Charge (Scanning Fee) - Rs.35 per page

Things to be ADDED to Others:

Appeal Fee – Rs.1000 (fixed)
Document Withdrawal Fee – Rs.200 (fixed)
Will Deposit Fee – Rs.1000 (fixed)
Filing of Translation Fee – Rs.50 (fixed)
Safe Custody Fee– Rs.10 per 15 days (Maximum of Rs.100)
Protest Application Fee – Rs.200 (fixed)

9 PARTY INFORMATION

i. Brief Description

The user is required to submit details of all the parties in 'Party Information' section. For property registration there shall be two parties: Claimant who may be the buyer, shareholder, co-owner, or transferee and second party would be the executant who may be seller, shareholder, co-owner or transferer. To identify the party some of the below details required:

- Name
- Name of parent/ husband/guardian/ authority holder
- Age
- Gender
- Profession
- Address

In the party information section, the user shall be required to mention the details of the following parties involve in the property registration process:

- I. Presenter (Only 1) maybe either claimant or executant or both
- II. Claimant (1 or multiple)
- III. Executant (1 or multiple)
- IV. Witness (Minimum 2)

Party Details – Presenter & Executant

Applicant
System

```

graph TD
    Start(( )) --> EnterParty[Enter Party Details]
    EnterParty --> EnterPresenter[Enter Presenter Details]
    EnterPresenter --> WhoPresenting{Who is presenting? (Claimant/Executant)}
    
    WhoPresenting -- No --> EnterExecutant[Enter Executant Details]
    EnterExecutant --> IsClaimant{Is Claimant?}
    IsClaimant -- Yes --> MarkClaimant[Mark as Claimant in Database]
    IsClaimant -- No --> SelectParty[Select Type of Party (Individual/Organization)]
    
    WhoPresenting -- Yes --> SelectParty
    
    SelectParty --> OrgInfo[Organization Information]
    SelectParty --> IndInfo[Individual Information]
    
    OrgInfo --> OrgName[Name of the Organization]
    OrgName --> OrgYear[Year of Incorporation]
    OrgName --> OrgTAN[Enter TAN]
    OrgName --> OrgAddress[Enter Address]
    
    IndInfo --> EnterName[Enter Name]
    EnterName --> EnterAlias[Enter Alias Name]
    EnterName --> FirstMiddleLast[First Name/Middle Name/Last Name]
    EnterName --> SelectGender[Select Gender]
    SelectGender --> GenderList[Male/Female/Other Gender]
    EnterName --> EnterAge[Enter Age (in Yrs)]
    EnterName --> EnterProf[Enter Profession of the Applicant]
    EnterProf --> SelectDropdown[Select from Dropdown]
    EnterName --> EnterAddress[Enter Address]
    EnterAddress --> HouseNo[House No., Street Address, State, District, City, Pin-code]
    EnterName --> RelativeName[Relative's Name]
    EnterName --> Relationship[Relationship (Dropdown)]
    
    IndInfo --> PANAvailable{PAN Available?}
    PANAvailable -- No --> UploadForm[Upload Form 60/61]
    PANAvailable -- Yes --> EnterPAN[Enter PAN]
    EnterPAN --> VerifyPAN{Verify PAN}
    VerifyPAN -- No --> AddNewParty[Add New Party Details]
    VerifyPAN -- Yes --> AddNewParty
    
    AddNewParty --> AddParty{Add Party?}
    AddParty -- Yes --> Submit[Submit]
    AddParty -- No --> Submit
    
    Submit --> SaveParty[Save the Party Details]
    SaveParty --> End(( ))
  
```

ii. Functional Step by Step Process

- i. **Select the Party:** The user shall select the 'party' from the below list to enter the party detail
 - a. Presenter
 - b. Executant
 - c. Consenting Witness
- i. In case the user selects **Presenter option**, then the user shall select from either 'Claimant' or 'Executant' option
- ii. In case the user has selected **Executant option**, the system will ask, if the user 'is claimant also?'

Case 1: If the user has selected 'yes' then the system will duplicate the information in the claimant section otherwise it will proceed to next step

- iii. **Select Type of Party:** The user shall select type of party from either individual or Organization option
 1. **Organization:** In case the user has selected the Organization option to enter the party details, the system will prompt the user to enter the below information
 - a. **Name of the Organization:** The user shall enter the name of the organization
 - b. **Year of Incorporation:** The applicant shall enter the year of incorporation of the organization
 - c. **TAN:** The applicant shall enter the TAN of the organization
 - d. **Registered Address:** The applicant shall enter the registered address of the Organization
 - o If individual is representing an organization, his personal PAN may not be entered
 - o After entering the organization information, the system will prompt the user to enter the authorised signatory information
 2. **Individual Information:** In case the user has identified himself as an Individual to enter the 'selected party details'. Then individual option will be selected, and the system will prompt the user to enter below information
 - a. **Enter Name:** The user shall enter the first name, middle name, and last name in the system
 - b. **Enter alias Name:** The user shall enter the Alias name in the system
 - c. **Relationship:** The applicant shall select the relationship type from the dropdown
 - d. **Relative Name:** As per the Relationship selected by the user, the system will prompt the user to enter relative name
 - e. **Enter Age (in Yrs.):** The applicant shall enter the age of the party as per the government issued id

- f. **Select Gender:** The applicant shall select the gender of the party Male, Female, and other gender from the dropdown
- g. **Enter Profession of the Applicant:** The user shall enter the Profession of the applicant
- h. **Address Details:** The applicant shall enter House No/Building Name, Street, City/Village, Taluka, District, State, Pin Code
- i. **PAN available:** The system will check for the availability of user's PAN card as per below cases

Case 1:

In case the user selected option to enter PAN then system will prompt the user to enter PAN

Case 2:

In case the user declares that it doesn't possess PAN then the system will prompt the user to upload declaration Form 60/61

Validation: PAN Card number must satisfy the following conditions:

- i. It should be ten characters long
 - ii. The first five characters should be any upper-case alphabets
 - iii. The next four-characters should be any number from 0 to 9
 - iv. The last character(tenth) should be any upper-case alphabet
 - v. It should not contain any white spaces
- j. **Verify PAN:** The system will verify the PAN number entered by the user. In case the PAN is invalid then the system will redirect the user to enter PAN again

iv. **Represented by Power of Attorney:**

Case 1:

In case the user has not selected 'Represented by Power of Attorney' option then the user will save the details and continue with the process

Case 2:

In case the user has selected 'Represented by Power of Attorney' option then the user shall select either 'Individual' or 'Organization' and enter the details as per below option:

1. **Individual Information:** In case the user has identified himself as an Individual. Then the user shall be required to enter the name (first name, middle name & last name), relationship, age, gender, profession and address in the system
2. **Organization:** In case the user has selected the Organization option, the system will prompt the user to enter the below information
 - a. **Organization Name:** The user shall enter the name of the organization
 - b. **Year of Incorporation:** The applicant shall enter the year of incorporation of the organization
 - c. **TAN:** The applicant shall enter TAN value in the system

- d. **Address Details:** The applicant shall enter House No/Building Name, Street, City/Village, Taluka, District, State, Pin Code
- e. **Represented by Authorised Signatory:** The user shall be required to enter the first name, middle name, and last name, relationship, relative name and age in the system

Note: In case the user has selected 'Organization' option then 'Represented for minor guardian' and 'Exemption from Appearance' option shall not be applicable

- v. **Presenting the document:** In property registration, there shall only be a single presenter, who would be presenting the document to Sub-Registrar at the SRO

Case 1:

In case the user is presenting the document then the system will allow the user to add new party details and enter executant details

Case 2:

In case the user is not presenting the document then the system will allow the user to select type of party


- vi. **Represented for minor guardian:** In case the user has selected 'Yes' to 'Represented for minor guardian' option then the user shall enter name, age, and relationship
- vii. **Exemption from Appearance (Section 88):** In case the user could not be present at Sub Registrar office on date and time of the document registration and the applicant possess the exemption letter from the distinguish authority, then

Case 1:

In case the user has selected 'Yes' in 'Exemption from Appearance' option then the user shall be required to enter 'exemption reference letter number' and upload exemption reference letter. Section 88 exemption is applicable only for court and certain functionaries as per notification of the department and provision of the law

- viii. **Add Party:** After filling details of claimant/ executant, the user shall have an option to add multiple individuals in both the section otherwise user could save the party information and move forward

Party Information - Identifiers



Functional Step by Step Process

- i. In case the user is an identifier, then in the application the following identifier details shall be required:
 - Name (First Name, Middle Name, Last Name)
 - Age
 - Gender (Male, Female, Transgender or other)
 - Profession of witness
 - Address (House no, Street Address, State, District & City)
 - Witness identifies (Claimant or Executant)

- ii. After user enters above identifier details, system shall ask the user if number of identifiers is greater than equal to two, as for executing the property registration document, at-least 2 identifiers would be required

Case 1:

In case the user selects 'Yes' then the system shall again prompt the user if they want to add more identifiers, in case the user selects yes then the process shall end otherwise user shall add more identifier and its details

Case 2:

In case the user selects 'No' then system shall again prompt the user to add at least two identifiers and its details

- iii. Add identifier: After filling details of consenting witness the user shall have an option to add multiple individuals otherwise user could save the party information and move forward

User Interface (UI)

Presenter

Presenter Details

<

PRESENTER

Who is presenting

☐ Claimant

☐ Executant

☐ Both

Whether Individual or Organization

☒ Individual

☐ Organization

Salutation*

Value

▼

First Name*

Value

Middle Name

Value

Last Name

Value

Alias Name

Value

Relationship*

Value

▼

Relative's Name*

Value

Age*	Gender*	Profession
Value	Value	Value
ID Proof Type	ID Number	☐ I don't have a PAN
PAN	Value	
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value
☐ Represented by Power of Attorney		
Save and Continue		

Executant

Enter the Details

<

EXECUTANT 1

EXECUTANT 2

Number of Executant

Is Consenting Witness

☐ Yes

☐ No

Is Claimant

☐ Yes

☐ No

☐ Represented for Minor Guardian

☐ Exempted from Personal Appearance (Section 88 Exempted)

Whether Individual or Organization

☒ Individual

☐ Organization

Salutation

First Name*

Middle Name

Last Name

Alias Name

Relationship*	Relative's Name*	
Value	Value	
Age*	Gender*	Profession
Value	Value	Value
ID proof	ID Number	☐ I don't have a PAN
Value	Value	
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value
☐ Represented by Power of Attorney		
Save and Continue		

Identifiers

IDENTIFIER 1		
Salutation	First Name*	Middle Name
Value	Value	Value
Last Name	Age*	Gender*
Value	Value	Value
Profession		
Value		
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value

Relationship*

Relative's Name*

Identifies

☐ Claimant


☐ Executant

Save and Continue

10 DOCUMENT SUMMARY – Applicant (Online)

i. Brief Description

It is the document summary of party information, property information, valuation of the property and calculation of stamp duty & fees and also contains witnesses’ particulars along with the check & verification of align data before sending it to the SRO



ii. Functional Step by Step Process

The system generates the ‘online document summary’ report, this report gives summary of all the details entered for the document registration. The user shall be able to go through the

document summary as presented by the system. Document summary shall contain below details:

- Address details (District, Taluka, Hobli, Village, SRO, Property Type, Survey No, Hissa No)
- Property(s) details
 - Property data – Bhoomi and Article selected
 - Court order details
 - Liability details
- Market Valuation and Fee calculation details
- Party(s) details (Claimant, Executant, Identifier(s) details)
- Upload Deed Document Along with Enclosures: The user shall be required to upload the deed document along with the enclosers in the application. The enclosure documents shall be according to the articles and type of registration
- The date of execution of the document also needs to be selected by the applicant
- The user shall be asked to select the Sub-Registrar office from the dropdown, and the application shall be forwarded to the selected SRO for evaluation

The user shall verify the above details in order to check any data entry mistakes, the user shall be required to accept the declaration and only after then the application shall be submitted for approval.

User Interface (UI)

Upload Deed Document

Please upload the draft Deed document for review



Date of Execution

Please select the date of execution



Select Sub registrar office

Please select the Sub-registrar office for Registration

Declaration

☐ I hereby confirm that all the information provided is correct to the best of my knowledge. Also, I understand that in case any information is found incorrect, misleading, or fraudulent, there can be action was taken against me as per the Information Technology Act, 2000 and it may or may not lead to the cancellation of this document.


Date: 01-Oct-2021

Place: Ranchi

11 DEPARTMENT LOGIN & DASHBOARD


i. Brief Description

Departmental login shall enable the authorized officers from SRO (Sub-Registrar Office) or any other officers from the department to login in the system. Login credentials which are 'username' and 'password' shall be provided by the department to the respective SRO or to other officers from the department. After system verify the login credentials and biometric authentication, concerned authorized officers from department shall be able to login in the system.



ii. Functional Step by Step Process

1. **Department Login:** The authorized officers from SRO or any other officers from the department shall login in the system by entering Username and Password provided to them by the department
2. The system shall check the validation of login credentials entered by the user. In case login credentials are valid, then the user shall verify the biometrics. In case login credentials are invalid then the system shall prompt to enter username and password again
3. In case the biometrics captured by the system gets verified then the user shall be able to be logged in the system otherwise system shall prompt to capture biometrics again



On the Departmental login dashboard, officers from SRO or any other officers from the department shall be able to view the below details:

- Total number of documents registered which will be categorized as Book 1, Book 3 & Book 4
 - **Book 1:** Book 1 will capture the contents of all registered non testamentary documents in respect of immovable property (e.g., Deeds of Sale, Gift, Mortgages, Lease, Release Deed, Exchange, Partition, Rectification, Cancellation etc.)
 - **Book 3:** Book 3 will capture the contents of testamentary documents like Will, Authority to adopt, Codicils Cancellations of wills etc.
 - **Book 4:** Book 4 will capture the contents of instruments like Power of Attorney, Adoption Deed, Divorce Deed, Trust, and other transactions involving movable assets etc.
- Total number of marriages registered which will be categorized as Hindu, Special or other marriages
 - **Hindu Marriage:** For Hindu marriage, the bride and groom shall submit declaration of marriage in the form of form no.1. Declaration will be from bride and groom having married outside the marriage officer in presence of witnesses
 - **For Special marriage,** Bride and groom shall submit notice for intended marriage after completion of 30 days from date of notice after that marriage will be solemnize by SRO

- **Special marriage in other forms section 13**, notice will be served by the married couple other than Hindus or inter religion marriage to get their marriage registered from date of their original marriage
- Total amount of revenue generated which will be categorized on the basis of stamp duty and registration fees
 - **Total Stamp Duty:** It is the addition of Government duty, Surcharge duty & Cess duty. As per the user selection of article, Total Stamp Duty shall be auto calculated by the system
 - **Total Registration Fees:** Registration Fees will be determined by the department. Registration Fees will be calculated based on the market value, consideration amount and cap amount. Registration fee shall be auto calculated as per user's selection by the system
- Total number of transactions of Encumbrance certificate, Certified copy, and Number of firm registrations
 - **Encumbrance Certificate:** Encumbrance certificate is a record showing registered transactions over a property. For obtaining EC or CC applicant shall submit application form no. 22
 - **Certified Copy:** Agencies like banks refer to certified copies of registered sales deed before giving loan on a mortgaged property to verify the ownership. IT department may also refer to a certified copy to ascertain value of transaction and assess the income of the property buyer or seller. CC of registered documents relating to immovable properties is obtained to verify the ownership of property and legality of the transaction effected through it
 - **Firm Registration:** The applicant shall submit deed along with declaration to registrar of firms (District Registrar). The user shall select the firm option. Any two or more major citizen can enter partnership and register the partnership firm. The firm is registered in the office of District Registrar (Registrar of firms) of the concerned jurisdiction
- The above details shall be accessible to the officers from SRO or any other officers from the department by providing the date range in the dashboard

Function:


Use Case Name	Department Login
XRef	9-Department Login & Dashboard
Trigger	Authorized officers from SRO or any other officers selects login button to get logged into the system
Precondition	Authorized officers from SRO or any other officers should be registered by the department to get logged in successfully
Basic Path	1. Authorized officers from SRO enters login credentials (username, password) and biometric to login 2. System checks authenticity of the Authorized officers from SRO

	3. The system shall check if the login credential and biometrics are valid else system will ask to enter login credential and capture biometric again
Alternative Paths	N.A.
Post condition	Authorized officers from SRO gets logged in to the system if authenticated successfully otherwise system will ask to enter the details again
Exception Paths	N.A.
Other	N.A.

User Interface (UI)



Kaveri Online Services
Department of Stamps and Registration, Government of Karnataka




12 SRO CONFIRMATION

i. Brief Description

The user shall review the application and upload the deed document, the applicant shall be required to send the request to the SRO for getting the approval for the document registration. The Sub-Registrar shall check the deed document along with enclosures and the details submitted by the applicant shall also be checked i.e., document information, party details, property schedule, market valuation and fee calculated as per the article selection.

All the details entered in the application shall be checked according to the deed document, which is uploaded by the user before sending the request to SRO.



ii. Functional Step by Step Process

- i. **Overview the Application:** After submitting the application the user shall be re-directed to the application viewer where the details submitted by the user shall be merged in a single view. The application viewer could be downloaded in the PDF format by the user. If user found any of the information incorrect then, he could edit the application and save it again
- ii. **Submit the Request to SRO:** After verifying the application information and uploading of the documents is complete, the user shall be required to accept the declaration and send the request to SRO for approval

- iii. **Application Alert Sent to SRO:** After the application is successfully submitted by the user in the Kaveri portal then the application shall be forwarded to the respective SRO. An alert shall be notified to the respective Sub-Registrar after successfully receiving the application
- iv. **Departmental Portal Login:** The Sub Registrar from the department shall login using their login credentials and do the Biometric authentication. In case the sub registrar's login credential and biometric authentication gets verified in the system then sub registrar will be logged in otherwise system will redirect to enter the login credential and do the biometric authentication again
- v. **Allocate Application to FDA/SDA:** The responsibility of the Sub-Registrar would be to allocate the applications to the respective Second Division Assistant (SDA) or First Division Assistant (FDA) and after the application gets reviewed by the SDA/FDA then it will be sent to the Sub-Registrar for final evaluation of the application

Application Received by SDA/FDA

- i. **Login and Select Active Applications:** The SDA/FDA shall login in the system and check the applications received by the SR for evaluation under the Active Application section
- ii. **Open Application and check the enclosure Document & Property schedule:** All the application which is being received by the SDA/FDA shall be accessible in FIFO (First In First Out) manner and there shall be a time frame of 24 – 48 hours to respond back to all the received applications. Firstly, SDA/FDA shall check the deed documents and enclosures which is submitted by the applicant in the portal. The SDA/FDA shall be required to check the property schedule as per the document
- iii. **Check Market Valuation and Fee Calculation:** The SDA/FDA shall be required to check the market valuation and fee calculation in the application as per the deed document and article selected by the user in the application. The SDA/FDA shall have the functionality to calculate the Market Value and Fee Calculation separately.
- iv. **Evaluate Party Details and Article Selection:** The SDA/FDA shall be checking the Party details submitted in the application as per the deed document uploaded by the user. The confirmation of the article selection shall also be checked by the SDA/FDA
- v. **Verified by SDA/FDA:** After checking the information in the application as per the deed document, the SDA/FDA user shall verify each section and mention remarks if necessary. If any discrepancy is found in the application, then the section will not be verified, and SDA/FDA shall mention the recommendation which needs to be corrected in the application by the Applicant.

Note: In case, if any one of the sections is not verified by the SDA/FDA then the remarks shall be mandatory.

Application Received by SR

- i. **Verified by Sub-Registrar:** The FDA/SDA will submit the application to Sub-Registrar after verification of the application. The SR will also check the information as per the deed document and verify each section and mention remarks if necessary.
- ii. **Check Market Valuation and Fee Calculation:** The SR shall be required to check the market valuation and fee calculation in the application as per the deed document and article selected by the user in the application. The SR shall also have the functionality to calculate the Market Value and Fee Calculation separately
- iii. **Confirm & Approved by Sub-Registrar:** After the assessment is completed by the SRO the Sub-Registrar shall be required to decide either to approve or not approve the application. The decision shall be made as per the rule book and guidelines of Stamps & Registration Department and in case the Sub-Registrar found discrepancies in the application then application evaluation result shall be sent to applicant along with the remarks from Sub-Registrar
- iv. **Application Approved:** In case the application is approved by the SRO, then the applicant would be able to continue with the payment process and appointment scheduling for the document registration

(**Note:** 1. The applicant will only receive the decision made by the Sub-Registrar and remarks entered for each section by the SR. The decision or remarks of the SDA/FDA will not be viewable to the Applicant and only SR shall have the access to view the SDA/FDA remarks; 2. After the application is received from FDS/SDA, the SR shall login and shall view the remarks made by FDA/SDA and shall add his/her own remarks and shall send it back to the applicant for either to attend to the remarks made and resend the application or to proceed to make payment; 3. When the changes (attend to SR remarks) are requested by the SR to the applicant, the system takes the applicant to the 1st page with the pre-filled data being retained as earlier over which he can over-write to make changes and then shall send back to the SR; 4. If the applicant is willing to attend to the remarks made by SR, then resend the application after corrections are made. If not willing to attend to the remarks made by SR, then the system shall generate the Endorsement with Reason for Rejection)

Function:

Applicant

Use Case Name	SRO Confirmation - Applicant
XRef	10 - SRO Confirmation
Trigger	Applicant submit the request to SRO for application evaluation
Precondition	Applicant fill the application, upload deed document and select the date of execution and Sub-Registrar office
Basic Path	1. Applicant submit request to SRO for the evaluation 2. Request sent to SRO for evaluation 3. If approved, Applicant could continue with the payment

	4. If not approved, Applicant accepts the remarks and correct the discrepancies in the application 5. After correcting discrepancies, Applicant again submit the request to SRO
Alternative Paths	If applicant does not get the approval online, then the user can appeal before DRO for re-conciliation and the decision taken by the DRO on the application shall be final
Post condition	Applicant gets the SRO approval to proceed to make payment for the Stamp duty and Registration fee approved
Exception Paths	N.A.
Other	N.A.

FDA/SDA

Use Case Name	SRO Confirmation – FDA/SDA
XRef	10 - SRO Confirmation
Trigger	Sub Registrar Allocate the Application to SDA/FDA
Precondition	Application successfully submitted by applicant and allocated by the Sub-Registrar for verification
Basic Path	1. SDA/FDA successfully login 2. SDA/FDA selects the application in FIFO manner 3. SDA/FDA reviews application Deed document, Property schedule, Market valuation, Fee calculation, Party details and Article selected 4. If the application is proper, then SDA/FDA will Verify all the sections else will not Verify and mention remarks
Alternative Paths	N.A.
Post condition	After submission of the application by SDA/FDA, then it will be evaluated by the Sub-Registrar
Exception Paths	N.A.
Other	N.A.

Sub Registrar

Use Case Name	SRO Confirmation – Sub Registrar
XRef	10 - SRO Confirmation
Trigger	Application received by Sub Registrar
Precondition	Application successfully submitted by applicant
Basic Path	1. Sub Registrar successfully login 2. Sub Registrar selects the application in FIFO manner 3. Sub Registrar Allocate the application to SDA/FDA 4. Sub Registrar reviews application after verified by SDA/FDA Deed document, Property schedule, Market valuation, Fee calculation, Party details and Article selected 5. If the application is proper, then Sub registrar will approve else Sub registrar will not approve and mention remarks
Alternative Paths	N.A.
Post condition	After approval from SRO, applicant could move forward in the application process, payment and appointment scheduling shall be enable for the applicant
Exception Paths	N.A.

Other	If applicant again submit application for Sub Registrar approval after correcting discrepancies, then the decision taken sub registrar will be final
-------	--

User Interface (UI)

Split Screen View


Kaveri Online Services
 Department of Stamps and Registration, Government of Karnataka


 Welcome Tanmay
 SUB REGISTRAR: BENGALURU URBAN

LAST LOGIN:
 12TH OCTOBER 2021 8:34AM



[< Back](#)

Application Details

APPLICATION NUMBER
 AP212001335016514

DATE OF SUBMISSION
 08-08-2021


APPLICATION TYPE
 Movable Property Registration

Property Details

Property 1 of 1

TYPE OF PROPERTY WITH DESCRIPTION : REGISTRATION OF HMV WITH RC KA01A1123

Deed Document



Market Valuation and Fee Calculation

Market Valuation and Fee Calculation				Market Valuation	Fee Calculation
Property	Title	Description	Applicant Input	FDA/ SDA Input	SR Input
Property 1 of 1 Agricultural plot located in District: Bengaluru (Rural), Taluka: Devanahalli, Hobli: Vijayapura, Village: Kommasandra, SRO: Kommasandra bearing Survey no.	Market Valuation	Total Valuation Amount ⓘ	₹ 69,00,000.00	₹ 69,00,000.00	₹ 69,00,000.00
	Consideration Amount	Total Consideration Amount	₹ 69,00,000.00	₹ 69,00,000.00	₹ 69,00,000.00
	Stamp Duty and Fee Calculation	Government Duty after Exemption (A)	₹ 50,000.00	₹ 50,000.00	₹ 50,000.00
		Surcharge Value (B)	₹ 1,000.00	₹ 1,000.00	₹ 1,000.00
		Cess Value (C)	₹ 5,000.00	₹ 5,000.00	₹ 5,000.00
		Denotation of Stamp duty (D)	₹ 5,000.00	₹ 5,000.00	₹ 5,000.00
		Total Stamp Duty (E)=(A)+(B)+(C)-(D)	₹ 51,000.00	₹ 51,000.00	₹ 51,000.00
		Registration Fees (F)	₹ 5,000.00	₹ 5,000.00	₹ 5,000.00
		Scanning Fees (G)	₹ 100.00	₹ 100.00	₹ 100.00
		Mutation Fees (H)	₹ 5,000.00	₹ 5,000.00	₹ 5,000.00
Total Payable Amount (E)+(F)+(G)+(H)			₹ 61,100.00	₹ 61,100.00	₹ 61,100.00

Verification Screen for SDA/FDA and SR

Application Verified by FDA/SDA


Select the section that needs to be corrected.

S.No.	Verified	Section	FDA/SDA Remarks	Verified	SR Remarks
01	☒	Date of Execution		☐	
02	☒	Property Details		☐	
03	☒	Party Details		☐	
04	☒	Property Schedule		☐	
05	☒	Market Valuation		☐	
06	☒	Fee Calculation		☐	
07	☒	Court order		☐	
08	☒	Liability		☐	

13 PAYMENT

i. Brief Description

After computing Stamp duty and registration fee based on valuation or amount of consideration and obtaining SRO confirmation for the property registration, the applicant shall be required to enter the challan number, amount, and date of challan. The system shall check the details in Khajane-2 based on the challan details entered by the user.



ii. Functional Step by Step Process

The user shall be required to visit Khajane-II portal for the payment of approved Stamp Duty and Registration Fees. The re-directed link to Khajane-II shall be available after user gets approval from the SRO.

Payment Details: For payment details, the system shall display the purpose of challan. The user shall enter the challan number, amount (in rupees) and date of challan transaction. After the user enters the details, the system shall check challan details in Khajane-II as per below mentioned condition:

Case 1:

In case the system finds challan details in Khajane-II then the system shall check if challan amount is greater than or equal to payable amount (as per stamp duty calculation). In case challan amount is greater than or equal to payable amount then user will get the message 'payment details successfully submitted', otherwise system shall prompt user to add another challan for the deficit amount.

Case 2:

In case the system doesn't find challan details in Khajane-2 then the system shall redirect the user to enter proper challan details in the system.

Note: 1. The user shall be given option to add multiple challan for the single document registration. The process to add another challan shall remain same as mentioned above;

2. During the payment process, the applicant shall have 3 options:

- a. Normal – where the party has to pay the SD, RF & SF as per the calculation of the SR
- b. Under-valuation – where the party mayn't accept SR's valuation, but he prefers to pay as per his valuation with an option to refer the document for determination under section 45-A to DR. After the DR's Order, the party has to make payment as per the orders of the DR. There should be a provision for making payment by Add Challan. Once the payment is made, an option has to be made to submit the challan to the SR. After receiving the challan, the SR shall order for Registration (Check & Register)
- c. Impound – where the party mayn't pay the proper SD by preferring to pay short levy of SD and the document gets impounded and sent to DR for ordering for the recovery of deficit SD with appropriate penalty. There should be a provision for making payment by Add Challan of deficit SD with appropriate penalty. Once the payment is made, an option has to be made to submit the challan to the SR. After receiving the challan, the SR shall order for Registration (Check & Register)

User Interface (UI)

Challan Verification

Already made the Payment?

Update the Payment details for your Application

Purpose of Challan

DOCUMENT REGISTRATION

Challan Number

Value

Verify Challan

NAME OF THE PERSON	DDO CODE	CHALLAN NUMBER	DDO OFFICE NAME	AMOUNT	DATE OF TRANSACTION	KTC 25 RECONCILIATION NO.

Submit

Challan Receipt Generation

This is a computer generated e-Acknowledgement & does not require any signature



Transaction Receipt

Transaction Reference No	013018013550891550
Bank Name	HDFC Bank
Bank Reference No	439943102
Amount (Rs.)	145
Transaction Execution Date & Time	2018-01-30 14:03:48.469
Mode Of Payment	Net Banking
Status	Payment received at payment gateway

Print Challan Receipt


Return to Application

14 APPOINTMENT SCHEDULAR

14.1 Schedule Appointment to Visit SRO

i. Brief Description

The registered user will be able to book an appointment to visit sub registrar office (SRO) through Appointment scheduling function. User will be able to schedule appointment for certain duration and have the option to reschedule and cancel the appointment. The user will be required to select appointment date and available slots shall be displayed. After the confirmation from the user the system will generate unique token number.



ii. Functional Step by Step Process

- i. The user shall select the appointment booking option only after successfully made the payment in Khajane - II
- ii. **User Type and Name:** The user type and Name shall be auto fetched from the party details for booking the appointment
- iii. **Sub Registrar office:** Based on the selection of SRO in Online Document Summary page, the SRO Name shall be displayed, and appointment shall be booked for the same SRO
- iv. **Date:** The user will select the date as per his convenience and the next available slot shall be displayed
- v. **Confirm Appointment:**

Case 1 – Appointment confirmed

- In case the **Appointment is confirmed**, the system will generate unique token number
- After token number is successfully generated, the system will display the slot booking confirmation to the user

Case 2 – Appointment not confirmed

- In case the user doesn't want to continue with the appointment, then the user will have an option either to change date or cancel the appointment
- vi. After slot booking confirmation, the User will receive all the appointment details over registered Email and SMS


Note: One hour time slot shall be left to discretion of Sub Registrar for emergency registration i.e., wills.

14.2 Reschedule Appointment

This rescheduling feature will get locked before pre-defined period which is configured by Sub-Registrar.

i. Brief Description

After scheduling the appointment, the user will have an option to Reschedule the appointment as per his convenience before actual appointment.



ii. Functional Step by Step Process

- i. **Appointment scheduling service:** The user shall select appointment scheduling option, then the system will display all the unique tokens generated for the user. The rescheduling option will be available to the user 24 hours before appointment gets expired
- ii. **Token Number:** The user shall select the token number to Reschedule the Appointment, the user will select the reschedule option
- iii. **Token request validation:**

Case 1 – Token Expired

- In case the Token Number selected by the user is expired, then the system will end the process

Case 2 – Token not Expired

- In case the Token Number selected by the user is available, the system will allow the user to Reschedule the appointment

- iv. **User Type and Name:** The user type and Name shall be auto fetched from the party details for booking the appointment
- v. **Sub Registrar office:** Based on the selection of SRO in Online Document Summary page, the SRO Name shall be displayed, and appointment shall be booked for the same SRO
- vi. **Date:** The user will select the new date as per his convenience and the next available slot shall be displayed
- vii. **Confirm Appointment:**

Case 1 – Appointment confirmed

- In case the user confirms the appointment, the system will generate unique new token number
- After new token number is successfully generated, the system will display the slot booking confirmation to the user

Case 2 – Appointment not confirmed


- In case the user doesn't want to continue with the appointment, then the user will cancel the appointment

- viii. After slot booking confirmation, the User will receive all the appointment details over registered Email and SMS

14.3 Cancel Appointment

i. Brief Description

After scheduling the appointment, the user will also have an option to cancel the appointment as per his convenience before the actual appointment. or token number may get automatically expire in case of over-run of date and time.



ii. Functional Step by Step Process

- i. **Appointment scheduling service:** The user shall select appointment scheduling option, then the system will display all the unique tokens generated for the user
- ii. **Token Number:** The user shall select the token number to cancel the Appointment, the user will select the reschedule option

- iii. **Token numbers to cancel:** The user shall enter the reason behind the cancellation of the appointment and cancels the token

User Interface (UI)

Schedule an Appointment in the SRO

Select User Type

Presenter Name (Executant)

Select Sub Registrar Office

Koramangala, Bengaluru

Select Date of Appointment

<

September 2021

>

S	M	T	W	T	F	S
29	30	31	1	2	3	4
5	6	7	8	9	10	11
12	13	14	15	16	17	18
19	20	21	22	23	24	25
26	27	28	29	30	1	2

Continue



Success

Your appointment for 15th November 2021, is successfully scheduled.
Please reach the office 15 minutes early for a smooth registration experience.

Close

14.4 Status Tracking

Status Tracking should be available at every step of the registration process to inform the citizen on the status of application and to track timely completion of registration services in all SRO offices. It keeps track of various things such as time taken for registration of a particular

document, scanning of a document etc..

Status tracking would be displayed in LED display board available in each SRO office.

In addition to the information above, please find a detailed requirements document attached:

<https://csgkarnataka.sharepoint.com/sites/ULMS/Knowledge%20Base/Forms/AllItems.aspx?id=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS%2FStatus%20Tracking%20Module%20FRS%20V%2E02%2Epdf&parent=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS>


Please use the above link to access Status Tracking detailed FRS.

15 APPLICATION REVIEW AND ALLOCATION TO DEO BY SR

i. **Brief Description**

As per the time slot booked by the Parties, they visit the Sub-Registrar Office and present the documents Infront of the Sub-Registrar. The Sub-Registrar shall start the registration process and perform the verification of Executant, Identification of Party, Seller/Purchaser Name, Classification of Document, Full Stamp Duty & Registration Fee Paid.

After the verification is completed by Sub-Registrar then the allocation to DEO shall be done for the assessment of application. Sub registrar shall allocate the received applications based on the slot timing which will allow the DEO to process the application for the verification of Parties, capture the photograph and biometrics of all the parties, generate summary report and endorsement to present for approval by Sub Registrar.



ii. Functional Step by Step Process

1. **SRO Login:** The authorized Sub Registrar, shall login in the system by entering Username and Password provided to them by the department along with the biometric verification
2. The Sub-Registrar shall start the registration process and perform the verification of Executant, Identification of Party, Seller/Purchaser Name, Classification of Document, Full Stamp Duty & Registration Fee Paid
3. After the verification is completed by the Sub-Registrar then the allocation to DEO shall be done for the assessment of application
4. Sub registrar shall allocate the received applications based on the slot timing
5. SR will select DEO (Data entry operator) from the dropdown, to allocate for the pending applications. After DEO selection, SR shall select Allocate button for successfully allocating the application

6. The system shall check if more application is pending, In case application is pending then the system shall redirect to allocate application based on slot timing otherwise process will end

Function:

Application Allocation to DEO: by SRO

Use Case Name	Application Review and Allocation to DEO by SR
XRef	13 – Application Review and Allocation to DEO by SR
Trigger	Sub Registrar start verifying the Applications
Precondition	Document Presentation by the Applicant to the Sub-Registrar
Basic Path	1. Sub Registrar login in the system 2. Sub Registrar verify the application and could accept or not accept the application for the document registration 3. Sub Registrar select the application allocation option 4. SR allocate verified applications to DEO (Data entry operator) 5. System checks if more application allocation is required
Alternative Paths	N.A.
Post condition	DEO process the application submitted for the document registration
Exception Paths	N.A.
Other	N.A.

Note: The Sub-Registrar shall possess the authority to withdraw the application from the DEO before the registration process is initiated by the user.

User Interface (UI)

Presentation Verification	Yes	No
Document is Presented by Tanmay Sinha	☐	☐
Confirm Date of Execution	☐	☐
Confirm Seller and Purchaser Name	☐	☐
Check Proper Identification and Schedule of the Property	☐	☐
Confirm Voluntary Execution by the Parties	☐	☐
Check the Classification of Document	☐	☐
Check Market Valuation and Stamp Duty Payable	☐	☐
Full Amount Paid	☐	☐
All the required documents are provided	☐	☐
Deed document presented is same as the document uploaded	☐	☐
All corrections and Interlineation are attested	☐	☐

Document accepted for Registration

Not Accepted for Registration


Allocate application to DEO

S.No.	Application Number	Date	Time	Application Type	Status	Data Entry Operator	Action
01	AP212001335016514	08-08-2021	09.00AM	Immovable Property Registration	Allocation Pending	Select	<button>Allocate</button>
02	AP212001335016514	08-08-2021	09.00AM	Movable Property Registration	Verification Pending	DEO 1	<button>Verify</button>
03	AP212001335016514	08-08-2021	09.00AM	Immovable Property Registration	Verification Pending	DEO 2	<button>Verify</button>
04	AP212001335016514	08-08-2021	09.00AM	Immovable Property Registration	Verification Pending	DEO 3	<button>Verify</button>
05	AP212001335016514	08-08-2021	09.00AM	Movable Property Registration	Verification Pending	-----	<button>Verify</button>

15.1 Application Re-Allocation to DEO

i. Brief Description

If it is required, the Sub-Registrar shall possess the authority to reallocate the application to another DEO.



ii. Functional Step by Step Process

1. **SRO (Sub Registrar officer) Login:** The authorized SRO from the department shall login in the system by entering Username and Password provided to them by the department along with the biometric verification
2. The SRO shall select the application allocation option, after which the system will display all the allocated applications. SRO shall select the assigned application for reallocation to the DEO
3. SRO will select respective DEO (Data entry operator) from the dropdown, to reallocate the application. The application shall be successfully reallocated to the DEO in the system

16 DOCUMENT REGISTRATION

1. After Document Review by the SR, the application is allocated to DEO. The authorized DEO from the department shall login in the system by entering Username and Password provided to them
2. The DEO shall select the application as per the scheduled time slot-based on FIFO (first in first out) process
3. DEO will then check if all the parties are present, the party present in the office should voluntarily provide their photos and biometric authentication. In case the documents are valid and voluntary execution is successfully done, DEO will start the Document Registration process
4. The system will display application details and property details:
 - In application details system will display: Application number, submission date & application type
 - In property details system will display: Property data from Bhoomi & Aligned databases and Court order details
5. The DEO after capturing the party details, shall generate Document Summary, Endorsement, Receipt, EC and Acknowledgement Slip

Registration: Document Registration

Use Case Name	Registration: Document Registration
XRef	14 Registration: Document Registration
Trigger	The DEO selects the application for starting the registration process
Precondition	Application must be allocated to DEO by SR
Basic Path	1. The DEO selects the application to continue the document registration process 2. The DEO will only capture the Party Details which includes photograph, Biometrics and eKYC 3. After the party details capture the DEO shall print the Document Summary, Endorsement, Receipt, EC and Acknowledgement Slip
Alternative Paths	N.A.
Post condition	1. The Sub-Registrar shall be the Approving authority for Document Registration and during the complete process the application will be sent to SR for approval as well as for the eSignature on the scanned document
Exception Paths	N.A.
Other	N.A.

16.1 Registration: Party Details

i. Brief Description

For property registration there shall be two parties: Claimant which may be buyer, shareholder, co-owner, or transferee and second party would be executant which may be seller, shareholder, co-owner or transferer. To verify the party some of the below details will be checked by DEO:

➤ Name, Age, Gender, Address, PAN, and Profession

In the party detail section, the DEO shall be required to verify the details of the following parties involve in the property registration process:

- i. Presenter (Only 1) maybe either claimant or executant
- ii. Claimant (1 or multiple)
- iii. Executant (1 or multiple)
- iv. Witness (Minimum 2)

UIDAI Guidelines for Capturing Fingerprints:

- The fingers have to be positioned correctly on the platen to enable capture. There should be no direct light shining on the platen. Use the Indicators on fingerprint devices for positioning of fingers. The fingers should be placed in right direction on the device.
- Use a lint free cloth periodically to clean the platen of the fingerprint device for good fingerprint capture
- Check devices periodically for scratches, out of focus images, only partial images getting captured. In case any such problem is noticed, then report to your Supervisor/HQ and request for change of equipment.
- Fingerprints cut off, wet/smudged fingerprint; very light prints due to insufficient pressure will result in poor quality. The party's hands should be clean (no mud, oil etc.). Ask citizen to wash hands with water and soap, if necessary.
- The fingers should not be excessively dry or wet. Moisten with a wet cloth or dry finger with a dry cloth
- The Party should ensure that the fingers are placed flat and till the top joint of the finger is placed well on the scanner. The top of the fingers should be within the platen area and not outside the defined area.
- The operator should check the actionable feedback when capture fails. Some actionable feedbacks provided by software are:
 - Number of fingers present does not match with expected number of fingers
 - Finger not positioned correctly
 - Too much Pressure (duty cycle)
 - Too little pressure
 - Central region missing
 - Excessive moisture (wetness)
 - Excessive dryness
- The operator should visually check the image for quality and for typical problems. In case there are problems go back to steps above to retry the capture.

- When image quality is pass or if maximum number of captures are exhausted, move on to the next step
- Fingerprints are best captured in standing position
- Make sure your own fingerprints do not get mixed with the party's fingerprints
- Operators can carefully put small pressure on the party's fingers to capture the fingerprints but always make sure not to mix your own fingerprints

User Interface

< Back

Presentation (Sub Registrar)

Biometric Capture (DEO)

Summary Report Generation (DEO)

Verification of Summary Report (SR)

Communication Slip Generation (DEO)

Approval (SR)

Receipt and Endorsement (DEO)

Scan and Upload Document (DEO)

Acknowledgement Slip (DEO)

Generate EC (DEO)

Document Registration

DOCUMENT NUMBER
P-1700

DATE OF PRESENTATION
08-08-2021

APPLICATION TYPE
Property Registration

Party Details

Party Type

Executant

Select Individual for Appearance

ABC

Party eKYC


☐ Party Present

PARTY TYPE : EXECUTANT

INDIVIDUAL/ORGANIZATION : ORGANIZATION

ORGANIZATION NAME: ABC CORPORATION	ORGANIZATION ID: 1234567890	REGISTERED ADDRESS: BANGALORE	PAN/TIN/TAN: ABCDE1234A
REPRESENTED BY:			
FIRST NAME: TANMAY	MIDDLE NAME: -	LAST NAME: SINHA	AGE: 26 YEARS
SEX : MALE	ADDRESS: RANCHI, JHARKHAND	PAN : ABCDE1234A	PROFESSION : DESIGNER
PHOTOGRAPH		LEFT THUMB	
CAPTURE		CAPTURE	

Document Registration – DEO – Party Details



ii. Functional Step by Step


1. **DEO (Data Entry operator) Login:** The authorized DEO, from the department shall login in the system by entering Username and Password provided to them by the department to check the party details
2. The DEO will select the application as per the scheduled time slot-based on FIFO (first in first out) process
3. DEO will then check if all the parties are present, then the system shall display the party details for the verification
4. The DEO shall select from the below party type from the dropdown in the system:
 - Presenter
 - Claimant
 - Executant
 - Witness
5. The system will display application details and party details:
 - **In application details system will display:** Application number, submission date & application type
 - **In party details system will display:** Name, Age, Gender, Address, PAN & Profession
6. Based on party type selection, DEO will select individual for appearance. DEO will then match the party detail with respect to deed document, in the system. Then the system will check if the party is witness in case the party is not witness then the DEO will proceed with e-KYC and capture the photograph in the system otherwise DEO will check if all parties are verified. In case all parties are verified then DEO will save and continue with the process in the system otherwise DEO will select from the party type option for verification of the party
(Note: In case, the of appearance of parties at different times, the document shall be kept pending for appearance of the party. Kindly refer **section 24.6** for 'Late Appearance' under 'Exceptional Cases Module')
7. After capturing photograph of the party, system will prompt if recapture of photograph is required. In case recapturing is required then the DEO will capture photograph again in the system otherwise DEO will capture the Biometrics of the party
8. After capturing Biometrics of the party, system will prompt if recapture of Biometric is required. In case recapturing is required then the DEO will capture biometrics of the party again in the system otherwise DEO will check if all parties are verified. In case all parties are verified then DEO will save and continue with the process in the system otherwise DEO will select from the party type option for verification of the party

Note: eKYC shall be mandatory for all the Parties which include Presenter, Claimant, Executant and Consenting Witness except for the Identifiers (Witness)

16.2 Registration: Document Summary & Print

i. Brief Description

For all the Parties except Identifiers eKYC, Photo and Biometric shall be captured. After this, the Document Summary report is generated and signed by the DEO and given to the Presenter to verify the data entered in the system are proper or any correction are needed. After Presenter's verification and signature, Document Summary is verified by the FDA/SDA. If it is found correct, the report will be given to Sub Registrar for approval.



ii. Functional Step by Step Process

1. Preview of the Document Summary report will be displayed to the DEO along with the Application Details consisting of Pending Number, Date of Execution and Application Type
2. The DEO shall send the Document Summary to the Sub-Registrar for Approval
3. The Sub-Registrar evaluate the Document Summary based on the Deed Document Uploaded
4. The Sub-Registrar shall take the decision based on the document review; three decisions could be taken by SR:
 - I. Register and Send to DEO
 - II. Kept the Document Pending
 - III. Refused Registration

(Note: If the SR takes the decision to **Keep the Document Pending**, then he/she has to choose from among the following options (reasons) which shall get recorded in the Minute Book

- a. Pending for determination of undervaluation, referred to District Registrar u/s 45A of KS Act 1957
- b. Pending for short levy of Stamp Duty, impounded u/s 33 of KS Act 1957
- c. Pending for condonation of delay, u/s 25 of Registration Act 1908, document exceeding 4 months from the date of last execution read with Rule 52 of Registration Rule 1965
- d. Pending for appearance of the parties, u/s 34 of Registration Act 1908
- e. Pending for private attendance u/s 31 of Registration Act 1908)

(Note: If the SR takes the decision to **Refuse the Registration**, then he/she has to choose from among the following options (reasons) which shall get recorded in the Minute Book

- a. Refused document registration for denial of execution u/s 35 of Registration Act 1908
 - b. Refused document registration for property not belonging to jurisdiction of the Sub Registrar u/s 28 of Registration Act 1908
 - c. Refused document registration for document presented by a wrong person u/s 32 of Registration Act 1908
 - d. Refused document registration for exceeding 8 months from the date of execution u/s 25 of Registration Act 1908
 - e. Refused document registration for not fulfilling the conditions of section 21 of Registration Act 1908)
5. In case, document is sent back to DEO for Registration, then Print of the Document Summary report will be taken by DEO and given to the Presenter for verification
 6. Upon verification and signed by DEO, Presenter, and FDA/SDA, Sub Registrar will approve and sign the Document Summary Report

Document Summary Report will have the following details:

1. **Document Number Pending generated**
This will be a system generated number as and when the user starts the Document Registration

For example, P – 1700. “P” indicates pending number for the document which is under process of Registration. “1700” indicated the continuation number of the documents processed for the Registration from the beginning of the Financial Year.

Book Number, Number of Pages of Document, Nature of Deed and Stamp Article details are already mentioned by the applicant in the Online Application, the same information shall be displayed in the Document Summary Report

Document Details :	
Document Number :	P - 1700
Book :	Book-1
No. of Pages :	41
Nature of Deed :	Sale
Stamp Article :	Conveyance
Execution Date:	19-07-2021

2. Execution Date

The DEO shall enter the Date of Execution on the Document Summary page as per the Deed document

3. Stamp Duty Payment Details

In case of offline, the DEO shall enter the Stamp Duty Payment Details from the Challan of Khajane 2 or eStamp Portal of Stock Holding Corporation of India Limited (SHCIL).

In case of Online, Payment Details shall be auto fetched from the system and DEO shall verify the same

Stamp Duty Payment Details :			
Sr. No.	Payment Mode	Amount (In Rs.)	DD/Challan Description
[1]	By Cash	5000.00	

4. Receipt Payment Details

User shall enter all details with respect to Receipt by looking into the Challan submitted

- Receipt Number - indicates the continuation number of the documents processed for the Registration from the beginning of the Financial Year.
- Date of Receipt – Date of payment of Khajane2 Challan or Date of payment at SRO
- Amount Paid By – This shall be auto fetched from the system
- Total Receipt Amount (In Rs.) – If it is Online, Receipt Amount shall be auto fetched from the system. If it is offline, DEO shall enter the Receipt Amount

Receipt Payment Details :**Receipt Number : 25**

Date of Receipt : 11-11-2021 06:18:25 PM

Amount Paid By : Mrs Raghav

Total Receipt Amount (In Rs.): 1105.00

Fees Description *

[1.] Registration Fee

[2.] Scanning Fee

Amount (In Rs.) **

[1.] Rs. 1105.00

Amount (In Rs.) *

1000.00

105.00

Payment Mode **

By Cash

Description **

Paid in Cash Rs.1105

5. Index II Village, Property Type, Boundary Details, Valuation Details, All Duties (Consideration, Market Value, Government Duty, Cess Duty, Additional/Surcharge Duty and Total Stamp Duty), Schedule Description, Party Details, Identifying Parties are already mentioned by the applicant in the Online Application, the same information shall be displayed in the document summary

6. Property Number Details

Property Number Details are already mentioned by the applicant in the Online Application, the same information shall be displayed in the document summary report.

In case of Agriculture Land,

- Survey Number
- Hissa Number
- Pyki Number
- Sketch Number

In case of Non-Agriculture Land,

- Site Number
- Corporation Number
- Municipal List Number
- Property Number
- Flat Number
- Converted Survey Number
- Apartment Number

Index II village : Chokkanahalli Property Type : BBMP

Boundary Details :

[East] :Open towards Open Space in Tower -'B'/Wing-'B' of 'NIKOO HOMES-II' [West] :Staircase in 13th Floor and Open towards Open Space in Tower-'B'/Wing - 'B' of 'NIKOO HOMES-II'

[North] :Corridor in 13th Floor in Tower- 'B'/Wing -'B' of 'NIKOO HOMES-II' [South] :Open towards Open Space in Tower-'B'/Wing - 'B' of 'NIKOO HOMES-II'

Valuation Details : Estimated value of the property based on the discription available in the document/application as per guidelines. Property Description Name of the Presenter/Applicant: Description of Property :Residential Apartment bearing No. B-1305 in 29th Floor of Tower "B"/ Wing "B" in the project viz., NIKOO HOMES-II, constructed on Schedule A Property and forming part of development in BHARTIYA CITY and apartment having 1099 sq ft of carpet area and 208 sq ft of sit-out/Balcony/Deck, Utility and External Wall Area and 327 sq ft of proportionate in common areas and totally measuring 1634 sq ft of super built up area, with right to use ONE covered car parking space/s in the Ground/Basement Level Article :Conveyance District :Gandhinagar Taluk :Yelahanka (Yelahanka 2) SRO :Byatarayanapura Location of Property : Bharathi City ,Chokkanahalli Property Type Type = Residential - Flat/Apartment Estimated Guideline Rate = Rs. 0 /Sq.Feet Construction = Madras Roof, Kodapa roof, Mangalore Tiles, Brick wall/Mud wall, AC Sheet, red oxide flooring and country wood doors and windows. Estimated Guideline Rate for Construction = Rs. 1070.0222 /Sq.Feet Area Built-up Area = 1634 Sq.Feet ____ Built up Component Built-up Area = 1634 Sq.Feet EGR for Built-up after depreciating 0 % = Rs.1070.02 /Sq.Feet Value of Built-Up Area = Rs.1748412.68 ____ Total Estimated Market Value(EMV)of the Property = Rs.1748413 (Rs. Seventeen lakh forty eight thousand four hundred and thirteen only)

****All Duties below are in Rs.****

Consideration : [3268000.00] Market Value : [7305100.00] Govt.Duty : [365260.00]

CESS Duty : [36526.00] Additional : [7306.00] Stamp Duty : [409092.00]

Land Mark : Department / Property Type: BBMP , Index-II Village: Chokkanahalli , Word Name: BBMP Word No. 5, Habli Name: Yelahanka 2.

Schedule Description

Schedule Type	Area	Description	Bhoomi Parties
C	Schedule Area :1634 Sq.Feet	Residential Apartment bearing No. B-1305 in 29th Floor of Tower 'B' / Wing 'B' in the project viz., NIKOO HOMES-II, constructed on Schedule A Property and forming part of development in BHARTIYA CITY and apartment having 1099 sq ft of carpet area and 208 sq ft of sit-out/Balcony/Deck, Utility and External Wall Area and 327 sq ft of proportionate in common areas and totally measuring 1634 sq ft of super built up area, with right to use ONE covered car parking space/s in the Ground/Basement Level together with 310 sq ft of undivided share in the Schedule A Property being part of Municipal No. 6/1 ((comprised of Sy Nos. 35(p), 38(p), 48, 49(p) and 50(p)) and situated at Chokkanahalli Village in Municipal Ward No. 5 of Jakkur, Yelahanka Hobli, Bengaluru North Taluk Schedule Allocated To : Gopi Krishnan . T.P S/o T.P. Haridas . Sowmya, C.V W/o Gopi Krishnan T.P.	

Property Number Details

Property Number Type	Numbers	Add. Description
Site No	6/1	
Corporation No	6/1	
Municipal List No	6/1	
Property No	6/1	
Flat No	B-1305	
Converted Survey No	35(p), 38(p), 48, 49(p) and 50(p))	
APT No	B-1305	

Party Details :

Sr. No.	Party Name , Age , Address , Profession	Party Type	Is Executor	Is Presenter	Admission Date	Sec. 88 Exemption	Photo	Thumb	

1.	Gopi Krishnan . T.P S/o T.P. Haridas , ಡಾ° ... r/o :- Bangalore. Male.	Claimant	Yes					
2.	Sowmya. C.V W/o Gopi Krishnan T.P r/o :- Bangalore. . Female	Claimant	Yes					
3.	Gopi Krishnan . T.P S/o T.P. Haridas ಡಾ° ... r/o :- Bangalore. Male.	Presenter	Yes	Yes				
4.	M/s BHARTIYA URBAN PRIVATE LIMITED (formerly known as M/s Bhartiya City Developers Pvt Ltd..) rep by its duly . Authorised Signatory and Manager- Legal: Mr. Ramachandra A K rep by his SPA Holder Thyagaraj T.K ... r/o :- Bangalore. . Male.	Executant	Yes					

Identifying Parties :

Sr. No.	Witness Name	Address	Age	Profession
1.	Chethan	r/o :- No. 20, V M Road, Bangalore		
2.	R. Ashok	r/o :- No. 1/5, Palace Road, Bangalore		

Signature of Presenter

Signature of Operator


Signature of SDA/FDA

- After taking the print of the Document Summary report that document will be verified and signed by the Presenter from party side and signed by the Operator (DEO) and FDA/SDA from Department side and sent to the Sub Registrar for signature

16.3 Registration: Endorsement & Print

i. Brief Description

On verification of the Summary Report, if all the details found correct Sub Registrar approves for Registration. Upon approval of the Sub Registrar, system will generate document number and Endorsement will be printed. Signature of the Presenter, Claimant, Executant, Witness and Sub Registrar shall be taken on the physical copy of the Endorsement.




ii. Functional Step by Step Process


1. On Approval by the Sub Registrar, the Document Number will be generated from the system.
2. Document details such as Document Number, Execution Date and Application Type will be displayed on the screen
3. Endorsement will be generated and Printed
4. Signature of the Presenter, Claimant, Executant, Witness and Sub Registrar are obtained on the physical copy of the Endorsement.

4. Party Information Endorsement

- Party Information Endorsement will have the Presenter details such as Presenter Name, Photograph and Signature followed by Sub Registrar Signature.
- Execution Admission by the Claiming Parties which includes Claimant Name, Photograph and Signature followed by Sub Registrar Signature.
- Execution Admission by the Executing Parties which includes Executor Name, Photograph and Signature followed by Sub Registrar Signature
- If appearance of the Party as per section 88 exemption is given and the particulars of the exemption letter will be recorded

ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು	ಫೋಟೋ	ಹೆಚ್ಚುತ್ತಿರುವ ಗುರುತು	ಸಹಿ
	ಶ್ರೀ K. Narayanagowda S/o H. Kempalaih			

ಬರೆದುಕೊಟ್ಟಿದ್ದಾಗಿ(ಮುಖ್ಯ ಪೂರ್ಣ/ಭಾಗಶಃ ಪ್ರತಿಫಲ ರೂ..... (ರೂಪಾಯಿ)..... ಮುಖ್ಯದ್ದಾಗಿ)
ಒಪ್ಪಿರುತ್ತಾರೆ



ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು	ಫೋಟೋ	ಹೆಚ್ಚುತ್ತಿರುವ ಗುರುತು	ಸಹಿ
	K. Narayanagowda S/o H. Kempalaih (ಬರೆದುಕೊಂಡವರು)			
2	Mamatha W/o Late H. K. Ramachandraswada (ಬರೆದುಕೊಂಡವರು)			Mamathagowda M.V.


5. Identifying Witness (Identifiers) Endorsement

Identifying Witness Endorsement will have the Name, Address and Signature of the two Witness followed by Sub Registrar Signature.

ಗುರುತಿಸುವವರು


...6.....ನೇ ಪ್ರಯತ್ನ ಪಡ್ತಾವೆಂದು ಸಂಖ್ಯೆ: 105
20-21

ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು ಮತ್ತು ವಿಳಾಸ	ಸಹಿ
1	Murali, No. 8, Allur Layout, Yelahanka Town, Bangalore.	
2	Ashwath Kumar, K No. 24 6th B Cross, 3rd Main Road, Domlur Layout, Bangalore.	


ಹಿರಿಯ ಉಪನಿರ್ದೇಶಕರಾದ
ಕಾಂತ್ಯಾಚಾರ್, ಬೆಂಗಳೂರು-9

6. Registration Certificate as per Section 60 of Registration Act

Registration Certificate will have the Book Number, Document Number which consists of Office name in Trilateral Letters i.e., Abbreviation of the Sub Registrar's Office Name, Book Number and Serial Number of the Document of the year and Date followed by Sub Registrar Signature



Designed and Developed by C-DAC, ACTS, Pune

16.4 Registration: Scan & Upload


i. **Brief Description**

For document registration, after verifying the property details, party details, property schedule, market valuation, stamp duty, fee calculation and payment details, DEO will scan and upload the registered documents and annexures. DEO will scan the below mentioned document, after scanning the document successfully DEO will upload the document in the server.

- a. Registered Document
 - Deed
 - Endorsement
- b. Annexures

The user shall have two separate sections to upload the Registered Deed document and Annexures, all the annexures shall be scanned and uploaded at once.

Document Registration – DEO – Scan & Upload



ii. Functional Step by Step Process

1. DEO will scan and upload the below mentioned document through the scanning system in the mentioned order:
 - c. Registered Document
 - Deed
 - Endorsement
 - d. Annexures
2. DEO will then check if rescanning is required. In case rescanning is required then DEO will again scan the required documents otherwise DEO will save the documents. The system will display message “Scanning Complete”, DEO will then preview the scanned documents
3. DEO will then take confirmation of scanned document with the concern parties. In case concern parties does not agree with the scanned document then DEO will correct the discrepancies in the scanned document in the system
4. In case concern parties agree with the scanned document then DEO will upload the scanned document and the document will be stored in the server. After scanned document will be successfully uploaded in the system, system will display message “all the documents have been successfully uploaded” and generate unique document number

User Interface

[< Back](#)

Presentation
(Sub Registrar)

Biometric
Capture (DEO)

Summary Report
Generation (DEO)

Verification of
Summary Report (SR)

Communication Slip
Generation (DEO)

Approval
(SR)

Receipt and
Endorsement (DEO)

Scan and Upload
Document (DEO)

Acknowledgement
Slip (DEO)

Generate EC
(DEO)

Document Registration

DOCUMENT NUMBER	DATE OF PRESENTATION	DATE OF EXECUTION	APPLICATION TYPE
GAN-1-01458-2021-22	08-08-2021	06-08-2021	Property Registration

Scan and Upload Document

Registered Document

The registered document consist of the deed document and endorsement . Press scan to continue.

Scan

Preview

Annexure

All the annexures needs to be scanned and uploaded. Press scan to continue.

Scan

Preview

Upload All documents


Continue

188 | Page

16.5 Registration: Digital Signature by SR

i. Brief Description

The Sub-Registrar shall be required to digitally sign all the scanned documents which includes scanned deed document and annexures.




ii. Functional Step by Step Process

1. After the deed document and annexures are scanned and uploaded by the DEO, the application is sent to SR for Digitally Signed the file
2. Sub-Registrar shall receive the request from the DEO for Digital Signature
3. The Sub-Registrar shall trigger the Digital Sign and the complete document shall be digitally signed by the SR
4. After which, Sub-Registrar shall send back the application to DEO to continue and print the EC for the current transaction made in the system

16.6 Registration: Encumbrance Certificate & Print

i. Brief Description

Encumbrance Certificate is the certificate showing the particulars of transaction taken place over a property. During the Registration process, the data i.e., Party Information, Property Information, Valuation and Consideration, Date of Execution, Date of Registration and Document Number along with Book Number are stored in Index II database. From this Index II data Encumbrance Certificate in Form Number 15 will get generated.



ii. Functional Step by Step Process

1. During Registration process, after entering all the data, the data will get stored in the Index II Form database for the purpose of EC generation

2. DEO shall generate the EC as per the Index II data
3. System shall display the document details for the Encumbrance generation
4. Print of the Encumbrance Certificate shall be given to the Party as a confirmation of Registration

Encumbrance Certificate will have the following details:

1. Application Number, Encumbrance Certificate printed Date and Time and Certificate Number
2. **Form Number 15** – Encumbrance Certificate shall get generated in the form “Form Number 15” followed by Proforma Number 15 (Rule 148)
3. Details of the Property which includes Property Number and Extend of the Property which has been entered in the Online application
4. Table of EC Proforma:
 - Serial Number
 - Property Particulars – It includes Village Name and Property Schedule Description
 - Date of Registration
 - Nature of Document and Value in Rupees
 - Particulars of Parties
 - Executing Party
 - Claiming Party
 - Number of Pages of Deed document
 - Document Reference Details
 - Document Number – Trilateral Code of the Office Name followed by Book Number, Document Number and Year of Registration
5. Signature of the FDA/SDA and Sub Registrar
6. Disclaimer shall be printed on the EC document as per the Proforma

User Interface

[< Back](#)

Document Registration

DOCUMENT NUMBER

DATE OF PRESENTATION

DATE OF EXECUTION

APPLICATION TYPE

GAN-1-01458-2021-22

08-08-2021

06-08-2021

Property Registration

Ecumbrance Certificate

1/3


Index Entry

ಕ್ರಮ	ಎ) ಸ್ಥಳದ ವಿವರ	ಬಿ) ದಾಖಲಾತಿ ದಿನಾಂಕ	ಸಿ) ದಾಖಲಾತಿ ವಿವರ (ರೂ.)	ಡಿ) ದಾಖಲಾತಿ ವಿವರ		ಇ) ದಾಖಲಾತಿ ವಿವರ	ಫ) ದಾಖಲಾತಿ ವಿವರ
(1)	(2)	(3)	(4)	ಉತ್ತರ ಪಕ್ಷ	ಉತ್ತರಾಧಿಕಾರಿ	ಒ. & ಸಹಿ	(7)
1	Land situated at Kodi Chikkanahalli Property Schedule Description: (LAND MARK) Kodi chikkanahalli (EAST) Site No. 25 (WEST) Road (SOUTH) Site No. 47 (NORTH) Site No.	24/03/2015	Article Name: DTD Market Value: 0 Consideration Amount: 200000	Mr. Ganapati Prabhakar Hegde	For Canara Bank, rep By its Manager Kodandaramapuram	BMH/0701	BMH-1-09519-2014-15

16.7 Registration: Acknowledgement slip and Registration complete

i. Brief Description

After registration and scanning of the document and EC generation, system will generate acknowledgement slip and it will be printed. Signature of the FDA/SDA and Sub Registrar are obtained having deed document is scanned and handed over to presenter then the presenter will sign on the physical of the acknowledgement slip after receiving the deed document.



ii. Functional Step by Step Process

1. After scanning and uploading the document and EC generation, system will generate acknowledgement slip and will display below document details:
 - a. Document Registration
 - Application Number
 - Date of Submission
 - Application Type

Document Registration

APPLICATION NUMBER
GAN-1-01458-2021-22

DATE OF SUBMISSION
08-08-2021

APPLICATION TYPE
Property Registration

b. Acknowledgement Slip

- Document Number
- Date of Registration
- Date of Scanning

➤ Time and date will be auto generated by the system

2. DEO will preview the Acknowledgement Slip in the system and take the print of the slip. Signature of the FDA/SDA and Sub Registrar are obtained, and original deed document will be handed over to presenter
3. Then the presenter will sign on the physical copy of the acknowledgement slip which will certify that no documents submitted by the parties are remaining with the sub registrar after receiving the original deed document
4. As the DEO print Acknowledgement Slip and close the window, the Document Registration will be completed, and J-slip will be sent to BHOOI in case the document registration involves an agricultural property

User Interface

Document Registration

DOCUMENT NUMBER
GAN-1-01458-2021-22

DATE OF PRESENTATION
08-08-2021

DATE OF EXECUTION
06-08-2021

APPLICATION TYPE
Property Registration

Acknowledgement Slip



16.7.1 Verify document

This is a service which would be provisioned for guest user on home screen of citizen landing page. Through this service citizen can verify the authenticity of document which is them if it was

registered in KAVERI or KAVERI 2 post 2003. This helps in avoiding forgery of document or tampering or misleading of purchaser

In addition to the information above, please find a detailed requirements document attached:
<https://csgkarnataka.sharepoint.com/sites/ULMS/Knowledge%20Base/Forms/AllItems.aspx?id=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS%2FVerify%20Document%20Module%20FRS%20V%2E02%2Epdf&parent=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS>

Please use the above link to access Verify document detailed FRS.


17 ENCUMBRANCE CERTIFICATE (EC) SEARCH

i. Brief Description

Encumbrance Certificate is the certificate which shows the previous transactions of Registrations on the Property. It can be searched in case of Agriculture Land based on Duration (From Date and To Date), District, Taluka, Hobli, Village Name, Survey Number, Hissa Number, Pyki Number, Property Number Type, Previous Property Number, Present Property Number along with Extent of the Property and Boundaries. It also can be searched with reference to seller and purchaser.

In case of Non-Agriculture Property, it can be searched based on the Duration (From Date and To Date), District, Taluka, Hobli, Village Name/Town/Ward, Road Name, Property Number Type, Previous Property Number, Present Property Number, Extent of the Property and Boundaries. It also can be searched with reference to seller and purchaser.

EC Search



ii. Functional Step by Step Process

1. Applicant shall select encumbrance certificate, after which the applicant will get an option to select below option:
 - Search by Blockchain key: The applicant shall enter Blockchain ID/ Card Number and search. The system shall display search result and continue with the process
 - Search by Document details: The applicant shall select District, Taluka, Hobli, Village. After which system shall fetch data from Master Database
2. The user shall enter boundary details i.e., east, west, north & south and description of the property
3. The user shall select Property Number type and enter property number
4. Add Property Details:

Case 1:

In case the user selects 'Yes' to add property details then the user shall select Property Number type and enter property number

Case 2:

In case the user selects 'No' to add property details then the system will send OTP to the registered mobile number. Applicant will enter OTP received and verify

5. OTP Verification:

Case 1:

In case OTP is verified by the system then the applicant will search for EC and system will generate Index II. The applicant will accept the result and proceed


Case 2:

In case OTP is not verified by the system then the applicant will be asked to enter OTP again

17.1 EC Payment

i. Brief Description

Once the Encumbrance Certificate is found, user shall be directed to do the Payment to get the Digitally Signed Encumbrance Certificate.



Functional Step by Step Process

1. Applicant shall select Payment Details, after which the system will display below details:
 - Application Fee
 - Search Fee
2. The system will display Application Number and Application Type
Application Number will be of the format **BMH-EC-A-017566-2018-19**. i.e, Tri Lateral of the Sub Registrar Office (**BMH**) followed by Type of Application (**EC**) followed by Application first letter (**A**)

followed by serial number of the application **(017566)** followed by present Financial Year **(2018-19)**

3. The user shall enter Remitter Name and select SRO office name from the drop down. The user will then proceed to payment. System shall be redirected to Khajane-2
4. Payment Confirmation:

Case 1:

In case Payment is confirmed then the system will generate transaction receipt. Applicant will be able to print the receipt


Transaction Receipt

Transaction Reference No	013018013550891550
Bank Name	HDFC Bank
Bank Reference No	439943102
Amount (Rs.)	145
Transaction Execution Date & Time	2018-01-30 14:03:48.469
Mode Of Payment	Net Banking
Status	Payment received at payment gateway


Case 2:

In case Payment is not confirmed by the system then the applicant will be redirected to retry and proceed for payment again

17.2 EC Online Application Summary

i. Brief Description

Once the payment is done, the application details will be displayed on the system for the applicant to verify the details entered.




ii. Functional Step by Step Process

1. The document summary will be displayed to the user and the elements of the summary page will be displayed by the system
2. System will display application details such as application number & application type and applicant details such as Name and Aadhar number of user registered in the system.
3. System will display Property details with description, Payment details and transaction receipt details in document summary
4. Applicant will be able to see the preview of the application and unsigned EC. Then it will be sent to SRO for Approval

17.3 EC Generation

i. Brief Description

An EC is the certificate showing the list of transactions on the property mentioned in “Form 15”. If no transactions are found, system generates nil EC in the form of “Form 16”. This report is signed by SR.



ii. Functional Step by Step Process

SDA

- 1.Applicant shall submit the application for online EC.
- 2.The application shall be scrutinized by the SDA as per the parameters entered by the applicant in the system
- 3.As per the details entered in the application SDA will prepare the EC
- 4.If it is found correct, SDA shall view and download the EC
- 5.After downloading, SDA shall Digitally Sign the EC by using Adobe Acrobat
- 6.After signing the EC, SDA shall update the document with remarks and send it to FDA for further Approval

FDA

- 1.FDA shall receive the digitally signed EC from SDA
- 2.FDA shall validate the EC details as per the parameters entered by the applicant in the system
- 3.If it is found correct, FDA shall view and download the EC. If it is not found correct FDA shall revert the application back to the SDA
- 4.After downloading, FDA shall Digitally Sign the EC by using Adobe Acrobat
- 5.After signing the EC, FDA shall update the document and send it to Sub Registrar for further Approval

Sub Registrar

- 1.Sub Registrar shall receive the digitally signed EC from FDA
- 2.Sub Registrar shall validate the EC details as per the parameters entered by the applicant in the system
- 3.If it is found correct, Sub Registrar shall view and download the EC. If it is not found correct Sub Registrar shall revert the application back to the FDA
- 4.After downloading, Sub Registrar shall Digitally Sign the EC by using Adobe Acrobat
- 5.After signing the EC, Sub Registrar shall update the document and send it to the Applicant
- 6.Applicant shall view and download the Digitally Signed EC

18 MISCELLANEOUS DOCUMENT

i. Brief Description

Documents coming under Section 18 of Registration Act which are optional for Registration are considered as Movable Properties. It is also referred as Miscellaneous Documents.

Any of the following documents may be Registered under Section 18 of the Registration Act

- (a) Instruments (other than instruments of gift and wills) which purport or operate to create, declare, assign, limit or extinguish, whether in present or in future, any right, title or interest, whether vested or contingent, of a value less than one hundred rupees, to or in immovable property
- (b) Instruments acknowledging the receipt or payment of any consideration on account of the creation, declaration, assignment, limitation or extinction of any such right, title or interest
- (c) Leases of immovable property for any term not exceeding one year, and leases exempted under section 17
- (d) Instruments transferring or assigning any decree or order of a Court or any award when such decree or order or award purports or operates to create, declare, assign, limit or extinguish, whether in present or in future, any right, title or interest, whether vested or contingent, of a value less than one hundred rupees, to or in immovable property;]
- (e) Instruments (other than wills) which purport or operate to create, declare, assign, limit or extinguish any right, title or interest to or in movable property
- (f) Wills and
- (g) All other documents not required by section 17 to be registered


Movable Property Registration

After Successful login, the user shall be directed to the Kaveri Services page. In Kaveri services page, the user shall be required to select the Property Registration option. Under Property Registration, the user is required to select Miscellaneous Document.

18.1 Property Description

i. Brief Description

In the Property Description function, user is required to enter the Property Type with Description and select the Stamp Article, Stamp – Sub Article and Registration Fee Article. Based on the selectin of Article the Book Number will be auto fetched from the system




ii. Functional Step by Step Process

1. Applicant shall select the Miscellaneous Document under Property Registration option.
2. After selecting the Miscellaneous Document, user shall be required to enter the Property Type along with the Property Description.
3. The user shall select the Stamp Article, Stamp – Sub Article and Registration Fee Article.
4. Based on the selectin of Article the Book Number will be auto fetched from the system.
5. Next, the user shall select “save and continue” to continue the further process of Registration.

18.2 Stamp Duty and Fee Calculation

i. Brief Description

In the Stamp Duty and Fee Calculation function, user shall enter the consideration amount. Based on the consideration amount, system will calculate and display the Government Duty. Along with this, the user shall be asked to enter details with respect to Exemption, Denotation and Number of pages of the Draft Deed document to complete the Stamp Duty and Fee Calculation



ii. Functional Step by Step Process

- i. User shall enter the Consideration Amount. Consideration amount is the total amount involved in the transaction agreed between two parties.
- ii. The system shall display government duty to the user
- iii. **Exempted for the duty:**

Case 1:

- a. In case the user selects 'exemption on stamp duty' then the user will be required to select 'duty exempted' in either 'Percentage (%)' or 'Rupees (₹)' and the value in 'Percentage (%)' or 'Rupees (₹)'
- b. The user will be required to upload exemption certificate issued by the competent authority and enter the certificate number, date, exemption description, denotation amount and Number of pages of draft deed document and annexures
- c. Based on the details entered by the user, the system shall calculate all the duties and will display the total payable amount

Case 2:

- a. In case the user selects denotation if he has paid stamp duty in earlier and subsequent instrument is employed for completion of transaction then duty already paid is denoted and the difference of duty will be calculated by the system automatically
- b. In case the user does not select 'exemption on stamp duty' then the user will be required to enter the denotation amount if it is applicable and Number of pages of draft deed document and annexures, based on that the system shall calculate all the duties and will display the total payable amount

18.3 Party Information

i. Brief Description

The user is required to submit details of all the parties in 'Party Information' section. For property registration there shall be two parties: Claimant who may be the buyer, shareholder, co-owner, or transferee and second party would be the executant who may be seller, shareholder, co-owner or transferer. To identify the party some of the below details required:

- Name
- Name of parent/ husband/guardian/ authority holder
- Age
- Gender
- Profession
- Address

In the party information section, the user shall be required to mention the details of the following parties involve in the property registration process:

- V. Presenter (Only 1) maybe either claimant or executant or both
- VI. Claimant (1 or multiple)
- VII. Executant (1 or multiple)
- VIII. Witness (Minimum 2)

Party Details – Presenter & Executant

Applicant	System

ii. Functional Step by Step Process

- ii. **Select the Party:** The user shall select the 'party' from the below list to enter the party detail
 - a. Presenter
 - b. Executant
 - c. Consenting Witness
- ix. In case the user selects **Presenter option**, then the user shall select from either 'Claimant' or 'Executant' option
- x. In case the user has selected **Executant option**, the system will ask, if the user 'is claimant also?'

Case 1: If the user has selected 'yes' then the system will duplicate the information in the claimant section otherwise it will proceed to next step

- xi. **Select Type of Party:** The user shall select type of party from either individual or Organization option
3. **Organization:** In case the user has selected the Organization option to enter the party details, the system will prompt the user to enter the below information
- e. **Name of the Organization:** The user shall enter the name of the organization
 - f. **Year of Incorporation:** The applicant shall enter the year of incorporation of the organization
 - g. **TAN:** The applicant shall enter the TAN of the organization
 - h. **Registered Address:** The applicant shall enter the registered address of the Organization
 - o If individual is representing an organization, his personal PAN may not be entered
 - o After entering the organization information, the system will prompt the user to enter the authorised signatory information
4. **Individual Information:** In case the user has identified himself as an Individual to enter the 'selected party details'. Then individual option will be selected, and the system will prompt the user to enter below information
- k. **Enter Name:** The user shall enter the first name, middle name, and last name in the system
 - l. **Enter alias Name:** The user shall enter the Alias name in the system
 - m. **Relationship:** The applicant shall select the relationship type from the dropdown
 - n. **Relative Name:** As per the Relationship selected by the user, the system will prompt the user to enter relative name
 - o. **Enter Age (in Yrs.):** The applicant shall enter the age of the party as per the government issued id

- p. **Select Gender:** The applicant shall select the gender of the party Male, Female, and other gender from the dropdown
- q. **Enter Profession of the Applicant:** The user shall enter the Profession of the applicant
- r. **Address Details:** The applicant shall enter House No/Building Name, Street, City/Village, Taluka, District, State, Pin Code
- s. **PAN available:** The system will check for the availability of user's PAN card as per below cases

Case 1:

In case the user selected option to enter PAN then system will prompt the user to enter PAN

Case 2:

In case the user declares that it doesn't possess PAN then the system will prompt the user to upload declaration Form 60/61

Validation: PAN Card number must satisfy the following conditions:

- vi. It should be ten characters long
 - vii. The first five characters should be any upper-case alphabets
 - viii. The next four-characters should be any number from 0 to 9
 - ix. The last character(tenth) should be any upper-case alphabet
 - x. It should not contain any white spaces
- t. **Verify PAN:** The system will verify the PAN number entered by the user. In case the PAN is invalid then the system will redirect the user to enter PAN again

xii. **Represented by Power of Attorney:**

Case 1:

In case the user has not selected 'Represented by Power of Attorney' option then the user will save the details and continue with the process

Case 2:

In case the user has selected 'Represented by Power of Attorney' option then the user shall select either 'Individual' or 'Organization' and enter the details as per below option:

- 3. **Individual Information:** In case the user has identified himself as an Individual. Then the user shall be required to enter the name (first name, middle name & last name), relationship, age, gender, profession and address in the system
- 4. **Organization:** In case the user has selected the Organization option, the system will prompt the user to enter the below information
 - f. **Organization Name:** The user shall enter the name of the organization
 - g. **Year of Incorporation:** The applicant shall enter the year of incorporation of the organization
 - h. **TAN:** The applicant shall enter TAN value in the system

- i. **Address Details:** The applicant shall enter House No/Building Name, Street, City/Village, Taluka, District, State, Pin Code
- j. **Represented by Authorised Signatory:** The user shall be required to enter the first name, middle name, and last name, relationship, relative name and age in the system

Note: In case the user has selected 'Organization' option then 'Represented for minor guardian' and 'Exemption from Appearance' option shall not be applicable

- xiii. **Presenting the document:** In property registration, there shall only be a single presenter, who would be presenting the document to Sub-Registrar at the SRO

Case 1:

In case the user is presenting the document then the system will allow the user to add new party details and enter executant details

Case 2:

In case the user is not presenting the document then the system will allow the user to select type of party

- xiv. **Represented for minor guardian:** In case the user has selected 'Yes' to 'Represented for minor guardian' option then the user shall enter name, age, and relationship


- xv. **Exemption from Appearance (Section 88):** In case the user could not be present at Sub Registrar office on date and time of the document registration and the applicant possess the exemption letter from the distinguish authority, then

Case 1:

In case the user has selected 'Yes' in 'Exemption from Appearance' option then the user shall be required to enter 'exemption reference letter number' and upload exemption reference letter. Section 88 exemption is applicable only for court and certain functionaries as per notification of the department and provision of the law

- xvi. **Add Party:** After filling details of claimant/ executant, the user shall have an option to add multiple individuals in both the section otherwise user could save the party information and move forward

Party Information - Identifiers



Functional Step by Step Process

- iv. In case the user is an identifier, then in the application the following identifier details shall be required:
- Name (First Name, Middle Name, Last Name)
 - Age
 - Gender (Male, Female, Transgender or other)
 - Profession of witness
 - Address (House no, Street Address, State, District & City)
 - Witness identifies (Claimant or Executant)

- v. After user enters above identifier details, system shall ask the user if number of identifiers is greater than equal to two, as for executing the property registration document, at-least 2 identifiers would be required

Case 1:

In case the user selects 'Yes' then the system shall again prompt the user if they want to add more identifiers, in case the user selects yes then the process shall end otherwise user shall add more identifier and its details

Case 2:

In case the user selects 'No' then system shall again prompt the user to add at least two identifiers and its details

- vi. Add identifier: After filling details of consenting witness the user shall have an option to add multiple individuals otherwise user could save the party information and move forward

User Interface (UI)

Presenter

Presenter Details

<

PRESENTER

Who is presenting

☐ Claimant

☐ Executant

☐ Both

Whether Individual or Organization

☒ Individual

☐ Organization

Salutation*

Value

▼

First Name*

Value

Middle Name

Value

Last Name

Value

Alias Name

Value

Relationship*

Value

▼

Relative's Name*

Value

Age*	Gender*	Profession
Value	Value	Value
ID Proof Type	ID Number	☐ I don't have a PAN
PAN	Value	
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value
☐ Represented by Power of Attorney		
Save and Continue		

Executant

Enter the Details

<

EXECUTANT 1

EXECUTANT 2

Number of Executant

Is Consenting Witness

☐ Yes

☐ No

Is Claimant

☐ Yes

☐ No

☐ Represented for Minor Guardian

☐ Exempted from Personal Appearance (Section 88 Exempted)

Whether Individual or Organization

☒ Individual

☐ Organization

Salutation

First Name*

Middle Name

Last Name

Alias Name

Relationship*	Relative's Name*	
Value	Value	
Age*	Gender*	Profession
Value	Value	Value
ID proof	ID Number	☐ I don't have a PAN
Value	Value	
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value
☐ Represented by Power of Attorney		
Save and Continue		

Identifiers


IDENTIFIER 1		
Salutation	First Name*	Middle Name
Value	Value	Value
Last Name	Age*	Gender*
Value	Value	Value
Profession		
Value		
Address Details*		
House No./Building Name*	Street Address *	State*
Value	Value	Value
District*	City/Village	PIN Code*
Value	Value	Value

Relationship*	Relative's Name*
Value	Value
Identifies	
☐ Claimant	
☐ Executant	
Save and Continue	

18.4 Document Summary – Applicant (Online)

i. Brief Description

It is the document summary of party information, property information, valuation of the property and calculation of stamp duty & fees and also contains witnesses' particulars along with the check & verification of align data before sending it to the SRO



ii. Functional Step by Step Process

The system generates the ‘online document summary’ report, this report gives summary of all the details entered for the document registration. The user shall be able to go through the document summary as presented by the system. Document summary shall contain below details:

- Address details (District, Taluka, Hobli, Village, SRO, Property Type, Survey No, Hissa No)
- Property(s) details
 - Property data – Bhoomi and Article selected
 - Court order details
 - Liability details
- Market Valuation and Fee calculation details
- Party(s) details (Claimant, Executant, Identifier(s) details)

- Upload Deed Document Along with Enclosures: The user shall be required to upload the deed document along with the enclosers in the application. The enclosure documents shall be according to the articles and type of registration
- The date of execution of the document also needs to be selected by the applicant
- The user shall be asked to select the Sub-Registrar office from the dropdown, and the application shall be forwarded to the selected SRO for evaluation

The user shall verify the above details in order to check any data entry mistakes, the user shall be required to accept the declaration and only after then the application shall be submitted for approval.

User Interface (UI)

Upload Deed Document

Please upload the draft Deed document for review



Upload

Date of Execution

Please select the date of execution



Select Sub registrar office

Please select the Sub-registrar office for Registration



Declaration

☐ I hereby confirm that all the information provided is correct to the best of my knowledge. Also, I understand that in case any information is found incorrect, misleading, or fraudulent, there can be action was taken against me as per the Information Technology Act, 2000 and it may or may not lead to the cancellation of this document.

Date: 01-Oct-2021
Place: Ranchi


Cancel

Agree and Submit

19 CERTIFIED COPY (CC) SEARCH

i. Brief Description

Certified copy is the copy of the registered scanned document. This copy is signed by SR. Certified Copy will be generated for the documents which are coming under Book 1 of Document Registration, Marriage Registration and Marriage Notice. For the Certified Copy stamp duty need to be paid and has to be certified as per Section 10A of Stamp Act. The certificate of Stamp is as per Appendix BA under Rule 10A of Stamp Rules.



ii. Functional Step by Step Process

1. Applicant shall select Certified Copy, after which the applicant will get an option to select below option:

- Search by Blockchain key: The applicant shall enter Blockchain ID/ Card Number and search. The system shall display search result and continue with the process
- Search by Document details: The applicant shall select Document Type (Document Type will have Document Registration, Marriage Registration, Marriage Notice), District, Sub Registrar Office, Book Type (Book-1, Book-1 Part-I Memos, Book-1 Part-III(a), Book-1 Part-III(b), Book-1 Part-IV, Book-1 Part-V, Documents as per Rule 17(2) & (3), Book-1 Part-VI), Document Number and Year of Registration. After which system shall fetch data from Master Database

2. OTP Verification:

Case 1:

In case OTP is verified by the system then the applicant will search for CC and system will generate the Registered Deed Document. The applicant will accept the result and proceed


Case 2:

In case OTP is not verified by the system then the applicant will be asked to enter OTP again

19.1 CC Payment

i. Brief Description

Once the Certified Copy is found, user shall be directed to do the Payment to get the Digitally Signed Certified Copy.



ii. Functional Step by Step Process

- Applicant shall select Payment Details, after which the system will display below details:
 - Application Fee
 - Search Fee
 - Stamp Duty
- The system will display Application Number and Application Type
- The user shall enter Remitter Name and select SRO office name from the drop down. The user will then proceed to payment. System shall be redirected to Khajane-2
- Payment Confirmation:

Case 1:

In case Payment is confirmed then the system will generate transaction receipt. Applicant will be able to print the receipt



Transaction Receipt

Transaction Reference No	013018013550891550
Bank Name	HDFC Bank
Bank Reference No	439943102
Amount (Rs.)	145
Transaction Execution Date & Time	2018-01-30 14:03:48.469
Mode Of Payment	Net Banking
Status	Payment received at payment gateway


Case 2:

In case Payment is not confirmed by the system then the applicant will be redirected to retry and proceed for payment again

19.2 CC Online Application Summary

i. Brief Description

Once the payment is done, the application details will be displayed on the system for the applicant to verify the details entered.




ii. Functional Step by Step Process

- 1.The document summary will be displayed to the user and the elements of the summary page will be displayed by the system
- 2.System will display application details such as application number & application type and applicant details such as Name and Aadhar number
- 3.System will display Input Search Parameters, Payment details and transaction receipt details in document summary
- 4.Applicant will be able to see the preview of the application. Then it will be sent to SRO for Approval

19.3 CC Generation

i. Brief Description

CC is the copy of Registered Deed Document. Upon search, as per the input parameters entered by the user the Registered Deed Document will be displayed. The user shall submit the Application to Sub Registrar for Approval. Once the Sub Registrar approves the application, the user will be able download the digitally signed CC.



ii. Functional Step by Step Process

SDA

- 1.Applicant shall submit the application for online CC.
- 2.The application shall be scrutinized by the SDA as per the parameters entered by the applicant in the system
- 3.As per the details entered in the application, SDA will prepare the CC
- 4.If it is found correct, SDA shall view and download the CC
- 5.After downloading, SDA shall Digitally Sign the CC by using Adobe Acrobat
- 6.After signing the CC, SDA shall update the document with remarks and send it to FDA for further Approval

FDA

- 1.FDA shall receive the digitally signed CC from SDA
- 2.FDA shall validate the CC details as per the parameters entered by the applicant in the system
- 3.If it is found correct, FDA shall view and download the CC. If it is not found correct FDA shall revert the application back to the SDA

4. After downloading, FDA shall Digitally Sign the CC by using Adobe Acrobat
5. After signing the CC, FDA shall update the document and send it to Sub Registrar for further Approval

Sub Registrar

1. Sub Registrar shall receive the digitally signed CC from FDA
2. Sub Registrar shall validate the CC details as per the parameters entered by the applicant in the system
3. If it is found correct, Sub Registrar shall view and download the CC. If it is not found correct Sub Registrar shall revert the application back to the FDA
4. After downloading, Sub Registrar shall Digitally Sign the CC by using Adobe Acrobat
5. After signing the CC, Sub Registrar shall update the document and send it to the Applicant
6. Applicant shall view and download the Digitally Signed CC

20 COURT ORDER ENTRY MODULE

Brief Description


Department communication with the Court Orders is a statutory requirement. If there are any restraining orders of the Court to restrict Registration, the Department should comply with the orders of the Court to honor the directions of the Court.

20.1 Search and Add Court Order

i. Brief Description

The Court Order details are searched against the Property in the system. If any Orders found in the system, the details shall be displayed. Otherwise, Sub Registrar can add the Court Order details into the system

Search and Add Court Order




i. Functional Step by Step Process

1. Sub Registrar shall click on Search Court Order details.
2. Sub Registrar needs to enter the Court Order number to search.
3. System shall search the Court Order details in the system.
4. If the order found in the system, system shall display the order details (Order Number, Issuing Authority, Issue Date, Description, Article, Cancelled or In Force)
5. If the order is not found, system shall display the message “No Result Found”.
6. If the order is not found in the system, Sub Registrar shall add the court order details.
7. Sub Registrar shall enter the Court Order Details such as Court Order number, Issuing Authority, Registration Article, Date of Issue of Order, Order Description, Order status (In Force or Cancelled). Then, system shall auto save the Application Details
8. After entering order details, Sub Registrar shall enter the Property Details such as, Type of Property (Agriculture/Non-Agriculture), District, Taluk, Hobli, Village, Boundary Details (East, West, North, South), Property Description, Area of the Property with Measurement Unit, Extent Description (If available), Property Number Type and Property Number Details.
9. If the Sub Registrar wants to add more details with respect to the Property, he can click on Add More Details and he shall enter the Property Number Type and Property Number Details
10. If the Sub Registrar wants to add more Property, he can click on Add More Property and shall enter the required Property details
11. After entering Property Details, Sub Registrar shall enter the Party Details such as First Name, Middle Name, Last Name, Age and Address
12. If the Sub Registrar wants to add more Parties he can click on Add More Parties and shall enter the required Party details
13. If No, Sub Registrar shall Save the details and Submit.
14. Once the details are submitted, the Court Order Details get added into the system.

20.2 Edit Court Order

i. Brief Description

If there are any modifications in the existing Court Order, Sub Registrar can edit the Court Orders in the system.




ii. Functional Step by Step Process

1. System shall display the Court Order details (Order Number, Issuing Authority, Issue Date, Description, Article, Cancelled or In Force)
2. Sub Registrar shall click on edit Court Order details
3. Sub Registrar shall be able to edit the Court Order Details such as Court Order number, Issuing Authority, Registration Article, Date of Issue of Order, Order Description, Order status (In Force or Cancelled). Then, system shall auto save the Application Details
4. After editing the order details, Sub Registrar shall be able to edit the Property Details such as, Type of Property (Agriculture/Non-Agriculture), District, Taluk, Hobli, Village, Boundary Details (East, West, North, South), Property Description, Area of the Property with Measurement Unit, Extent Description (If available), Property Number Type and Property Number Details.
5. If the Sub Registrar wants to add more details with respect to the Property, he can click on Add More Details and he shall enter/edit the Property Number Type and Property Number Details
6. If the Sub Registrar wants to add more Property, he can click on Add More Property and shall enter/edit the required Property details
7. After editing the Property Details, Sub Registrar shall be able to edit the Party Details such as First Name, Middle Name, Last Name, Age and Address
8. If the Sub Registrar wants to add more Parties he can click on Add More Parties and shall enter/edit the required Party details
9. If No, Sub Registrar shall Save the details and Submit.
10. Once the details are submitted, the Court Order Details get updated into the system.

20.3 Cancel Court Order

i. Brief Description

If the restrictions by the Court Order is cancelled, then Sub Registrar shall enter the cancellation order in the system.



ii. Functional Step by Step Process

1. System shall display the Court Order details (Order Number, Issuing Authority, Issue Date, Description, Article, Cancelled or In Force)
2. Sub Registrar shall click on cancel Court Order details
3. Sub Registrar shall be able to cancel the Court Order by entering details such as Court Order number, Issuing Authority, Date of Cancellation of Order and remarks
4. After entering all the details, Sub Registrar shall click on Save and Submit. Then, the details get saved into the system

User Interface

Search and Add Court Order

Search Court Order

ISSUING AUTHORITY

TYPE OF CASE

YEAR

ORDER NO

Add Court Order

ORDER NUMBER*

ISSUING AUTHORITY*

REGISTRATION ARTICLE*

DATE OF ISSUE*

TYPE OF CASE

DESCRIPTION*

Add Property Details

Property 1 of 1

Delete

☐ Is Agricultural Property

DISTRICT

Value

SUB REGISTRAR OFFICE

Value

INDEX II: VILLAGE

Value

HOBLI

Value

PROPERTY NUMBER DETAILS

Enter one or more details to further improve your search

PROPERTY NUMBER TYPE

Value

PRESENT PROPERTY NUMBER DETAILS

Value

PROPERTY NUMBER TYPE

Value

OLD PROPERTY NUMBER DETAILS

Value

[Add more details](#)

BOUNDARIES

East

Value

West

Value

North

Value

South

Value

Description of Property

Value

AREA

Value

MEASUREMENT UNITS

Value

EXTENT DESCRIPTION

Value

[Add more property](#)

Add Party Details

Party 1 of 1

Delete

FIRST NAME*

Value

MIDDLE NAME

Value

LAST NAME

Value

AGE

Value

ADDRESS

Value

[Add more party](#)

Save

Cancel

Cancel Court Order

Cancel Court Order

ORDER NUMBER*

ORDERED BY*

DATE OF CANCELLATION

Value

Value

Value

REMARKS*

Value

Save

Cancel

21 LIABILITY MODULE

Brief Description


Liability is the arrears of deficit stamp duty and registration fee arising due to undervaluation of the property, mis classification of documents, review of orders of the Deputy Commissioners of Stamp by Chief Controlling Revenue Authority (CCRA) and also observation made by the audit authorities. This deficit of stamp duty and registration fee is the Liability to be recorded on the property

21.1 Search Liability

ii. Brief Description

The Liability details are searched against the Property in the system. If any details found in the system, the details shall be displayed. Otherwise, Sub Registrar can add the Liability details into the system on the orders of the District Registrar

After result display, two options shall be displayed to the user. Show similar property and show exact property. If the user selects similar property, list of all the similar properties with respect to the property number shall be displayed and from this list user can select the required property. If the user selects show exact property, the exact property with respect to the property number shall be displayed




i. Functional Step by Step Process

1. Sub Registrar shall click on Search Liability details.
2. Sub Registrar needs to select SRO Name, Book Number, Financial year and enter the Document Number to search.
3. System shall search the property details in the system.
4. If the property is found in the system, system shall display the property along with the Liability details (Issue Date, Issued By, Liability amount, Order Number and Liability Note)
5. If the property is not found, system shall display the message "No Data Found".
6. Once the result is displayed, system shall show two options. Show Similar Property and Show Exact Property
7. If the user selects similar property, list of all the similar properties with respect to the property number shall be displayed and from this list user can select the required property. If the user selects show exact property, the exact property with respect to the property number shall be displayed
8. As per the selection property details shall be displayed to the user

21.2 Add Liability

i. Brief Description

Upon search, if the Liability details on the property are not found in the system, Sub Registrar can add the Liability details to the property.




i. Functional Step by Step Process

1. From the list of Similar Properties and the Exact Property, Sub Registrar needs to select the required property for which the liability details have to be added
2. Sub Registrar shall click on Add Liability details.
3. Sub Registrar need to enter Issue Date, Issued By, Liability Amount, Order Number and Liability Note
4. After entering the liability details on the property, Sub Registrar shall click on Save button to save the details

21.3 Liability Report

i. Brief Description

Liability Report shall be provided to each Sub Registrar to view the Liabilities entered on the property for the required period.



i. Functional Step by Step Process

1. Sub Registrar shall click on Liability report
2. Sub Registrar need to select SRO Name and From Date and To Date for which he needs to view the report
3. Sub Registrar shall click on Get Details to view the report
4. System shall display all the Liability entries made during that period. Each Liability entry has the following details such as Order Number, Liability Note, Final Registration Number, Property Schedule, Property Number Details and Village/ Town
5. After getting the details, Sub Registrar can take print of the report by click on Print report

User Interface

Liability Filing

SEARCH LIABILITIES

SRO Name*

Value

Book Name*

Value

Financial Year*

Value

Document Number

Value

Search

Property Details

Property Details						
S.No.	Select	Property Details	Property Number Details	Executant	Claimant	Liability Details
1	☐	Note: [Schedule A] Property admeasuring 300 sq.m	Site No. 7	Anand	Anand, Pavithra	Order number:1231, Issue Date: 03-12-13
Show Similar Property Show Exact Property						

Add Liabilities Details

Issue Date*

Value

Issued By*

Value

Liability Amount*

Value

Order Number

Value

Liability Note*

Value

Save

Cancel

22 CROSS REFERENCE MODULE


Brief Description

On the Registration of a document which revokes or cancels or ratifies an error, in, or modifies the terms of a document previously registered in the same class or register book or a return of a lands acquired under the Land Acquisition Act or of a document received and filed under Section 89(Rule 17), or on the receipt of a communication from a Revenue Officer or from a Court which intimates a similar revocations, cancellation, ratification or modification, a note shall be entered at the foot of the entry of the later document or communication.

22.1 Add Cross Reference

i. Brief Description

Once document is finally registered it can't be altered but in certain situations like cancellation of document by court or communication by Revenue Commissioner or rectification it becomes mandatory to mark reference of subsequent document in the amended/modified/cancelled (previously registered) document.



i. Functional Step by Step Process

Before this process starts, the document to be cancelled/modified must be registered and scanned using KAVERI application.

1. Subsequent document of amendment/correction/cancellation follows the same process of registration as that followed for normal registration.
2. Sub Registrar shall click on Add Cross Reference
3. Sub Registrar needs to select Document Type
4. System shall display two Document Types such as Kaveri Registration Document and Endorsement

5. The registration system displays the options to select transaction type such as Modification, Rectification, Cancellation and Revocation
6. The registration system displays the options to select "Through" from where the cross references are originated (Court Order/Revenue Order, etc)
7. The registration system shows all the required information necessary to add a reference on the registered as well as previous document which is being modified/cancelled.
8. SR/FDA enters required details on to the displayed form.
9. System finds the original scanned image locations (i.e., Main Backup, Scanned etc.).
10. System internally links these two documents by adding references.
11. System alters scanned images identified in all above locations by adding a watermark with alteration description.
12. System also internally establish links in Index II table. Whenever, the linked document in index II is referred for encumbrance information, the reference to amending/cancelling document and vice-versa also appears in the search result.
13. Whenever a linked document is viewed or printed, the system displays/prints the information that the said document is amended/cancelled by the referred document having the specified document number and vice-versa.
14. Reference text for Kaveri Registration Document will be like
 - **For Rectification**
 - New Document Reference - This Document Rectifies by Document No. BMH-1-07916-2010-11"
 - Old Document Reference - This Document has been Rectified by Document No. BMH-1-07916-2010-11"
 - **For Modification**
 - New Document Reference - This Document modifies Document No. BMH-1-07916-2010-11"
 - Old Document Reference - This Document has been modified by Document No. BMH-1-07916-2010-11"
 - **For Cancelled**
 - New Document Reference - This Document Cancels Document No. BMH-1-07916-2010-11"
 - Old Document Reference - This Document has been Cancelled by Document No. BMH-1-07916-2010-11"
 - **For Revocation**
 - New Document Reference - This Document Revokes by Document No. BMH-1-07916-2010-11"
 - Old Document Reference - This Document has been Revoked by Document No. BMH-1-07916-2010-11"
 - **Through Court**

- New Document Reference – “The communication received from Civil Judge and JMFC Court No. OS No120/2010 dated 08/04/2022 Cancels the Document No.CKB-1-00520-2017-18”
- Old Document Reference – “This Document has been cancelled through communication received from Court No. OS No120/2010 dated 08/-4/2022 and filed as Document No. CKB-1-00120-2022-23”

15. Reference text for Endorsement will be like “Endorsement Date DD/MM/YYYY Certified that deficit Stamp Duty of Rs.1500 Registration Fee of Rs.500 has been paid by Sri/Smt Rajesh challan No.120 dt 09/04/2022 of SBI order no 12/20-21 dt 08/04/2022 of the DRO”

User Interface

Add Cross Reference to the document

☒ Endorsement
 ☐ Kaveri Registration Document

New Document Details

Document Number

Book

Year

Endorsement Details

Stamp Duty

Registration Fees

Bank

Remitted Type

Receipt Number

Remitted Date

Party Name

Order Number

Order Date

Order Office Name

User Interface through Court Orders

Document Type Selection

Controls Effects

Adding Cross Reference Version 1.1

Transaction

☒ Registered in this new bifurcated office

☐ Endorsement

☐ KAVERI Registered Document

Transaction Type: Cancellation Through: Court

☒ Registered in this new bifurcated office

☒ Registered in this new bifurcated office

New Document Number: 120 Book-1 2022-23

Old Document Number: 1500 Book-1 1969-70

Volumello: 1520 From Page Number: 120 To Page Number: 125

Court Order No.: OS NO 120/2010 Name of Court: CIVIL JUDGE AND JMFC Court Order Date: 08-Apr-2022

Add

Check the below generated summary of references(In red color). If references are correct click Yes or else click No.

Yes No

Add **Delete** **Clear** **Exit**

New Document Reference: This Communication Received from CIVIL JUDGE AND JMFC Court No. OS NO 120/2010 dated 08/04/2022 Cancels the Document No. 1500/1969-70 Stored at CD/VOLUME No.1520 Page 120 To 125 of Book No. 1.

Old Document Reference:

23 CONFIGURATION MODULE

i. **Brief Description**


Configuration module is the administrative tool for the management of the officer and employee's duty, role, and responsibility within the department.

23.1 Transfer Management

i. **Brief Description**

The officers working on various designations are being transferred to different offices of Sub-Registrar, District Registrar, and IGR. The Transfer Management tool shall be working for the proper management of the transfer processes within the offices of the department.

Transfer Request raised by the District Registrar




i. Functional Step by Step Process

1. The transfer request will be raised by the District Registrar in the system and for which the DR shall login in the Kaveri account and click on the Transfer and Postings
2. To raise the transfer request to the IGR (Admin), the details of the employee shall be required
3. The user shall enter the Employee ID/Name, and based on the suggestive search, the user will select the employee's id/name
4. The designation and current posting location shall be auto fetched and displayed to the user
5. After which the user shall be required to enter the new transfer location and the duration of new posting of the employee
6. The DR shall also be required to enter the reason for the transfer in the given space

7. After verifying the details, the DR shall submit the request in the system and the transfer request shall be sent to the IGR (Admin) for final approval


Employee Transfer History



i. Functional Step by Step Process

1. The District Registrar shall be given access to check the transfer history of all the employees that directly/in-directly report to him
2. To check the transfer details, the user shall be required to enter the Employee ID/Name, and based on the suggestive search, the user will select the employee's id/name and press the Search button
3. The system shall generate the employee transfer history along with the location, reason, and time period for which the employee gets transfer to the new location

Employee Transfer Request (Only IGR/Admin)



i. Functional Step by Step Process

1. The IGR/Admin shall be given access to approve/reject the request received from the District Registrar office
2. To check all the request received, the user will Login to the account and select Transfer and Postings
3. Under the Transfer and Postings section, the option of “Employee Transfer Requests” under which all the requests received from the District Registrar shall be displayed and the required decision (approved/rejected) needs to be taken by the user

Case 1:

- If IGR/Admin approve the transfer request, then the notification shall be triggered to the DR and to the transferred employee. The employee record shall be updated as per the new information in the database

Case 2:

- If IGR/Admin user decide to reject the transfer request in the system, then the user shall be required to enter the reason for rejecting the request
- After submitting the request, a notification shall be triggered in the system to the DR user account from which the request have been initiated and the reason for rejection will also be visible to the user

User Interface (UI)

Transfer Management

Employee Transfer

Employee Transfer History

Employee Transfer Requests

Employee ID/Name

Designation

Current Location

Transfer Location

Date

From

To

6 months

Reason

Send

Transfer Management

Employee Transfer

Employee Transfer History

Employee Transfer Requests

Enter Employee ID/Name

search

Search History

S.No.	Employee ID	Employee Name	Designation	Reason	From	To	Transfer Location
01	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	10-08-2021	Banglore 01
02	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 02
03	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 03
04	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 04

Transfer Management

Employee Transfer

Employee Transfer History

Employee Transfer Requests

Transfer Requests


S.No.	Employee ID	Employee Name	Designation	Reason	From	To	Transfer Location	Action	
01	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	10-08-2021	Banglore 01	Approve	Reject
02	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 02	Approve	Reject
03	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 03	Approve	Reject
04	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 04	Approve	Reject
05	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	10-08-2021	Banglore 01	Approve	Reject
06	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 02	Approve	Reject
07	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 03	Approve	Reject
08	12345567	Manoj	FDA	Lorem ipsum dolor sit amet, consetetur sadipscing elitr.	08-08-2021	18-08-2021	Banglore 04	Approve	Reject

23.2 Leave Management

i. Brief Description

Leave management is the set of processes that controls the leave application, approval and tracking of employee leave in the Department of Stamps & Registration.

Apply for Leave



i. Functional Step by Step Process

1. The leave request could be raised by the SDA/FDA/SR/DR/AIGR/DIGR in the system and for which the user shall login in the Kaveri account and click on the Leave Management
2. The total number of leaves utilised/available shall be displayed to the user, according to which the user could raise the request in the system
3. To raise the leave request in the system, the name of the employee and reporting authority shall be auto fetched and displayed to the user
4. The user shall be required to select the Leave type (Casual/Planned) from the dropdown and dates for which the user is applying for leaves
5. After the date's selection from the user, the total number of days shall be calculated and displayed to the user for confirmation

6. After all the details are filled, the user shall be required to enter the reason for which he/she would like to avail the leaves and briefly describe the reason in the given space
7. The status of the leave (approved/rejected) shall be communicated to the user in the dashboard as well as in the notification bar

Validation of Leave Management System:


1. **Casual Leaves** – 10 leaves in a year (Jan -Dec) + 2 RH (Restricted Holidays)
2. **Earned Leaves** – 15 leaves (Jan – June) + 15 leaves (Jul – Dec) – These leaves shall be carried forwards to the next session

Note: Maximum carried forward leaves could not extend 340 leaves for an individual

3. **Maternity Leave** – For a maximum of 6 months for female employees and could only be availed for 2 children/time
4. **Paternity Leave** – It could be availed by male employees for a maximum period of 15 days

- For Earned, Maternity and Paternity leaves total number of days will be counted.
- For the Casual Leaves, the holidays shall not be including, to calculate the number of leaves applied
- SDA and FDA shall apply for the leaves to the reporting SR. In case, if SR is not available then the Incharge shall act as the approving authority.
- The leave request raised by the SR shall be approved by DR
- The leave request raised by DR, AIGR, DIGR shall be approved by IGR

Leave Approval Request



i. Functional Step by Step Process

1. Only SR, DR and IGR shall have the rights to approve the leave request in the system for the officers reporting to them. For accepting the request, the user shall login in the Kaveri account and click on the Leave Management
2. In the Leave management dashboard, notification shall be displayed if any new request has been received for approval

3. The user shall be required to click on “Approval Requests” tab for accessing the pending requests assigned for the final approval
4. The Leave Approval Request dashboard shall display all the requests received from the officers in ascending order
5. The user needs to take decision and approve or reject the request as per the department policies

Case 1:

- In case, the user decided to approve the leave request, then the user shall confirm and press the “Approve” button
- The leave approval notification shall be sent to the requesting officer and the status shall be updated in the Leave management dashboard

Case 2:

- If the user decides to reject the leave request in the system, then the user shall be required to enter the reason for rejecting the request
- After submitting the request, a notification shall be triggered in the system to the requesting officer account from which the request have been initiated and the status shall be updated in the Leave management dashboard

User Interface (UI)

Total Number of Leaves Used

4/10

Casual Leaves

4/10

Planned Leaves

Leave Status

✓ Leave Approved From DD/MM/YYYY To DD/MM/YYYY By Manoj.SRO

✗ Leave Rejected From DD/MM/YYYY To DD/MM/YYYY By Manoj.SRO

Approval Requests

Apply Leave

Employee Name

Tanmay

Reporting To

Select

Leave Type

Select

Reporting Person

Search

Date

From

To

3 Days

Reason

Apply

Leave Approval Requests

24 SECTION 68 (2) CORRECTION MODULE

i. Brief Description

In addition to the information below, please find a detailed requirements document attached:

[https://csgkarnataka.sharepoint.com/:b:/r/sites/ULMS/Knowledge%20Base/FRS/68%20\(2\)%20correction%20Module%20FRS_V2.pdf?csf=1&web=1&e=Bvwfha](https://csgkarnataka.sharepoint.com/:b:/r/sites/ULMS/Knowledge%20Base/FRS/68%20(2)%20correction%20Module%20FRS_V2.pdf?csf=1&web=1&e=Bvwfha)

Please use the above link to access section 68(2) Filing detailed FRS.

Every Registrar shall have an authority to issue (whether on complaint or otherwise), any order consistent with this act which he considers necessary in respect of any act or omission of any Sub-Registrar sub-ordinate to him or in respect of the rectification of any error regarding the Book or the office in which any document have been registered.


24.1 Correction Request Sent by SR

i. Brief Description

The property owners shall submit the request to Sub-Registrar Office to rectify the correction in the document, which could have been occurred during the document registration process. For which the SR will check the property description/details and the registered deed document. There are 4 types of corrections which could be made in the registered document:

- Text Correction
- Property Number Correction
- Village Correction
- Party Name Correction

Correction Request Sent by Sub-Registrar



i. Functional Step by Step Process

1. The request would be raised to District Registrar (DR), for which the Sub-Registrar shall Log in to the system and select 68(2) Correction Note

2. The system shall re-direct the user to the Correction Module and the SRO details are auto fetched and displayed
3. The user shall enter the document registration number, based on which the Book Type and FY of registration shall be auto fetched and displayed to the user for confirmation
4. After the details are confirmed, then the user shall initiate the search and the property details mapped to the document shall be displayed
5. After which the SR shall select the type of correction required as per the request of the property owner and add the correction note
6. The SR shall also scan and upload the registered deed document presented by the owners, which will be uploaded in the correction request and along with the details saved for the selected indicators
7. After final verification of the details, SR shall submit the request to DR for approval and issue the DR order for the same

User Interface

Document Search Parameters

SRO Name*

Gandhinagar

Document Number*

Value

Book Type*

Book-1

Financial Year*

2004-05

View

Property Details

Sr.No.	Select Property (For text Correction)	Property Number Search Key (For Property Number Correction and Village Correction)	Party Search Key (Party Name Correction)	Property Description	Execution Date	Nature of Document	Escutant	Claimant	Page Count	Document Display
01	Select	Add/View	Add/View	(VILLAGE: Vyalakaval)LAND MARK) Shops No.1 and 2,Xhata No.40/2, of the BBMP (Comprised in property bearing earlier MI No. 1079/40),12th A cross vyalakaval,Malleswaram ward NO.5 Bangalore (EAST) Government Property (SOUTH) Private Property (SOUTH) Private Property (NORTH) Private Property Note(Schedule A)(Measuring E-W=40ft N-S=24ft of land in Shops No.1 and 2 ,Xhata No.40/2, of the BMP (Comprised in property bearing earlier MI No. 1079/40), 12th A Cross vyalakaval,Malleswaram,ward NO.5 Bangalore	06/08/2004 00:00:00	Article Name: Agreement of Sale of immovable Property (Possession not given) Market Value:0.0000 Consideration 500000.0000	B.S.Sathy Murthy	M.G.Eswara.- M.D.Gangadharasa Prashanth R.Dhondale,Prashanth R.Dhondale	8	

Note For Selected Property

Market Value to be read as 500000.00


Upload Document

Back Save

24.2 Correction Order Submit by DR

i. Brief Description

The District Registrar shall issue an order based on the remarks received from SR for corrections in the Index II Entry or property description of the registered document.



i. Functional Step by Step Process

1. The request would be raised by Sub-Registrar (SR) and Sent to DR for which the District Registrar shall Log in to the system and select 68(2) Correction Note
2. The system shall re-direct the user to the Correction Module and where all the requests received from the Sub-Registrar Offices will be displayed

3. The user shall select an application and view the registered deed document which is submitted by the SR for verification purpose
4. After which the user will select the Add Order button to submit the DR order
5. The user shall enter the order number, select order date and upload DR order for the correction request received from the SR
6. The user shall also enter the Correction Note U/S 68(2) and after confirmation of the details the user shall submit the order details
7. The notification will be sent to SR to make the correction in the document

User Interface

SR Correction Requests

S.No.	SRO Name	Order Request by SR	Registration No.	Request Date	Section 68(2) Note	View Document	Status	Action
01	Koppal	Koppal	TST-1-02968-2019-20	04-01-2019	Market Value to be read as 500000.00		Pending	<button>Add Order</button>
02	Koppal	Koppal	TST-1-02968-2019-20	04-01-2019	Market Value to be read as 500000.00		Pending	<button>Add Order</button>
03	Koppal	Koppal	TST-1-02968-2019-20	04-01-2019	Market Value to be read as 500000.00		Pending	<button>Add Order</button>
04	Koppal	Koppal	TST-1-02968-2019-20	04-01-2019	Market Value to be read as 500000.00		Pending	<button>Add Order</button>
05	Koppal	Koppal	TST-1-02968-2019-20	04-01-2019	Market Value to be read as 500000.00		Pending	<button>Add Order</button>

< 1 2 3 4 5 6 7 8 9 10 >

DR Order Details

District Name*

Value

SRO Name*

Value

View

Add Order Details

Order Number*

Value

Order Date*

Value

Upload DR Order PDF File*


68(2) Correction Note*

Save

24.3 Correction Note U/S 68(2) Submit by SR

i. Brief Description

The Sub-Registrar shall enter the correction note in the property description as per the order of the District Registrar.



ii. Functional Step by Step Process

1. As per the order submitted by the District Registrar, the corrections shall be made in the document U/S 68(2), for which the SR shall Log in to the system and select 68(2) Correction Note
2. The system shall re-direct the user to the Correction Module and where the correction orders received from the DR shall be displayed with the following details:
 - a. Document Number
 - b. DR Order Number

- c. Order Date
 - d. Order Updated Date and Time
 - e. Section 68(2) Note
3. The user shall be required to view the order submitted by the District Registrar, after which SR shall continue to Add Correction details as per the order
4. In case Text Correction is selected, then the 68(2) Correction note needs to be mentioned by the SR and submit
5. In case Property Number or Village Correction is selected, then the property details shall be displayed, and the user could change the following parameters:
 - a. Village/Area
 - b. Hobli
 - c. Current Property Number and Type
 - d. Old Property Number and Type

Note: If multiple DR order are submitted against the same property, then the SR shall have the functionality to deactivate the previous orders

6. In case Party Name Correction is selected, the details of all the parties shall be displayed and the user could update the name of the presenter, claimant and executant

Note: Edit option in the existing party details shall not be allowed, only the updated name of the party shall be mentioned by SR as per the DR's order

7. After final verification of all the details, the SR shall click on "Finalize" button to submit the details and the correction note shall be appended in EC and the document

User Interface

U/S 68(2) Orders from DR							
				Show 10 Entries	Search		
Sr.No.	Document Number	DR Order Number	Order Date	Order Upload Date	Section 68(2) Note	View Document	Action
1	GDN/2021-22/010	GDN/2021-22/010	11/08/2021	31/06/2021 11:17:13 AM	Market Value to be read as 500000.00 as per the order number GDN/2021-22/010 dated 11/08/2021 by District Registrar Gandhinagar		Add Correction
Showing 1 to 1							
Previous 1 Next							

Click on Select Property										
Sr.No.	Select Property (For text Correction)	Property Number Search Key (For Property Number Correction and Village Correction)	Party Search Key (Party Name Correction)	Property Description	Execution Date	Nature of Document	Executant	Claimant	Page Count	Final Registration Number
01	Select	Add/View	Add/View	(VILLAGE) Vyalikaval(LAND MARK) Shops No.1 and 2,Khata No.40/2, of the BBMP (Comprised in property bearing earlier MI No. 1079/40),12th A cross vyalikaval,Malleswaram ward NO.5 Bangalore (EAST) Government Property (SOUTH) Private Property (SOUTH) Private Property (NORTH) Private Property Note(Schedule A)Measuring E-W=40ft N-S=24ft of land in Shops No.1 and 2 ,Khata No.40/2, of the BBMP (Comprised in property bearing earlier MI No. 1079/40), 12th A Cross vyalikaval,Malleswaram,ward NO.5 Bangalore	06/06/2004 00.00.00	Article Name: Agreement of Sale of Immovable Property (Possession not given) Market Value:0.0000 Consideration 500000.0000	B.S.Sathya Murtliy	M.G.Eswara - M.D.Gangadharasa Prashanth R.Dhondale,Prashanth R.Dhondale	8	GAN-1-02368-2004-05
Showing 1 to 1										

Add Section 68(2) Note For Selected Property

Market Value to be read as 500000.00

BackSave

Previous Property Details

Sr.No.	DR Order Number	Order Date	Village	Current Property Type	Current Number	Old Property Type	Old Number	Survey No.	Surnoc	Hissa No	Order Note	Action
1	-	-	Vyalikaval	Khata No	40/2	Khata No.		0				Deactivate

Showing 1 to 1

Add New Property Number Search Parameters

Sub RegistrarMalleswaram

Village/AreaVyalikaval

Hobliother

Current Property Number TypeKhata No.

Current Number40*3

Old Property Number TypeSelect

Old Property NumberOld Number

Save

Selected Party Details

Sl.No.	DR Order Number	Order Date	Party Type	First Name	Middle Name	Last Name	Order Note	Action
1		-	Claimant	Prashanth R Dhondale			-	-
2		-	Claimant	Prashanth R Dhondale			-	-
3		-	Executant	B.S Sathya Murthy			-	-
4		-	Claimant	M.G.Eswara			-	-
5	GDN/2021-22/012	12-08-2021	Claimant	M.G.		Ishwara	Claimant M.G.Eswara to be read as M.G.Eshwara as per the order number GDN/2021-22/012 dated 12/08/2021 by District Registrar Gamdchinagar.	Edit

Showing 1 of 5 Entries

Save and Continue

Add Party Details



Party Type* Claimant

First Name* M.G.

Middle Name Middle Name

Last Name Ishwara

Save



25 FILING DOCUMENT MODULE

SUPPLEMENT TO REGISTER BOOK NO. 1 AND FILE OF COPIES AND TRANSLATION

25.1 (i) Supplements to register book no. 1 shall be kept as follows

i. **Brief Description**

Filing Document Module – As per Registration Rule 17, copies of the documents are filed for Registration in six parts of Book I. Six parts of Book I are as below

25.1.1 Book 1 Filing Part I - For the purposes of Sections 64, 65, 66 and 67 (Memos from the other Offices)

i. **Brief Description**

In addition to the information below, please find a detailed requirements document attached:

<https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book-I%20Part-I%20Other%20Memo%20Filing%20FRS%20V1.1.docx?d=w2083d13ea69b4967b561692d0286583d&csf=1&web=1&e=tcc6jZ>

Please use the above link to access Book 1 Part VI Filing detailed FRS.

1. **Section 64:** Sub-Registrar who has registered non testamentary document relating to immovable property not wholly situated in his own sub-district shall make memorendum there off and of the endorsement and certificate if any there on, and send the same to any other sub-registrar, sub-ordinate to the same registrar as himself in whose sub-district any part of search property situated and such sub-registrar shall file the memorendum in his Book – I (Part 1 of Book I as per rule 17)

ತಯಾರಿಸಿದವರ ಸಹಿ Prepared By	ಪರೀಕ್ಷಿಸಿದವರು Examined By	Designation ಹುದ್ದೆ : Designation (Reader) ಹುದ್ದೆ (ರಿಡರ್) :	ದ್ವಿ. ದ. ಸ. ದ್ವಿ. ದ. ಸ.
1908 ರ ಭಾರತದ ರಿಜಿಸ್ಟ್ರೇಷನ್ ಅಧಿನಿಯಮದ ಪ್ರಕಾರ 64-67 ಮೇರೆಗೆ ಸಬ್ ರಿಜಿಸ್ಟ್ರಾರ್ ರವರಿಗೆ ರವಾನಿಸುವುದು. ತಿಳಿಸಿದ ದಿನಾಂಕ..... ಪುಸ್ತಕ..... ಸಂಖ್ಯೆ 1, ಭಾಗ 1..... ರ ಪೂರಕದ 28 ಸಂಪುಟ ಕ್ರಮ ಸಂಖ್ಯೆ ಅಮೂಲಕ ದಿನಾಂಕ..... ಪುಟದಲ್ಲಿ ಪೈಲು ಮಾಡಲಾಗಿದೆ.			
ದಿನಾಂಕ : 18/11/2021	ಸಬ್ ರಿಜಿಸ್ಟ್ರಾರ್ ASst.Regist.District Registrar	ರಿಜಿಸ್ಟ್ರಾರ್ ಅಥವಾ ಸಬ್ ರಿಜಿಸ್ಟ್ರಾರ್ Registrar or Sub-Registrar	ಮುದ್ರೆಯ ದಿನಾಂಕ

FORM No. 26
[Vide Rule 162]
Intimation Slip Form

Name of the Registration Office sending the Memo or copy under Sections 64 to 67	Registrar No. and year of the document	Name of the registration office to which sent	No. and date of despatch. Signature of the Registration officer. Date	Date of receipt by the receiving office and No. in the Inward Register (from register)	Acknowledgment by the receiving officer. Signature of the Registering officer. Despatch No. Date
(1)	(2)	(3)	(4)	(5)	(6)

ii. Functional Step by Step Process for SECTION 64 Memorandum


1. The originating Sub Registrar follows the normal process to get the document registered and registers the document
2. The originating Sub Registrar after registration of the document containing the property of the other Sub Registrar jurisdiction, shall generate the Forms 25 and 26 by clicking on the '**Generate Forms 25 & 26**' button.
3. The Forms 25 and 26 shall get displayed on the Sub Registrar's dashboard along with the particulars
4. The Sub Registrar shall Digitally Sign by clicking on '**Digital Sign**' button and shall send to the other (concerned) jurisdictional Sub Registrar
(Note: The other (concerned) jurisdictional Sub Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)

5. The Forms 25 and 26 should appear in the dashboard of the other (concerned) jurisdictional Sub Registrar
6. The other (concerned) jurisdictional Sub Registrar shall click on '**View Forms 25 and 26**' button to view the same and shall file Form 25 by clicking on the '**File Form 25**' button; the filing document number along with date gets generated both in Forms 25 and 26
7. The other (concerned) jurisdictional Sub Registrar shall view Forms 25 and 26 by clicking on '**View Forms 25 and 26 for Digital Sign**' button, and shall Digitally Sign by clicking on '**Digital Sign**' button and shall send digitally signed Form 26 to the originating Sub Registrar by clicking on '**Send back to Originating SR**' button
8. The Form 26 should appear in the dashboard of the originating Sub Registrar
9. The originating Sub Registrar shall view the digitally signed Form 26 by clicking on '**View Digitally Signed Form 26**' button and shall file Form 26 by clicking on '**File Form 26 and Complete**' button

i. **Brief Description**

2. **Section 65:** Procedure where documents relates to in several districts (1), every Sub-Registrar on registering a Non-testamentary document relating to immovable property situated in more districts than 1 shall also forward a copy there off and of the endorsement and certificate (if any) there on, together with a copy of the map or plan (if any) mentioned in section 21, to Registrar of every district in which any part of such property is situated other than the district in which his own Sub-District is situated

(2), the Registrar on receiving the same shall file in his Book – I, the copy of the document and the copy of the map are plan (if any), and shall forward a memorandum of the document to each of the Sub-Registrars sub-ordinate to him, within whose Sub-District any part of such property is situate; and every sub-registrar receiving such memorandum shall file it in his Book – I.



ii. **Functional Step by Step Process for SECTION 65 Memorandum**

1. The originating Sub Registrar follows the normal process to get the document registered and registers the document
2. The originating Sub Registrar after registration of the document containing the property of the other district's Sub Registrar jurisdiction, shall generate the Forms 25 and 26 by clicking on the '**Generate Forms 25 & 26**' button.

3. The Forms 25 and 26 shall get displayed on the Sub Registrar's dashboard along with the particulars
4. The Sub Registrar shall Digitally Sign by clicking on '**Digital Sign**' button and shall send to the other (concerned) jurisdictional District Registrar
(Note: The other (concerned) jurisdictional District Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)
5. The Forms 25 and 26 should appear in the dashboard of the other (concerned) jurisdictional District Registrar
1. The other (concerned) jurisdictional District Registrar shall click on '**View Forms 25 and 26**' button to view the same and shall forward them to the concerned jurisdictional Sub Registrar under whose jurisdiction the property is situated by clicking on '**Send to concerned SR**' button
(Note: The concerned jurisdictional Sub Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)
6. The concerned jurisdictional Sub Registrar shall click on '**View Forms 25 and 26**' button to view the same and shall file Form 25 by clicking on the '**File Form 25**' button; the filing document number along with date gets generated both in Forms 25 and 26
7. The concerned jurisdictional Sub Registrar shall view Forms 25 and 26 by clicking on '**View Forms 25 and 26 for Digital Sign**' button, and shall Digitally Sign by clicking on '**Digital Sign**' button and shall send digitally signed Form 26 to the originating Sub Registrar by clicking on '**Send back to Originating SR**' button
8. The Form 26 should appear in the dashboard of the originating Sub Registrar
9. The originating Sub Registrar shall view the digitally signed Form 26 by clicking on '**View Digitally Signed Form 26**' button and shall file Form 26 by clicking on '**File Form 26 and Complete**' button

i. **Brief Description**


3. Section 66: Procedure after registration of documents relating to land—


(1) On registering any non-testamentary document relating to immovable property, the Registrar shall forward a memorandum of such document to each Sub-Registrar subordinate to himself in whose sub-district any part of the property is situate

(2) The Registrar shall also forward a copy of such document, together with a copy of the map or plan (if any) mentioned in section 21, to every other Registrar in whose district any part of such property is situate

(3) Such Registrar on receiving any such copy shall file it in his Book No. 1, and shall also send a memorandum of the copy to each of the Sub-Registrars subordinate to him within whose sub-district any part of the property is situate

(4) Every Sub-Registrar receiving any memorandum under this section shall file it in his Book No.





ii. Functional Step by Step Process for SECTION 66 Memorandum

Case 1:

Where the registration by DR within his jurisdictional SRs

1. The originating District Registrar follows the normal process to get the document registered and registers the document
2. The originating District Registrar after registration of the document containing the property of the concerned Sub Registrar within his jurisdiction, shall generate the Forms 25 and 26 by clicking on the '**Generate Forms 25 & 26**' button
3. The Forms 25 and 26 shall get displayed on the District Registrar's dashboard along with the particulars
4. The District Registrar shall Digitally Sign by clicking on '**Digital Sign**' button and shall send to the concerned Sub Registrar within his jurisdiction
(Note: The concerned jurisdictional Sub Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)
5. The Forms 25 and 26 should appear in the dashboard of the concerned jurisdictional Sub Registrar
6. The concerned jurisdictional Sub Registrar shall click on '**View Forms 25 and 26**' button to view the same and shall file Form 25 by clicking on the '**File Form 25**' button; the filing document number along with date gets generated both in Forms 25 and 26
7. The concerned jurisdictional Sub Registrar shall view Forms 25 and 26 by clicking on '**View Forms 25 and 26 for Digital Sign**' button, and shall Digitally Sign by clicking

- on **'Digital Sign'** button and shall send digitally signed Form 26 to the originating Sub Registrar by clicking on **'Send back to Originating DR'** button
- 8. The Form 26 should appear in the dashboard of the originating District Registrar
- 9. The originating District Registrar shall view the digitally signed Form 26 by clicking on **'View Digitally Signed Form 26'** button and shall file Form 26 by clicking on **'File Form 26 and Complete'** button

Case 2:

Where the registration by DR within other DR's jurisdictional SR


- 2. The originating District Registrar follows the normal process to get the document registered and registers the document
- 3. The originating District Registrar after registration of the document containing the property of the other district's Sub Registrar jurisdiction, shall generate the Forms 25 and 26 by clicking on the **'Generate Forms 25 & 26'** button
- 4. The Forms 25 and 26 shall get displayed on the District Registrar's dashboard along with the particulars
- 5. The District Registrar shall Digitally Sign by clicking on **'Digital Sign'** button and shall send to the other (concerned) jurisdictional District Registrar
(Note: The other (concerned) jurisdictional District Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)
- 6. The Forms 25 and 26 should appear in the dashboard of the other (concerned) jurisdictional District Registrar
- 7. The other (concerned) jurisdictional District Registrar shall click on **'View Forms 25 and 26'** button to view the same and shall forward them to the concerned jurisdictional Sub Registrar under whose jurisdiction the property is situated by clicking on **'Send to concerned SR'** button
(Note: The concerned jurisdictional Sub Registrar's address should auto-populate based on the Index Village or Road Master) to send Forms 25 and 26)
- 8. The concerned jurisdictional Sub Registrar shall click on **'View Forms 25 and 26'** button to view the same and shall file Form 25 by clicking on the **'File Form 25'** button; the filing document number along with date gets generated both in Forms 25 and 26
- 9. The concerned jurisdictional Sub Registrar shall view Forms 25 and 26 by clicking on **'View Forms 25 and 26 for Digital Sign'** button, and shall Digitally Sign by clicking on **'Digital Sign'** button and shall send digitally signed Form 26 to the originating Sub Registrar by clicking on **'Send back to Originating DR'** button
- 10. The Form 26 should appear in the dashboard of the originating District Registrar
- 11. The originating District Registrar shall view the digitally signed Form 26 by clicking on **'View Digitally Signed Form 26'** button and shall file Form 26 by clicking on **'File Form 26 and Complete'** button

- 4. **Section 67:** This section is ommitted and no longer in use.

25.1.2 Book 1 Filing Part II - For copies of maps or plans mentioned in Section 21

i. Brief Description

- (1) No non-testamentary document relating to immovable property shall be accepted for registration unless it contains a description of such property sufficient to identify the same.
- (2) Houses in towns shall be described as situate on the north or other side of the street or road (which should be specified) to which they front, and by their existing and former occupancies, and by their numbers if the houses in such street or road are numbered.
- (3) Other houses and lands shall be described by their name, if any, and as being the territorial division in which they are situate, and by their superficial contents, the roads and other properties on to which they abut, and their existing occupancies, and also, whenever it is practicable, by reference to a Government map or survey.
- (4) No non-testamentary document containing a map or plan of any property comprised therein shall be accepted for registration unless it is accompanied by a true copy of the map or plan, or, in case such property is situate in several districts, by such number of true copies of the map or plan as are equal to the number of such districts.



ii. Functional Step by Step Process

1. The Sub Registrar follows the normal process to get the document registered and registers the document
2. After the SR '**Checks and Registers**', the document number gets generated
3. The SR shall allocate to DEO to Print the Endorsement by clicking on '**Print Endorsement**' button (as in the usual process of registration)
(Note: But along with it, the print option to print the document number on Maps and Plans has to be provided)
4. The DEO shall print document number on Maps and Plans by clicking on '**Print Document No. on Maps & Plans**' button
5. While scanning the Deed Document by clicking on the '**Scan**' button, the **Plans and Maps** must also be scanned along with


25.1.3 Book 1 Filing Part III

25.1.3.1 (a) For copies of certificates of sale of immovable property granted by Civil Courts and Revenue officers

In addition to the information below, please find a detailed requirements document attached:

[https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book%20I Part%20III\(a\)%20Filing FRS.docx?d=w4e1796ed3e2d4f30bcb22f57309e2405&csf=1&web=1&e=ED3dbz](https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book%20I%20Part%20III(a)%20Filing%20FRS.docx?d=w4e1796ed3e2d4f30bcb22f57309e2405&csf=1&web=1&e=ED3dbz)

Please use the above link to access Book 1 Part 3(A) Filing detailed FRS.




25.1.3.2 (b) For statement regarding land acquired under the Land Acquisition Act, 1894, received from the Deputy Commissioner

In addition to the information below, please find a detailed requirements document attached:

[https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book%20I Part%20III\(b\)%20Filing FRS.docx?d=w67f83725f0c44caab70512cbf6dd3bd9&csf=1&web=1&e=FoodYT](https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book%20I Part%20III(b)%20Filing%20FRS.docx?d=w67f83725f0c44caab70512cbf6dd3bd9&csf=1&web=1&e=FoodYT)

Please use the above link to access Book 1 Part 3(B) Filing detailed FRS.

Part III – (b)Statement from Deputy Commissioner



ii. Functional Step by Step Process

Case 1

Definition: The Civil Court or the Revenue Officer/s issues Certificate of Sales. The claiming party shall submit to the Sub Registrar for Filing under Part III of Book 1 registration.

The applicant shall follow the usual process to get the document registered with some minor changes as stated below: (SEPARATE FLOW has to be designed)

1. User Registration (usual flow)
2. Document Information
 - a. Provide fields for incorporating Property Particulars (ie., Property Schedule)
 - b. Provide fields for capturing claiming party information (claimant)
 - c. Provide fields for capturing the authority issuing sales certificate (civil court/revenue officer) (executant)
 - d. Witness particulars (if any) (should be made optional)
3. There is NO MV Calculation
4. Stamp Duty and Scanning Fee (if any) (usual flow)
5. View Document Summary (usual flow)
6. Upload Documents with Enclosure/Annexures (including 88 Appearance Exemption Letter)
7. Submit for verification (usual flow)
8. Verification by SR (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Registration
 - a. Document submitted to the SR
 - b. SR checks and registers by way of Filing in Part III of Book 1
 - c. Scan the document and upload (store) in Part III Book 1
 - d. Delivery of Filing document (by FDA/SDA to the Presenter) and followed by printing of Acknowledgement

Case 2

Definition: The Land Acquisition Orders under the Land Acquisition Act, 1894 received from the Deputy Commissioners. The Deputy Commissioners shall send to the Sub Registrar, the copy of the Land Acquisition Orders for Filing under Part III of Book 1 registration and make entry in the Index

NOTE: Follow SIMILAR PROCESS as followwd in the COURT ORDER ENTRY Module

25.1.4 Book 1 Filing Part IV - Copies of the instruments and collateral securities executed Under the Karnataka Land Improvement Loans Act, 1963 (Karnataka Act 16 of 1963) and the Karnataka Agriculturists Loans Act, 1963 (Karnataka Act 17 of 1963), received from Revenue officers


- (a) Form 3
- (b) Mortgage Deed



Kaveri Application Home Screen

Inputs: DEO shall login to the Kaveri System


Output: All the modules of the Kaveri system shall be displayed to the DEO



FRUITS application access Screen

Inputs: DEO shall click on the FRUITS Module

Output: System shall ask the user whether he wants to process the applications received from FRUITS or not



After clicking FRUITS, detailed page of the Filing Document shall be displayed to the User

Inputs: User shall select “Yes” in the previous screen to process the applications received from FRUITS

Output: The system shall be redirected to the detailed page which has Form-3, Form-3 with Court Orders, Mortgage & Other and Status of the filing document

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

File Document Refresh

☐	Sr. No.	Form 3	Summary	Received On	Reference No	Deed Type
☒	1	View Form 3	View	05/01/2022 12:41:50	202200156690	Mortgage
☐	2	View Form 3	View	05/01/2022 12:41:53	202200156740	Mortgage

View Application Details Print


 Government of Karnataka
 Department of Stamps and Registration
 Print Date: 1/6/2022 1:27:31 PM
 Ref: KAVERI - FRUITS Integration
 Mortgage Deed
 Land Parcel Details 1 of 3
 Bhoomi District : Chikkaballapura(28), Bhoomi Taluk : Chikkaballapur
 Bhoomi Hobli : ಮಂಡಿಕಲ್, Bhoomi Village : ಶೆಟ್ಟಿಗರೆ
 (Kaveri Hobli : Mandikal Hobli, Kaveri Village : Shettigere.)
 Land Code : 469
 Property No. : 90*3

Total Documents: 11595
District: Chikkaballapura
Welcome to KAVERI Ver

1/6/2022 About

Form-3 Summary Screen

Inputs: User shall click on View Summary in the Form-3 page to process the Filing

Output: After clicking on view summary in Form-3 page, the summary of the Filing document with Property details and Owner details shall be displayed to the user where user can take a print of the same and verify with the original filing deed

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

File Document Refresh

☐	Sr. No.	Form 3	Summary	Received On	Reference No	Deed Type
☒	1	View Form 3	View	05/01/2022 12:41:50	202200156690	Mortgage
☐	2	View Form 3	View	05/01/2022 12:41:53	202200156740	Mortgage
☐					00156761	Mortgage

612022585637770724635850506.pdf - Adobe Reader

File Edit View Window Help

1 / 2 44.4% Tools Sign Comment

Signed and all signatures are valid. Signature Panel

Form 3 Document
FORM OF DECLARATION
(See Rule 4, Section 6 of Karnataka Agricultural Credit operations & Miscellaneous Provisions Act, 1974)

Sri/Smt./Kum. Manunatha Son / Wife / daughter of Byrappa aged about 41 years residing at SHETTERI VILLAGE, Chikballapur Taluk, Chikballapur District being desirous of taking financial assistance from Canara Bank, PERESANDRA Branch, amongst other, at PERESANDRA place on 04 Jan 2022 make this declaration as required by Section 6 of the Karnataka Agricultural Credit operations and miscellaneous Act, 1974 (Act 2, 1975) and that I / We own land immovable property or hold land as specified in the schedule and I / We hereby mortgage, create a charge on such land immovable property in favour of Canara Bank, PERESANDRA BRANCH as security for payment of the amount of financial assistance of Rs.250000.00 (Rupees _____) sought by me/us and also for all further assistance which the above Bank may give me / us together with interest there on and for all costs and expenses connection therewith.

SCHEDULE

SN	Village	Hobli	Taluk	Survey no & Block no. or Hissa No.	Extent	Assessment
1	shettigeri	mandikallu	chikballapur	71/9	0/10/0.00	250000
2	shettigeri	mandikallu	chikballapur	72/8	1/11/8.00	250000
3	shettigeri	mandikallu	chikballapur	90/3	0/8/0.00	250000

Survey Number with their boundaries:

SN	Survey no	East	West	North	South	Approximate value	Encumbrance if any, nature of amount
1	71/9	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	250000	250000
2	72/8	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	250000	250000
3	90/3	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	PRIVATE PROPERTY	250000	250000

Total Documents: 115999, Registered District: Chikballapur

Welcome to KAVERI Version 8.6.0


DEQ_III_CKB 1:28 PM 1/6/2022 About

6120...

Form 3 Screen

Inputs: User shall click on View Form-3 to process the filing

Output: After clicking on view Form-3, a digitally signed Form-3 shall be displayed to the user. Form-3 has details such as Property Schedule and Owner details.



Form-3 Screen

Inputs: User shall select the particular application for filing

Output: The system shall ask the user whether he wants to file the application or not

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

File Document Refresh

☐	Sr. No.	Form 3	Summary	Received On	Reference No	Deed Type
☒	1	View Form	IF	05/01/2022 10:41:50	000000100000	Mortgage
☐	2	View Form				Mortgage
☐	3	View Form				Mortgage

Digital Signer

Registered Token Details In Kaveri Online Services

Name

USB Token Serial No 26411E7001054120

USB Token PIN

[Proceed](#) [Cancel](#)

[Digital Sign](#)

Note : Form 3 is available for above transactions.

Total Documents: 115999, Registered Documents:113748, Pending Documents:2251
 District: Chikkaballapura, Sub Registrar: Chikkaballapur
 Server Name: CCB_R1


Welcome to KAVERI Version 8.6.0 Designed and Developed by C-DAC, Pune. DEQ_III_CKB 1:28 PM 1/6/2022 About

Start ISM-K... Untit... Logite... ID And... DR-C1... Canon... 3 Ka... Docu... 61202... 1:28 PM

Digital Signature Screen

Inputs: User shall select yes in the previous screen to do the filing

Output: System shall ask the user to do the digital signature. After that, Digital Signature screen shall be displayed to the user by which User shall do the Digital Signature



Digital Signature Confirmation Screen

Inputs: User shall complete the Digital Signature in the previous screen

Output: After Digital Signature, the system shall display the prompt of “Filing is in process” and completed the Filing process.

Upon completion of the Filing process, XML file shall be created and sent to the Bhoomi

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

Accept Document Refresh

Sr. No.	Summary	Received On	Reference No	Deed Type	File
1	View	05/07/2021 15:47:22	202100000050	Release	Accept
2	View	05/07/2021 15:47:23	202100000060	Release	Accept
3	View	07/12/2021 19:36:17	202100041260	Mortgage	Accept
4	View	31/12/2021 11:38:16	202100128980	Mortgage	Accept
5	View	03/01/2022 15:38:45	202200142930	Mortgage	Accept

Note : Form 3 is not available for above transactions.

Total Documents: 115999, Registered Documents:113748, Pending Documents:2251
 District: Chikkaballapura, Sub Registrar: Chikkaballapur
 Server Name: CKB_R1

Welcome to KAVERI Version 8.6.0
 Designed and Developed by C-DAC, Pune.

DEQ_III_CKB 1:29 PM 1/6/2022 About

Start ISM-Kan... Untitled... Logitec... ID And E... DR-C13... Canon L... 2 Kave... Docume... 1:29 PM

Inputs: System shall display all the registered documents list to the User

Output: User shall click on “Accept” to complete the Filing Process.

Upon completion of the Filing process, XML file of the J Slip shall be created and sent to the Bhoomi

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

From Date: 06 January 2022

To Date: 06 January 2022

Get Status

Document No./Final Registration No.	Reference No	Action	Status	Date
CKB-I Part-IV-00089-2021-22	202200153060	AutoFiled	Filed	06/01/2022 12:22:08
CKB-I Part-IV-00090-2021-22	202200153090	AutoFiled	Filed	06/01/2022 12:36:10
CKB-1-04557-2021-22	202200160610	Registered	Registered	06/01/2022 13:10:49
CKB-I Part-IV-00091-2021-22	202200156690	AutoFiled	Filed	06/01/2022 13:29:26

Total Documents: 115999, Registered Documents:113748, Pending Documents:2251

District: Chikkabalkapura, Sub Registrar: Chikkabalkapur

Server Name: CKB_R1

Welcome to KAVERI Version 8.6.0

Designed and Developed by C-DAC, Pune.

DEQ_III_CKB 1:30 PM 1/6/2022 About

Start ISM-Kan... Untitled... Logitec... ID And E... DR-C13... Canon L... 2 Kave... Docume... 1:29 PM

Inputs: User shall click on “Status”

Output: System shall display all the Filed documents along with the status of the application to the user

Filing of documents through FRUITS application

Filing of documents through FRUITS application is the process for facilitating the Registration of Mortgage deed and Filing of copy Form-3 declaration for loans or advances sanctioned by the Commercial banks, Rural Banks and Cooperative Societies for agriculture purpose

25.1.4.1 Filing of Form 3 for Agriculture Loan through FRUITS

i. **Brief Description**

If the loan amount is less the 3 lakh those documents will be considered under Form 3 for Filing. Filing of Mortgage deed through Form 3 does not require party to be present in the office of the Sub Registrar. Since this is with respect to agriculture loan, Government has given exemption of Stamp Duty and Registration Fee. Hence there is no Market Value Calculation, Stamp Duty and Registration Fee

ii. **Functional Step by Step Process**

1. Sub Registrar shall login to the Kaveri system and clicks on “Filing of documents from FRUITS”
2. The system shall display the detailed page which has Form-3, Form-3 with Court Orders, Mortgage & Other and Status of the filing document
3. Sub Registrar shall select Form 3 document for Filing

Gateway of KAVERI Version 8.6.0

KARNATAKA VALUATION AND e-REGISTRATION

FRUITS Details

Form 3 | Form 3 with Court Orders | Mortgage & other | Status

File Document Refresh

☐	Sr. No.	Form 3	Summary	Received On	Reference No	Deed Type
☒	1	View Form 3	View	05/01/2022 12:41:50	202200156690	Mortgage
☐	2	View Form 3	View	05/01/2022 12:41:53	202200156740	Mortgage
☐	3	View Form 3	View	05/01/2022 12:41:55	202200156761	Mortgage

Digital Sign

Note : Form 3 is available for above transactions.

Total Documents: 115999, Registered Documents: 113748, Pending Documents: 2251
 District: Chikkaballapura, Sub Registrar: Chikkaballapur

Welcome to KAVERI Version 8.6.0 Designed and Developed by C-DAC, Pune. DEO_IIL_CKB 1:26 PM 1/6/2022 About

Start ISM-Kan... Untitled... Logitec... ID And E... DR-C13... Canon L... 2 Kave... Docume... 1:26 PM

4. After clicking on Form 3, all the Form 3 requests submitted by various applicants to banks are displayed. The banks create applications in FRUITS application (developed by NIC). SRO views applications submitted via FRUITS on SRO dashboard. Each Form 3 document has the following details
 - View Form 3 – It is a digitally signed Form, received from bank (FRUITS) which has information on Date of receipt, Bank details (Bank Name), Farmer related details (party details—Name, Address), Property details (survey number, extent), Loan amount (Consideration Amount)

**Form 3 Document
FORM OF DECLARATION**

(See Rule 4, Section 6 of Karnataka Agricultural Credit operations & Miscellaneous Provisions Act, 1974)

Sri/Smt./Kum. PARASAPPA Son / Wife / daughter of Yallappa aged about 67 years residing at WARD NO 8 UPPAR STREET, KINNAL TO KOPPAL, koppal Taluk, Koppal District being desirous of taking financial assistance From RAICHUR DCC Bank, PACS KINNAL Branch, amongst other, at PACS KINNAL place on 03 Mar 2022 make this declaration as required by Section 6 of the Karnataka Agricultural Credit Operations and miscellaneous Act, 1974 (Act.2, 1975) and that I / We own land immovable property or hold land as specified in the schedule and I / We hereby mortgage, create a charge on such land immovable property in favour of RAICHUR DCC Bank, PACS KINNAL BRANCH as security for payment of the amount of financial assistance of Rs.150000.00

(Rupees _____) sought by me us and also for all further assistance which the above Bank may give me / us together with interest there on and for all costs and expenses connection there with.

SCHEDULE

SN	Village	Hobli	Taluk	Survey no & Block no. or Hissa No.	Extent	Assessment
1	kinnala	Irakallagada	koppal	71/1	1/31/0.00	150000

Survey Number with their boundaries						Approximate value	Encumbrance if any, nature of amount
SN	Survey no	East	West	North	South		
1	71/1	KISHOREBABU	PLOT	PLOT	DYAMAPPA	150000	150000

If the immovable property is not land furnish full particulars of the immovable property

01. Land owned and land as tenant to be shown separately

02. Strike out whichever is not applicable.

I / We hold the land described above as owners / tenants

I / We hereby declare that the facts stated above are true and correct to the best of my knowledge and belief.

Place: PACS KINNAL

Date : 03 Mar 2022

Signature of the applicant's

Applicant's signature attested by:

Here specify the name and address of witness;

Signature Not Verified

This document was digitally signed on 2022.03.03



Signature Not Verified

This document was digitally signed on 2022.03.03



Applicant's signature attested by:
Here specify the name and address of
witness;

Signature Not Verified
This document was digitally signed
on 2022.03.03

Signature Not Verified
This document was digitally signed
on 2022.03.03

Form 3 Document
FORM OF DECLARATION

(See Rule4, Section 6 of Karnataka Agricultural Credit operations & Miscellaneous Provisions Act, 1974)

Digitally signed by CHANDRASHEKHAR
KUDRIMATI
Date: 2022.03.03 16:48:11 +05:30
Reason: FRUITS BANK
Location: Branch Office



This document is automatically filed as KOL-I Part-IV-00587-2021-22
on 23-03-2022 06:07:38 PM at Koppala-SRO

Digitally Signed By:
NAGENDRAPPA
Designation : Sub-Registrar

- View Summary – Same details of Form 3 which is generated in Kaveri application based on the Bhoomi data



Government of Karnataka
Department of Stamps and Registration

Print Date:07/04/2022 03:22:13 PM
Integration

Ref: KAVERI - FRUITS

Reference No.:202200000760
PM

Data Recieved Date: 01/04/2022 12:53:30

Mortgage Deed

Land Parcel Details 1 of 1

Bhoomi District Code: 7, Bhoomi Taluk Code: 1, Bhoomi Hobli Code: 1, Bhoomi Village Code: 1
(Kaveri Hobli : Yelburga Hobli, Kaveri Village : Katral (Yelburga Hobli))
Land Code : 69
Property No. : 76*1
(Survey No. :76, Survey No. Character :*, Hissa No. : 1)
Acre : 4, Gunta : 4, Gunta F.: 0
Consideration Amount (In Rs): 1

(Note : Kaveri Village names are displayed as per Bhoomi mapping details,)

BHOOMI Owner Details : [Executant]

Owner Details 1 of 1

Owner Name : ರಾಜಪ್ಪ
Address : sadASDsdasdfsdf
Mobile No.: 9663869607
Bincom : 1
Relative Name : ಲೇ.ರಂಗಶೆಟ್ಟಿ
Owner No.:3
Main Owner No.:3
Sex : F
Age : 33
EPIC :
PAN :

BHOOMI Owner Details : [Executant]**Owner Details 1 of 1**

Owner Name : ರಾಜಪ್ಪ
Address : sadASDasdasdfasdf
Mobile No.: 9663869607
Bincom : 1
Relative Name : ಲೇ.ರಂಗಶೆಟ್ಟಿ
Owner No.:3
Main Owner No.:3
Sex : F
Age : 33
EPIC :
PAN :

about:blank

07/04/2022

Page 2 of 2

Bank Details : [Claimant]

Bank Name : Canara Bank, Branch Name : NELAMANGALA 2
Branch Address : ROOPA THEATRE COMPLEX,B,H,ROAD,NELAMANGALA 562123
Branch Mobile No. : 9663869607
Branch EPIC :
Branch PAN :

Note : Above application details are recieved from FRUITS system and displayed as it is.

- Document received details (Date and Time), Reference Number and Deed Type
- 5. The Sub Registrar shall accept the document for filing by digitally signing on the Form 3 document
- 6. Filing data should be stored in Book 1 Part IV
- 7. After Digitally Signing, an XML file along with the reference number shall be sent to Bhoomi

25.1.4.2 Filing of Form 3 if there is a Court Order on the property

1. When the Form 3 application is received from Fruits, auto search will happen to find the court orders
2. If the Court Order is found, the Sub Registrar has to decide whether to Register or Reject the application
3. If it is accepted, the Document gets Filed
4. If it is rejected, then the rejected status shall be sent back to the FRUITS application through XML file

25.1.4.3 Mortgage Deed through FRUITS

i. **Brief Description**

If the Loan amount advanced by the Bank is more the 3 lakh, then those documents will be considered as Mortgage Deed documents. Such documents should follow the usual process of registration. It doesn't come under filing of documents.

ii. **Functional Step by Step Process**

1. User Registration (usual flow)
2. Document Information (usual flow)
 - a. Select the following
 - i. Nature of Document – 'Mortgage'
 - ii. Article - 'Mortgage'
 - iii. Sub-article – either 'With Possession' or 'Without Possession'
 - iv. Book Number - 1
3. Property Search (usual flow)
 - a. Create an additional field to fetch the particulars wrt property, property schedule, party details, consideration, stamp duty & registration fee (including scanning)
4. Property Schedule (included in step 3)
5. Party Details (included in step 3)
6. MV, Stamp Duty & Fee Calculation (included in step 3)
 - a. MV isn't applicable
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
12. Document Registration (usual flow)
 - a. Upon completion of Registration process, XML file of the Confirmation Intimation shall be created and sent to the Bank through FRUITS

25.1.5 Book 1 Filing Part V - Copies of instruments received from the Land Development Banks under Section 85-A of the Karnataka Co-operative Societies Act, 1959 (Mortgage Deed)

i. **Brief Description**

If the Land Development Banks send the Mortgage Deeds through FRUITS or directly through the parties, the Registration takes place. If the Form 3 is sent, it will be filed as it is done in Part IV or if the Mortgage Deed is sent, it will be Registered as done in the case of 23.4.3 (Mortgage Deed through FRUITS)

ii. **Functional Step by Step Process**

1. User Registration (usual flow)
2. Document Information (usual flow)
 - a. Select the following
 - i. Nature of Document – ‘Mortgage’
 - ii. Article - ‘Mortgage’
 - iii. Sub-article – either ‘With Possession’ or ‘Without Possession’
 - iv. Book Number - 1
3. Property Search (usual flow)
 - a. Create an additional field to fetch the particulars wrt property, property schedule, party details, consideration, stamp duty & registration fee (including scanning)
4. Property Schedule (included in step 3)
5. Party Details (included in step 3)
6. MV, Stamp Duty & Fee Calculation (included in step 3)
 - a. MV isn’t applicable
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
12. Document Registration (usual flow)
 - a. Upon completion of Registration process, XML file of the Confirmation Intimation shall be created and sent to the Bank through FRUITS

25.1.6 Book 1 Filing Part VI – Copies of the court order directing the concern Sub Registrar to make a note of charge or encumbrance of the party or surety and its extinguishment on the immovable property, concerning the amount due or the surety amount, in the indices prescribed under the act

i. **Brief Description**

The Copies of the court order directing the concern Sub Registrar to make a note of charge or encumbrance of the party or surety and its extinguishment on the immovable property, concerning the amount due or the surety amount, in the indices prescribed under the act

In addition to the information below, please find a detailed requirements document attached:

https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Book-1%20Part%20VI_Copies%20of%20court%20order%20V1.1.docx?d=w360c9e513d8a440ebd25b067cfacf541&csf=1&web=1&e=VpZ1Ud

Please use the above link to access Book 1 Part VI Filing detailed FRS.

ii. **Functional Step by Step Process**

FOLLOW COURT ORDER ENTRY MODULE (Add & Edit Options) (Module No. 18)

MEMO CONCEPT

In case of change of Jurisdiction during Registration of Document, then the Origination SR (ie., Registration SR ie., R-SR) sends a MEMO to the Jurisdictional SR (J-SR)

Registration SR (R-SR) Login

1. 2 Buttons shall be present in the Registration SR (R-SR) Login - 'Print' & 'Send' buttons

2. Here, Print button for printing the Form 25

and Send button for marked as sent by R-SR to Jurisdictional SR (J-SR)

Jurisdictional SR (J-SR) Login

1. 3 Buttons shall be present in the Jurisdictional SR (J-SR) Login - 'View', 'Accept' and 'Print' buttons

2. Here, 'View' button for viewing the Form 25

'Accept' button for accepting the Form 25 and sending back Form 26 to the R-SR

'Print' button for printing the Forms 25 and 26

On clicking on 'Accept' button, the following things must happen:

1. Creation/Generation of New Document ID

2. Execution Date - will be the Same

3. Presentation Date - will change

4. Stamp 1 to Stamp 5 Date & Time - as Current Dates only

5. CD No. ()

6. R-SRO will be changed to J-SRO

7. Document No. & Final Registration No. Generated

8. All the Transaction Tables must be Updated Simultaneously - Document Master, Party Master, Property Master, Property Schedule Master, Property No. Details (Tables)

9. Update Document Master with Final Registration No., Book Type and Part Details

10. Generate Form 26 and send the same to R-SR

Registration SR (R-SR) Login

1. Generate and Print Endorsement at R-SR - must Print Only 60 Certificate
2. Replace OLD Registration No. with NEW Registration No.

25.2 (ii) A separate file shall also be opened for filing copies translations presented under sections 19 and 62 of the act or under rule 12(1). The copies and translation placed in this file shall be connected by a cross reference with the entry in the register

As per the provision of the Act, the copies of the translation can be scanned along with the original document and stored

25.3 (iii) A separate file shall also be maintained for communications received from officers of other departments intimating the cancellation, modification or rectification of transactions evidenced by papers previously filed or registered

As per the provision of the Act, the copies of the translation can be scanned along with the original document and stored

In addition to the information below, please find a detailed requirements document attached:

[https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Book%201%20Rule%2017%20\(3\)%20Module%20FRS%20V.01.docx?d=w462ffa17685641a185691bb0cc1090af&csf=1&web=1&e=wWRQNH](https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Book%201%20Rule%2017%20(3)%20Module%20FRS%20V.01.docx?d=w462ffa17685641a185691bb0cc1090af&csf=1&web=1&e=wWRQNH)

Please use the above link to access Rule 17(3) Filing detailed FRS.

26 EXCEPTIONAL CASES

26.1 Attendance at Private Residences (Private Attendance)

i. **Brief Description:**

In the exigencies, ill-health or detained in custody, if requested for visiting to private residence on payment of private residence fee and conveyance, the SR visits the private residence of the party or detention place and registers the document.

ii. **Process Flow Diagram:**




Figure: Process Flow Diagram for Private Attendance

iii. **Functional Step by Step Process:**

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (usual flow)
4. Property Schedule (usual flow)
5. Party Details (usual flow)

6. MV, Stamp Duty & Fee Calculation (usual flow)
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
 - a. After the DEO prints and uploads the document summary, the SR confirmation is required
12. Document Registration
 - e. But the SR keeps the document pending ('Document Kept Pending') during the document registration process where the reason for pending gets recorded in the Minute Book and Endorsement is printed on the document
(Note: Once the DEO prints the Endorsement, the pending status should revert back to SR login)
13. Exceptional Cases
 - a. As the document is kept pending, it comes under exceptional case
 - b. The applicant has to request for private attendance (either before or after submission of application form) depending on the exigencies (an application is made for the same, if required) along with Payment of Private Attendance Fee & Medical Certificate
 - c. On payment of fee for private attendance, the application gets retrieved from the Minute Book
(Note: 1. Rs.1000 per person is charged as fee for private attendance (transportation arrangement for the SR has to be made by the applicant only);
2. Two identifying witnesses are required (to be present at the given location);
3. The SR would visit the party/parties at their private residences after working hours (in the evening) based on his/her availability and time constraints in usual scenario)
 - d. The party has to Book an Appointment and shall mention the Location for Private Attendance; usually the SR visits the applicant on the same day based on the medical certificate (ie., the medical condition of the applicant); ifn't the SR will schedule another day based on his/her availability – in either case, SR will intimate the applicant
 - e. Then the SR will pay visit to private residence of the party (ie., the executant for sale deed & presenter for the will) within his jurisdiction; if out of SR's jurisdiction, then a commission is sent to the jurisdictional SR where he follows the below steps:
 - i. Verify the party's identity
 - ii. Takes the party's photo & thumb impression
 - iii. Get identified by 2 witnesses
 - iv. Records the Deposition
 - v. Takes the signature of the party and 2 witnesses

- f. If the SR is satisfied, then after arriving back to the SRO office, shall start the registration process by clicking on '**Check and Register**' button, thereby generating the registration number (ie., the SR registers the document)
- g. From this step onwards, follow the usual process and get the document registered
- h. DR needs to be notified (by SR) after the registration process is completed

iv. **Process Abstract**

Registration Rules, 1965 (Chapter X)

1. Application for attendance at a private residence

An application for attendance at a private residence shall be in writing and shall, in all possible cases, be signed by the person seeking the concession though it may be presented by any person to the Registering officer.

2. Attendance at a private residence

A requisition for attendance at a private residence shall be complied with as early as possible. If compliance would interfere with the regular business of the office or involve the closing of the office and if the case does not fall under the proviso to Section 31 of the Act, a commission should if practicable, be issued. Every such attendance by a Sub-Registrar or under his orders shall be reported to the Registrar within 24 hours.

3. Attendance at a private residence by the Registrar/Sub-Registrar

A Registrar may attend at a private residence situated within the limits of his district even though it may not lie within the sub-district for the purpose.

4. Persons exempt from personal appearance

(i) Persons exempt by law from personal appearance in Court are, under the Code of Civil Procedure, 1908

(a) women, who according to the customs and manners of the country, ought not to be compelled to appear in public, and

(b) persons of rank especially exempted by the Government.

(ii) A list of persons exempted under clause (i) (b) shall be obtained by the Registrar from the High Court or District Court and communicated to every Sub-Registrar in his district.

(iii) When in the course of attendance at a private residence the Registering officer is required to record in respect of the same document the admission of execution of persons not entitled to the concession, the request may be complied with, provided that an attendance fee is levied in respect of each such person.

5. Form and procedure of payment of commission

(i) A commission issued under Section 33 or Section 38 shall be prepared in the form hereunder* and shall, when the person to be examined resides within the sub-district, be addressed ordinarily by the registering office to one of his clerks, if any. When the person to be examined resides in another sub-district, whether within the same district or in another district, the commission shall be directed to the Sub-Registrar of the latter sub-district. The Sub-Registrar receiving a commission so addressed may, if he cannot attend personally, redirect it to any officer of his establishment vide also Sections 75 and 76 of the Code of Civil procedure, 1908.

The form above referred to.

*Commission under Section 33 or Section 38 of the Indian Registration Act, 1908.

To

The District Registrar/Sub-Registrar.

Whereas the accompanying power-of-attorney/document, dated the and purporting to have been executed by A.B. son of residing in your sub-district has been presented for attestation/registration in this office and whereas it is necessary that it should be ascertained whether it has been voluntarily executed by the person by whom it purports to have been examined in connection.

Executed take -
----- you are hereby requested to ----- the examination
of

therewith order
..... upon the interrogatories hereunto attached and to return this commission with
the examination of the said to this office on or before the day of

Given under my hand and seal this day of 20

Signature of Registering Officer.

Seal.

(ii) When the commission is for the examination of an executant, and has been executed, the Commissioner shall return the document to the office from which it was issued endorsed as follows.

Having attended the at residence of A.B., son of C.D., at I have this day examined the said A.B., who has been identified to my satisfaction by E. F., son of G. H., etc., resident of And the said A.B., admitted (or denied) the voluntary execution of this power-of-attorney/the execution of this document.

Left thumb impression of executant when necessary.

Full signature of the executant.

Signature of witnesses.

Commissioner.

(iii) Where receipt of consideration is acknowledged before the Commissioner, he shall add the following clause to this endorsement:

“and acknowledged receipt of Rs. (or goods to be specified) being consideration (in whole or in part).”

(iv) Where consideration is paid in the presence of the Commissioner, he shall add the following to the endorsement.

“I also certify that Rs. (or goods to be specified) were paid (or delivered) in my presence to the said A.B. by.”

The signature of the payee and payer shall also be taken below this endorsement, as provided in the specimen form in Schedule B.

(v) On receiving the Commissioner’s report, the Registering Officer shall, if satisfied as to the execution of the document, make the following endorsement below the report.

“From the foregoing report I am satisfied that this Power-of Attorney/document has been voluntarily executed by the said A.B.”

Date:

Signature of Registering Officer.

6. Manner of examination of witnesses

A commissioner may examine witnesses in the same manner as a Registering Officer and persons who may be required to give evidence before a Commissioner and who refuse to do so shall be subject to the penalties and punishments which they would incur for the same offence if committed in a Registration Office.

7. Manner of examination by the Registering Officer

A Registering Officer may examine the Commissioner personally in his office touching any of the circumstances connected with the discharge of his commission, especially with reference to the voluntary nature of the admission of execution.

26.2 Under-valuation

i. Brief Description:

The property to be registered is below the estimated guideline value as per the provision of section 45A, then such documents are referred to DR for detection of under-valuation.

ii. Process Flow Diagram:




Figure: Process Flow Diagram for Under-Valuation

iii. Functional Step by Step Process:

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (usual flow)
4. Property Schedule (usual flow)
5. Party Details (usual flow)
6. MV, Stamp Duty & Fee Calculation (usual flow)

7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment
 - a. If the party isn't accepting to pay the stamp duty as per the market value as determined by the SR, then the party has the option to go for 'Under-valuation'.
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
 - b. After the DEO prints and uploads the document summary, the SR confirmation is required
12. Document Registration
 - a. But the SR keeps the document pending ('Document Kept Pending') during the document registration process where the reason for pending gets recorded in the Minute Book and the Endorsement is printed on the document
(Note: Once the DEO prints the Endorsement, the pending status should revert back to SR login)
13. Exceptional Cases
 - a. As the document is kept pending, it comes under exceptional case
 - b. The applicant has to request for Under-valuation (ie., as per section 45-A)
 - c. The SR then shall refer such document(s) to DR for detection of Under-valuation
 - d. The DR shall visit the property for assessing market value of the property
 - e. After assessment, the DR will pass an Order (ie., the DR Order) and send it to both the party and the SR
 - f. If the party agrees to the DR valuation, then the Deficit Stamp Duty Fee will be paid by the party through K2 portal by filling 'Add Challan' option in the payment section
(Note: if the party isn't agreeing to DR valuation, then the appeal lies with the regional commissioner (of revenue); next appeal to High Court)
 - g. On payment of fee for Under-valuation, a message should come to the SR and the application gets retrieved from the Minute Book
 - h. Confirmation of the SR (only for the payment of fee for under-valuation) is required at this point if time
 - i. Once the SR gets the confirmation of the payment being made by the party, the SR shall start the registration process by clicking on '**Check and Register**' button, thereby generating the registration number (ie., the SR registers the document)
 - j. From this step onwards, follow the usual process and get the document registered

iv. **Process Abstract**

Karnataka Stamp Act, 1957

1. Instrument of conveyance, etc. undervalued how to be dealt with.

(1) If the registering officer appointed under the Registration Act, 1908 (Central Act XVI of 1908) while registering any instrument of,-

- (a) Conveyance [section 2(1)(d)];
- (b) Gift [Article 28(a)];
- (c) Exchange of property (Article 26);
- (d) Settlement (Article 48-A(i))
- (e) Reconstitution of Partnership (Article 40-B (a));
- (f) Dissolution of partnership (Article 40-C (a));
- (g) An agreement to sell covered under sub-clause (i) of clause (e) of Article 5;
- (h) a lease covered under item 8 [(vi)] 8 of Article 30;
- (i) A power of Attorney covered under clause (e), clause (ea) and clause (eb) of Article 41;
- (j) Release 6 [(Article 45-(a))6];
- (k) Conveyance under a decree or final order of any Civil Court

has reason to believe having regard to the estimated market value published by the Committee constituted under section 45B, if any or otherwise, that the market value of the property which is the subject matter of such instrument has not been truly set forth, he shall after arriving at the estimated market value, communicate the same to the parties and unless the parties pay the duty on the basis of such valuation, shall keep pending the process of registration and refer the matter along with a copy of such instrument to the Deputy Commissioner for determination of the market value of property and the proper duty payable thereon.

(l) Agreement [Article 5(f)] 306 1957: KAR. ACT 34]

(m) Award [Article 11(a)]

(n) Trust [Article 54 (A) (iii)]

(o) Transferable Development Rights [Article 20(7)]

(2) On receipt of a reference under sub-section (1), the Deputy Commissioner shall, after giving the parties a reasonable opportunity of being heard and after holding an inquiry in such manner as the State Government may by rules prescribe, determine by order as for as may be within ninety days from the date of receipt of such reference the market value of the property which is the subject matter of instrument specified in sub-section (1) and the duty payable thereon. The difference, if any, in the amount of duty, shall be payable by the person liable to pay the duty with interest at twelve percent per annum if he does not pay within ninety days from the date of order of the Deputy Commissioner

Provided that the payment of interest is not applicable to instruments executed prior to 31st day of March, 2006.

(3) The Deputy Commissioner may, suo motu within two years from the date of registration of any instrument specified in sub-section (1) not already referred to him under sub-section (1), call for and examine the instrument for the purpose of satisfying himself as to the correctness of the market value of the property which is the subject matter of any instrument specified in subsection (1) and the duty payable thereon and if after such examination he has reason to believe that the market value of such property has not been truly set forth in the instrument, he may determine by order the market value of such property and the duty payable thereon in accordance with the procedure provided for in sub-section (2). The difference, if any, in the amount of duty, shall be payable by the person liable to pay the duty with interest at twelve percent per annum if he does not pay within ninety days from the date of order of the Deputy Commissioner:

Provided that nothing in this sub-section shall apply to any instrument registered before the commencement of the Karnataka Stamp (Amendment) Act, 1975

Provided further that the payment of interest is not applicable to instruments executed prior to 31st day of March 2006.

(4) The order of the Deputy Commissioner under sub-section (2) or (3) shall be communicated to the person liable to pay the duty. A copy of every such order shall be sent to the registering officer concerned.

(5) Any person aggrieved by an order of the Deputy Commissioner under sub-section (2) or sub-section (3) may, prefer an appeal before the Regional Commissioner and all such appeals 1957: KAR. ACT 34] Stamp 532 shall be preferred within such time and be heard and disposed off in such manner as the State Government may by rules prescribe

Provided that no appeal shall be admitted unless the person aggrieved has deposited, in the prescribed manner, fifty percent of the difference in the amount of duty as determined by the Deputy Commissioner under sub-section (2) or (3):

Provided further that where after the determination of the market value by the Appellate Authority or determined again by the Deputy Commissioner on a remand of the case the stamp duty borne is found to be sufficient, the amount deposited shall be returned to the person concerned:

Provided also that such person shall pay the difference in duty along with interest at twelve percent per annum if he does not pay within ninety days from the date of order of the Deputy Commissioner or sixty days from the date of order of the Appellate Authority, so however, the payment of interest is not applicable to instruments executed prior to eighteenth day of August 1999

26.3 Impound

i. Brief Description:

The document being stamped short of stamp duty than the required, then it is impounded u/s either 33 by any public officer or u/s 34 by the court. Accordingly, deficit of stamp duty required to be made good and penalty to be recovered under the orders of DR (deputy commissioner of stamps).

ii. Process Flow Diagram:




Figure: Process Flow Diagram for Impound

iii. Functional Step by Step Process:

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (usual flow)
4. Property Schedule (usual flow)
5. Party Details (usual flow)

6. MV, Stamp Duty & Fee Calculation (usual flow)
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment
 - a. If the party is unable to pay the proper stamp duty as per the market value as determined by the SR, then the party resorts to go for 'Under-stamping' (Impound)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
 - b. After the DEO prints and uploads the document summary, the SR confirmation is required
12. Document Registration (usual flow)
 - a. But the SR keeps the document pending ('Document Kept Pending') during the document registration process where the impounding gets recorded in the Minute Book and the Endorsement is printed on the document
(Note: Once the DEO prints the Endorsement, the pending status should revert back to SR login)
13. Exceptional Cases
 - a. The document is imported due to short levy of stamp and kept pending, it comes under exceptional case
 - b. The SR then shall impound the document and send to DR for Orders
 - c. The DR shall issue notice to the party for payment of short levy of stamp duty
 - d. The DR will pass an Order (ie., the DR Order) and send it to the party and the SR
 - e. The party shall pay the deficit stamp duty and penalty through K2 portal by filling 'Add Challan' option in the payment section
(Note: if the party isn't agreeing to DR valuation, then the NO appeal)
 - f. On payment of deficit stamp duty and penalty, the party shall enter the challan number and shall submit to SR
 - g. On confirmation of the SR, the application gets retrieved from the Minute Book
 - h. The SR shall start the registration process by clicking on '**Check and Register**' button, thereby generating the registration number (ie., the SR registers the document)
 - i. From this step onwards, follow the usual process and get the document registered

iv. Process Abstract

Karnataka Stamp Act, 1957 (CHAPTER IV INSTRUMENTS NOT DULY STAMPED)

1. Examination and impounding of instruments

(1) Every person having by law or consent of parties' authority to receive evidence, and every person in charge of a public office, except an officer of police, before whom any instrument, chargeable in his opinion, with duty, is 1957: KAR. ACT 34 produced or

comes in the performance of his functions, shall, if it appears to him that such instrument is not duly stamped, impound the same.

(2) For that purpose every such person shall examine every instrument so chargeable and so produced or coming before him, in order to ascertain whether it is stamped with a stamp of the value and description required by the law in force in the State of Karnataka when such instrument was executed or first executed: Provided that,

(a) nothing herein contained shall be deemed to require any Magistrate or Judge of a Criminal Court to examine or impound, if he does not think fit so to do, any instrument coming before him in the course of any proceeding other than a proceeding under Chapter XII or Chapter XXXVI of the Code of Criminal Procedure, 1898;

(b) in the case of a Judge of the High Court, the duty of examining and impounding any instrument under this section may be delegated to such officer as the Court appoints in this behalf.

(3) For the purposes of this section, in cases of doubt, the Government may determine, — (a) what offices shall be deemed to be public offices; and (b) who shall be deemed to be persons in charge of public offices.

2. Instruments not duly stamped inadmissible in evidence, etc.

No instrument chargeable with duty shall be admitted in evidence for any purpose by any person having by law or consent of parties' authority to receive evidence, or shall be acted upon, registered or authenticated by any such person or by any public officer, unless such instrument is duly stamped: Provided that,

(a) any such instrument not being an instrument chargeable with a duty not exceeding fifteen naye paise]1 only, or a mortgage of crop [Article 35 (a) of the Schedule] chargeable under clauses (a) and (b) of section 3 with a duty of twenty-five naye paise shall, subject to all just exceptions, be admitted in evidence on payment of the duty with which the same is chargeable, or, in the case of an instrument insufficiently stamped, or the amount required to make up such duty, together with a penalty of five rupees, or, when ten times the amount of the proper duty or deficient portion thereof exceeds five rupees, of a sum equal to ten times such duty or portion;

(b) where a contract or agreement of any kind is effected by correspondence consisting of two or more letters and any one of the letters bears the proper stamp, the contract or agreement shall be deemed to be duly stamped;

(c) nothing herein contained shall prevent the admission of any instrument in evidence in any proceeding in a Criminal Court, other than a proceeding under Chapter XII or Chapter XXXVI of the Code of Criminal Procedure, 1898;

(d) nothing herein contained shall prevent the admission of any instrument in any Court when such instrument has been executed by or on behalf of the Government, or where it bears the certificate of the Deputy Commissioner as provided by section 32 or any other provision of this Act and such certificate has not been revised in exercise of the powers conferred by the provisions of Chapter VI

3. Admission of instrument where not to be questioned

Where an instrument has been admitted in evidence such admission shall not, except as provided in section 58, be called in question at any stage of the same suit or proceeding on the ground that the instrument has not been duly stamped.312 1957: KAR. ACT 34] Stamp 528

4. Admission of improperly stamped instruments

The State Government may make rules providing that, where an instrument bears a stamp of sufficient amount but of improper description, it may, on payment of the duty with which the same is chargeable, be certified to be duly stamped, and any instrument so certified shall then be deemed to have been duly stamped as from the date of its execution.

5. Instruments impounded how dealt with

(1) When the person impounding an instrument under section 33 has by law or consent of parties authority to receive evidence and admits such instrument in evidence upon payment of a penalty as provided by section 34 or of duty as provided by section 36, he shall send to the Deputy Commissioner an authenticated copy of such instrument, together with a certificate in writing, stating the amount of duty and penalty levied in respect thereof, and shall send such amount to the Deputy Commissioner or to such person as he may appoint in this behalf.

(2) In every other case, the person so impounding an instrument shall send it in original to the Deputy Commissioner

6. Deputy Commissioner's power to refund penalty paid under sub-section (1) of section 37

(1) When a copy of an instrument is sent to the Deputy Commissioner under sub-section (1) of section 37, he may, if he thinks fit, refund any portion of the penalty in excess of five rupees which has been paid in respect of such instrument.

(2) When such instrument has been impounded only because it has been written in contravention of section 13 or section 14, the Deputy Commissioner may refund the whole penalty so paid.

7. Deputy Commissioner's power to stamp instruments impounded.

(1) When the Deputy Commissioner impounds any instrument under section 33, or receives any instrument sent to him under sub-section (2) of section 37, not being an instrument chargeable with a duty not exceeding fifteen naye paise only or a mortgage of crop [Article 35 (a) of the Schedule] chargeable under clause (a) or (b) of section 3 with a duty of twenty-five naye paise, he shall adopt the following procedure:

(a) if he is of opinion that such instrument is duly stamped, or is not chargeable with duty, he shall certify by endorsement thereon that it is duly stamped, or that it is not so chargeable, as the case may be;

(b) if he is of opinion that such instrument is chargeable with duty and is not duly stamped he shall require the payment of the proper duty or the amount required to make up the same, together with a penalty of five rupees; or if he thinks fit; an amount not exceeding ten times the amount of the proper duty or of the deficient portion thereof, whether such amount exceeds or falls short of five rupees: Provided that, when such instrument has been impounded only because it has been written in contravention of section 13 or section 14, the Deputy Commissioner may, if he thinks fit, remit the whole penalty prescribed by this section.

(2) Subject to any orders made under Chapter VI, every certificate under clause (a) of sub-section (1) shall, for the purposes of this Act be conclusive evidence of the matters stated therein.

(3) Where an instrument has been sent to the Deputy Commissioner under sub-section (2) of section 37, the Deputy Commissioner shall, when he has dealt with it as provided by this section, return it to the impounding officer.

8. Instruments unduly stamped by accident

If any instrument chargeable with duty and not duly stamped, not being an instrument chargeable with a duty not exceeding fifteen naye paise or a mortgage of crop [Article 35 (a) of the Schedule] chargeable under clause (a) or (b) of section 3 with a duty of twenty-five naye paise is produced by any person of his own motion before the Deputy Commissioner within one year from the date of its execution or first execution and such person brings to the notice of the Deputy Commissioner the fact that such instrument is not duly stamped and offers to pay to the Deputy Commissioner the amount of the proper duty, or the amount required to make up the same, and the Deputy Commissioner is satisfied that the omission to duly stamp such instrument has been occasioned by accident, mistake or urgent necessity, he may, instead of proceeding under sections 33 and 39, receive such amount and proceed as next hereinafter prescribed.

9. Endorsement of instruments on which duty has been paid under section 34, 39 or 40.-

(1) When the duty and penalty (if any) leviable in respect of any instrument have been paid under section 34, section 39 or section 40, the person admitting such instrument in evidence or the Deputy Commissioner, as the case may be, shall certify by endorsement thereon that the proper duty or, as the case may be, the proper duty and penalty (stating the amount of each) have been levied in respect thereof and the name and residence of the person paying them.

(2) Every instrument so endorsed shall thereupon be admissible in evidence, and may be registered and acted upon and authenticated as if it had been duly stamped, and shall be delivered on his application in this behalf to the person from whose possession it came into the hands of the officer impounding it, or as such person may direct: Provided that,

(a) no instrument which has been admitted in evidence upon payment of duty and a penalty under section 34, shall be so delivered before the expiration of one month from the date of such impounding, or if the Deputy Commissioner has certified that its further detention is necessary and has not cancelled such certificate;

(b) nothing in this section shall affect order XIII, rule 9 of the First Schedule to the Code of Civil Procedure, 1908.

26.4 Condonation of Delay (Delay Condone)

i. Brief Description:

If the document presented for registration exceeds 4 months from the date of execution, the delay for presentation needs to be condoned as per rule 52 of Registration Rules, 1965.

ii. Process Flow Diagram:




Figure: Process Flow Diagram for Condonation of Delay

iii. Functional Step by Step Process:

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (usual flow)
4. Property Schedule (usual flow)
5. Party Details (usual flow)

6. MV, Stamp Duty & Fee Calculation (usual flow)
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
 - a. After the DEO prints and uploads the document summary, the SR confirmation is required
12. Document Registration (usual flow)
 - a. But the SR keeps the document pending ('Document Kept Pending') during the document registration process where the reason for pending gets recorded in the Minute Book and the Endorsement is printed on the document
(Note: Once the DEO prints the Endorsement, the pending status should revert back to SR login)
13. Exceptional Cases (usual flow)
 - a. As the document is kept pending, it comes under exceptional case
 - b. The applicant has to request for Condonation of Delay (Delay Condoned)
 - c. The SR then shall refer such document to DR for Condonation of Delay (Delay Condoned)
 - d. The party shall make the Payment of Fine for Condonation of Delay
 - e. The DR will pass an Order (ie., the DR Order) on the Payment of Fine
(Note: In brief, the delay after the expiration of the time allowed for presentation:
 - i. does not exceed 1 week, a fine equal to the registration fee or appearance
 - ii. exceeds 1 week but does not exceed 1 calendar month, a fine equal to 2 times the registration fee
 - iii. exceeds 1 month but does not exceed 2 months, a fine equal to 5 times the registration fee
 - iv. exceeds 2 months but does not exceed 4 months, a fine equal to 10 times registration fee)
 (Note: The rate of fines for delay and the total leviable fee are mention in Registration Rules, 1965 (Rate of Fines for Delays, etc.). Refer next page for the same; also Delay Condonation Fee of Rs.200 must be added in additional to the above mentioned Delay Condonation Fine)
 - f. On receiving the Condonation Order from DR, and once the SR confirms the payment, the application gets retrieved from the Minute Book
 - g. The SR shall start the registration process by generating the registration number (ie., the SR registers the document)
 - h. From this step onwards, follow the usual process and get the document registered

iv. Process Abstract

Registration Act, 1908

1. Provision where delay in presentation is unavoidable,

(1) If, owing to urgent necessity or unavoidable accident, any document executed, or copy of a decree or order made, in India is not presented for registration till after the expiration of the time hereinbefore prescribed in that behalf, the Registrar, in cases where the delay in presentation does not exceed four months, may direct that, on payment of a fine not exceeding ten times the amount of the proper registration-fee, such document shall be accepted for registration.

(2) Any application for such direction may be lodged with a Sub-Registrar, who shall forthwith forward it to the Registrar to whom he is subordinate.

Registration Rules, 1965

2. Rate of fines for delays, etc.

(i) The fines for delays in presentation and appearance under Sections 25 and 34 shall be regulated as follows.

(a) When the delay does not exceed one week after the expiration of the time allowed for presentation, a fine equal to the registration fee or appearance has to be paid

(b) When the delay exceeds one week but does not exceed one calendar month after the expiration of the time allowed for presentation, a fine equal to twice the registration fee has to be paid

(c) When the delay exceeds one month but does not exceed two months after the expiration of the time allowed for presentation, a fine equal to five times the registration fee has to be paid

(d) When the delay exceeds two months but does not exceed four months after the expiration of the time allowed for presentation, a fine equal to ten times registration fee has to be paid

(ii) The fine shall be levied in addition to the proper registration fee.

(iii) The term "registration fee" as used in this rule means the fee actually leviable under any of the Articles I to IV of the Table of Fees and notes thereunder.

3. Calculation of rate of fine in case of documents in duplicate

When a document is presented for registration in duplicate or triplicate, the fine leviable under Rule 52 shall be calculated as for one document only.

4. Calculation of fine in certain cases

Whenever a fine for delay in appearance is levied on more occasions than one in respect of one and the same document, the amount of the fine leviable on the second

and subsequent occasions shall be the difference, if any, between the total amount leviable up to the second or subsequent occasion and the fine or fines previously levied in respect of such document.

5. Application for condoning delay in presentation, etc

(i) Whenever an application under Section 25 or Section 34 is lodged with a Sub-Registrar, he shall forward the same, whether he considers the reason for delay to be satisfactory or not, for the orders of the Registrar but as laid down in Rule 46(iii) there is no objection to his recording the admission of execution on such a document before forwarding the application to the Registrar.

(ii) When the Registrar condones the delay either under Section 25(1) or under the proviso to Section 34(1) and directs either the acceptance of the document for registration or its registration as the case may be, the Sub- Registrar, on receipt of orders to that effect from the Registrar shall make an endorsement on the document above the registration certificate in the following form and close the same with his signature and date

Acceptance for registration/admission to registration was directed by the Registrar of In his Order No. dated on payment of the fine of Rs. for a delay of Under Section 25/Section 34 of the Indian Registration Act, 1908.

Date:

Signature of the Sub-Registrar.

26.5 Power of Attorney Authentication/Attestation

i. Brief Description:

For the purpose of Section 32 of the Registration Act, the authenticated or attested power of autonomy is required. Hence it has to be authenticated or attested by SR as per the manner prescribed in the authentication certificate.

ii. Process Flow Diagram:




Figure: Process Flow Diagram for Power of Attorney Authentication

iii. Functional Step by Step Process:

1. User Registration (usual flow)
 - a. The executant fills the application online
2. Document Information (usual flow)
 - a. Select the 'Type of Service' as 'Document Registration'
3. Property Search
 - a. Select 'Miscellaneous' in 'Type of Documents'
 - b. Select 'Authentication of Power of Attorney'
4. Property Schedule (not needed)

5. Party Details

(Note: Here, capturing of the party details of the claimant is optional and not mandatory)

6. MV, Stamp Duty & Fee Calculation

(Note: Here, MV is redundant; only SD & FC are calculated)

7. Online Document Summary (usual flow)

8. SRO Conformation (usual flow)

9. Payment (usual flow)

10. Appointment Scheduler (usual flow)

11. Document Summary/Signature (usual flow)

12. Document Registration (usual flow)

(Note: 1. The executant appears before the SR (the authorised agent (claimant) may/mayn't appear); 2. During 'Document Registration' process, on the Endorsement, the 'Authentication/Attestation Certificate' in the prescribed proforma should appear)

Note: Format of AUTHENTICATION CERTIFICATE

"Authentication under clause (a) of sub-section (1) of Section 33. The power-of-attorney has been executed by..... of in my presence on the day of 20..... The said..... is personally known to me/the identity of the said has been proved by the testimony of Sri to my satisfaction, and whose signature are affixed to this endorsement.

Signature of the person identifying the principal.

Signature of (Sub) Registrar."

Seal.

Dated:

Note: Format of ATTESTATION CERTIFICATE

"Attestation under sub-section (2) of Section 33, This Power-of-Attorney has of been voluntarily executed by ----- of ----- I have satisfied myself in this behalf by personal examination of ----- by examination of the said ----- - on commission. The said-- ----- is personally known to me. The identity of the said ----- has been proved by the testimony of ----- to my satisfaction, and whose signature is affixed hereunto.

Seal.

Signature of the person identifying Dated. the principal.

Signature of the (Sub) Registrar."

13. Exceptional Cases (if required)

(Note: The Authentication/Attestation shall be recorded in the 'Attestation Register PoA')

iv. **Process Abstract**

Registration Act, 1908

Power-of-attorney recognizable for purposes of section 32

(1) For the purposes of section 32, the following powers-of-attorney shall alone be recognized, namely:

- (a) if the principal at the time of executing the power-of-attorney resides in any part of 1 [India] in which this Act is for the time being in force, a power-of-attorney executed before and authenticated by the Registrar or Sub-Registrar within whose district or sub-district the principal resides;
- (b) if the principal at the time aforesaid 2 [resides in any part of India in which this Act is not in force], a power-of-attorney executed before and authenticated by any Magistrate;
- (c) if the principal at the time aforesaid does not reside in 1 [India], a power-of-attorney executed before and authenticated by a Notary Public, or any Court, Judge, Magistrate, 3 [Indian] Consul or Vice-Consul, or representative 4 *** of the Central Government:

Provided that the following persons shall not be required to attend at any registration-office or Court for the purpose of executing any such power-of-attorney as is mentioned in clauses (a) and (b) of this section, namely:

- (i) persons who by reason of bodily infirmity are unable without risk or serious inconvenience so to attend;
- (ii) persons who are in jail under civil or criminal process; and
- (iii) persons exempt by law from personal appearance in court.

5 Explanation.—In this sub-section “India” means India, as defined in clause (28) of section 3 of the General Clauses Act, 1897 (10 of 1897).

(2) In the case of every such person the Registrar or Sub-Registrar or Magistrate, as the case may be, if satisfied that the power-of-attorney has been voluntarily executed by the person purporting to be the principal, may attest the same without requiring his personal attendance at the office or Court aforesaid.

(3) To obtain evidence as to the voluntary nature of the execution, the Registrar or Sub-Registrar or Magistrate may either himself go to the house of the person purporting to be the principal, or to the jail in which he is confined, and examine him, or issue a commission for his examination.

(4) Any power-of-attorney mentioned in this section may be proved by the production of it without further proof when it purports on the face of it to have been executed before and authenticated by the person or Court hereinbefore mentioned in that behalf.

Registration Rules, 1965 (Chapter XI)

1. Examination of a Power-of-Attorney

(i) When a power of attorney is executed before a Registering Officer he shall, after satisfying himself of the identity of the party and obtaining when necessary his left thumb impression against the signature, authenticate it in the following form

“Authentication under clause (a) of sub-section (1) of Section 33. The power-of-attorney has been executed by..... of in my presence on the day of20. The said..... is personally known to me/the identity of the said has been proved by the testimony of Sri to my satisfaction, and whose signature are affixed to this endorsement.

Signature of the person identifying the principal.

Signature of (Sub) Registrar.”

Seal.

Dated:

(ii) When a Power-of-Attorney which has not been executed before a Registering Officer is presented to him for attestation under the proviso to Section 33 the Registering Officer shall, if he attends himself at the private residence of the principal or if the principal appears in the office behind a purdah in the case of Ghosha ladies and is examined with the help of any witness, adopt the following form of attestation.

“Attestation under sub-section (2) of Section 33, This Power-of-Attorney has of been voluntarily executed by ----- of ----- I have satisfied myself in this behalf by personal examination of ----- by examination of the said ----- on commission. The said-- ----- is personally known to me. The identity of the said ----- has been proved by the testimony of ----- to my satisfaction, and whose signature is affixed hereunto.

Seal.

Signature of the person identifying Dated. the principal.

Signature of the (Sub) Registrar.”

(iii) In authenticating a Power-of-Attorney which occupies more than one sheet of paper, the seal and the signature of the Registering Officer shall be affixed to each sheet.

(iv) Every interlineation, blank, erasure or alteration in the body of a Power-of-Attorney which is authenticated and not registered shall, at the time of authentication, be detailed in a footnote added to the document below the endorsement of authentication and shall be signed by the Registering Officer even if the party himself has entered a similar note in the document, or there are no interlineations, blanks or erasures of alterations, in the body, that fact shall be noted. Interlineations, etc., in the authentication or attestation endorsements shall be initiated by the Registering Officer.

2. Procedure regarding Special or General Power-of-Attorney

(i) Special Powers-of-Attorney for registration purposes produced before a Registering Officer are to be retained and filed in original. If general powers be so produced, their copies with the proper Court fee stamp should be obtained and filed. Both of these should be filed separately.

(ii) On the original or copy thus filed, a note as follows should be endorsed showing for what purposes the Power-of-Attorney has been employed:

(a) Document serial No. of daily Register dated has been presented for registration by under authority of this Power-of-Attorney (or Power-of-Attorney of which this is a copy).

(b) Execution of document No. registered at page of Book No. Volume has been admitted by On behalf of under authority of this Power-of-Attorney (or the Power-of-Attorney of which this is a copy).

Seal.

Signed A.B.

Date.

Registrar or Sub-Registrar.

(iii) The above note should be recorded on the day on which the power is acted upon, pages, volume, etc., being filled up after registration of the deed.

3. Attestation of endorsement on a Power-of-Attorney

One copy of a general power will suffice for the registration of more than one document on the same day or for the registration of different documents presented at different times. The endorsement under Rule 64 should be written on each occasion the power is being acted upon. If there be no space on the copy for the endorsement a fresh paper may be attached thereto.

4. Form of endorsement

The endorsement prescribed in Rules 63 and 64 shall be written in English.

5. Registration of a Power-of-Attorney

A Power-of-Attorney may be brought to a registering Officer (i) for authentication or attestation, or (ii) for registration, or (iii) for both authentication or attestation and registration. In the first case, he shall merely make the entry prescribed for authentication or attestation; in the second case, he shall register the power in the same manner as any other document; and in the third case, he shall first authenticate or attest the power and then admit it to registration in the usual manner.

6. Manner of registration of a Power-of-Attorney

Although a Power-of-Attorney may be registered like any other instrument, it is not valid for registration purposes unless authenticated or attested as the case may be when a person who does not understand the distinction between authentication or attestation and registration, the registering officer should explain the difference to him and give such information as may be necessary.

7. Powers of registering authorities regarding Power of Attorney

District Registrars or Sub-Registrars cannot legally authenticate or attest Power-of-Attorney other than those required for registration purpose. A Registering Officer can authenticate or attest a General Power-of-Attorney only when it contains a specific authority to present a document or to admit execution of a document executed by the principal.

8. Abstracts of Power-of-Attorney

(i) An abstract in Form No. 12, Schedule A shall be retained to each Power-of-Attorney authenticated or attested by a Registering Officer as prescribed in Rule 25 whether such power is general or special registered or not registered. The notes of interlineations, blanks, erasures and alterations made by the Registering Officer on the original power shall be copied verbatim in the abstract.

(ii) (a) Each registration office shall maintain a register of all revocations of Power-of-Attorney registered in, or communicated to it, in the prescribed Form 12-A and also note the fact of such revocation in Form No.12 as aforesaid. (b) When notice of a revocation is given to a Registering Officer, he shall send an intimation of the same to such other offices as may be specified by the person on revoking the power.

26.6 Late Appearance (or Parties Appearing at Different Times)

i. Brief Description:

If the parties appear at different times, as per provisions of Sections 23, 24 and 25, the SR can admit execution or appearance.

ii. Process Flow Diagram:




Figure: Process Flow Diagram for Late Appearance

iii. Functional Step by Step Process:

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (usual flow)
4. Property Schedule (usual flow)
5. Party Details (usual flow)

6. MV, Stamp Duty & Fee Calculation (usual flow)
7. Online Document Summary (usual flow)
8. SRO Conformation (usual flow)
9. Payment (usual flow)
10. Appointment Scheduler (usual flow)
11. Document Summary/Signature (usual flow)
 - a. On the scheduled date and time, all but one (or more) appear before the SR and follow the usual process of getting the document registered. But as any one (or more) of them is absent, the document is kept pending till his/their appearance
12. Document Registration
 - a. But the SR keeps the document pending ('Document Kept Pending') during the document registration process where the reason for pending gets recorded in the Minute Book and the Endorsement is printed on the document
(Note: Once the DEO prints the Endorsement, the pending status should revert back to SR login)
13. Exceptional Cases

(Note: 1. This scenario takes place when there are several executants and they appear at different times (ie., not all of them will be present on the scheduled date and time). Hence, until all of them appear and until DEO captures the required information (ie., capture photo, thumb impression, signature of the parties and 2 witness, etc.), the document is kept pending by the SR;

2. As the concerned parties (except the one (or more) who goes for Late Appearance) have already made the required payment of fee, no further payment will be required at this stage)

 - a. As the document is kept pending, it comes under exceptional case
 - b. The person(s) who is appearing for Late Appearance, shall report to the SR at SRO; the time and date of his/their appearance will be recorded based on their appearance
(Note: the person(s) appearing for late attendance are supposed to visit the SRO within 8 months from the date of execution and get the document registered. If they appear within 4 months, no need to make any additional payment; if it exceeds 4 months, the Condonation of Delay applies and he/they have to make the payment accordingly (Refer 26.4 Condonation of Delay under Exceptional Cases); if it exceeds 8 months, then the registration gets terminated automatically)
 - c. As the required payment of fee is already being made (during initial scheduled date and time), the SR allows the application to get retrieved from the Minute Book
 - d. Based on the availability, the SR shall allocate the person(s) appearing for late attendance to the DEO of his choice
 - e. The DEO shall take the capture e-KYC (ie., Biometrics & Photograph) of the person(s) appearing for late appearance and the 2 witnesses (for person(s) appearing late) ie.,
 - i. Verify the party's identity

- ii. Takes the party's photo & thumb impression
 - iii. Get identified by 2 witnesses
 - iv. Takes the signature of the party/parties and 2 witnesses
(This comes under 7. Online Document Summary step)
- f. The DEO shall get the Document Summary Printed, Signed (gets the Signature of Presenter, DEO, FDA/SDA and SR) and Uploaded
(Note: The DEO shall capture and update the Document Summary of the Late Appearing Parties)
- g. The DEO shall send the same for SR Confirmation
- h. On Confirmation by the SR by clicking on 'Check and Register' button, the Registration Process begins and the Document Number gets generated (This comes under 11. Document Summary/Signature & 12. Document Registration)
- i. From this step onwards, follow the usual process and get the document registered

iv. Process Abstract

Registration Rules, 1965 (Chapter XII)

1. Enquiry before registration by registering officer.

(1) Subject to the provisions contained in this Part and in sections 41, 43, 45, 69, 75, 77, 88 and 89, no document shall be registered under this Act, unless the persons executing such document, or their representatives, assigns or agents authorised as aforesaid, appear before the registering officer within the time allowed for presentation under sections 23, 24, 25 and 26: Provided that, if owing to urgent necessity or unavoidable accident all such persons do not so appear, the Registrar, in cases where the delay in appearing does not exceed four months, may direct that on payment of a fine not exceeding ten times the amount of the proper registration fee, in addition to the fine, if any, payable under section 25, the document may be registered.

(2) Appearances under sub-section (1) may be simultaneous or at different times.

(3) The registering officer shall thereupon—

- (a) enquire whether or not such document was executed by the persons by whom it purports to have been executed;
- (b) satisfy himself as to the identity of the persons appearing before him and alleging that they have executed the document;
- (c) in the case of any person appearing as a representative, assign or agent, satisfy himself of the right of such person so to appear.

(4) Any application for a direction under the proviso to sub-section (1) may be lodged with a Sub-Registrar, who shall forthwith forward it to the Registrar to whom he is subordinate.

(5) Nothing in this section applies to copies of decrees or orders.

27 Abstract for 7 Special Articles

27.1 Partition

Nature of Document: **Partition**

Article: **39 Partition**

Sub Article: **39(a), 39(b), 39(c), 39(d)**

Book No.: **1**

27.1.1 Brief Description

Partition is the division of property among the co-parceners (Joint family members) or co-owners of the properties. i.e., dividing the properties into shares in to meets and bounds

Sub Articles of Partition based on nature of the property use:-

- (a) Partition of Non-Agriculture Land
- (b) Partition of Agriculture Land
- (c) Partition of Movable Property
- (d) Partition of any Property (In combination of a, b, and c)

27.1.2 User Input

In order to calculate the Stamp Duty user, need to provide the below information with respect to the shares (User Input):

1. No. of Claimants
2. No. of Executants
3. No. of Shares
4. Nature of the property (Agriculture/Non-Agriculture/Miscellaneous (Movable))
5. Property assigned to the shares
6. Enter the extent of the share
7. Enter the Linear measurement of the share East to West, North to South (Only for Non-Agriculture land)

8. Enter the boundaries of the share East, West, North, South (For both Agriculture and Non-Agriculture land)

9. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = Stamp Duty = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.1.3 Process Abstract

Process Abstract:

(a) Partition of Non-Agriculture Land

Fixed Stamp Duty of Rs.1000 per share for eAsthi, BBMP, Corporations, CMC, TMC and Urban development authorities Property and Fees Rs.1000 per share

Total Stamp Duty Payable = No. of share * 1000

Total Registration Fee Payable = No. of share * 1000

Fixed Stamp Duty of Rs.500 per share for RDPR (eSwathu) Property and Fees 500 per share

Total Stamp Duty Payable = No. of share * 500

Total Registration Fee Payable = No. of share * 500

(b) Partition of Agriculture Land

Fixed Stamp Duty of Rs.250 per share and Fees Rs.200 per share

Total Stamp Duty Payable = No. of share * 250

Total Registration Fee Payable = No. of share * 200

(c) Partition of Movable Property (Money)

Fixed Stamp Duty of Rs.250 per share Fees Rs.300 per share

Total Stamp Duty Payable = No. of share * 250

Total Registration Fee Payable = No. of share * 300

(d) Partition of any Property

If the shares of the partition are in combination of a, b, c the Total Stamp Duty and Fee payable per share is highest of the a, b, c

Example 1: Combination of the property “a” and “b” (“a”- non agriculture property, “b”- agriculture property)

For the properties “a” and “b”, highest stamp duty among “a” and “b” is “a”. Hence property “a” will be considered for calculation of stamp duty and fee

Total Stamp Duty Payable = No. of share * a

Total Stamp Duty Payable = No. of share * 1000 for eAsthi or

Total Stamp Duty Payable = No. of share * 500 for eSwathu

Total Registration Fee Payable = No. of share * a

Total Registration Fee Payable = No. of share * 1000 for eAsthi or

Total Registration Fee Payable = No. of share * 500 for eSwathu

Example 2: Combination of the property “a” and “c” (“a”- non agriculture property, “c”- movable property)

For the properties “a” and “c”, highest stamp duty among “a” and “c” is “a”. Hence property “a” will be considered for calculation of stamp duty and fee

Total Stamp Duty Payable = No. of share * a

Total Stamp Duty Payable = No. of share * 1000 for eAsthi or

Total Stamp Duty Payable = No. of share * 500 for eSwathu

Total Registration Fee Payable = No. of share * a

Total Registration Fee Payable = No. of share * 1000 for eAsthi or

Total Registration Fee Payable = No. of share * 500 for eSwathu

Example 3: Combination of the property “b” and “c” (“b”- agriculture property, “c”- movable property)

For the properties “b” and “c”, highest stamp duty and registration fee among “b” and “c” is “c”. Hence property “c” will be considered for calculation of stamp duty and fee

Total Stamp Duty Payable = No. of share * c

Total Stamp Duty Payable = No. of share * 250

Total Registration Fee Payable = No. of share * c

Total Registration Fee Payable = No. of share * 300

Example 4: Combination of the property “a”, “b” and “c” (“a” – non agriculture property, “b”- agriculture property, “c”- movable property)

For the properties “a”, “b” and “c”, highest stamp duty among “a”, “b” and “c” is “a”. Hence property “a” will be considered for calculation of stamp duty and fee

Total Stamp Duty Payable = No. of share * a

Total Stamp Duty Payable = No. of share * 1000

Total Registration Fee Payable = No. of share * a

Total Registration Fee Payable = No. of share * 1000

Example 5: Any number of properties in a share, the stamp duty payable for a share is highest of “a”, “b” or “c” (“a” – non agriculture property, “b”- agriculture property, “c”- movable property)

If the shareholder is having 10 properties in a single share, then he needs to pay the stamp duty which is higher among the 10. For example, Person A is having 10 properties in a single share, then he needs to pay single stamp duty of the highest stamp duty of the property.

27.2 Joint Development Agreement

Nature of Document: **JDA**

Article: **5 Agreement**

Sub Article: **5(f) When given for a Developer or Promoter for Development**

Book No.: **1**

27.2.1 Brief Description

Agreement is an arrangement agreed upon by the parties to develop a property into multi-unit building (Apartment) or Layout and they share among themselves the developed property. JDA will be registered in Book 1.

27.2.2 User Input

In order to calculate the Stamp Duty user, need to provide the below information with respect to the property (User Input):

1. No. of Claimants
2. No. of Executants
3. Sharing Ratio of the Landowner
4. Sharing Ratio of the Builder/Developer
5. Nature of the property (Agriculture/Non-Agriculture)
6. Money advanced if any for Landowner
7. Money advanced if any for Developer
8. Enter the extent of the land
9. Enter the Linear measurement of the land East to West, North to South (Only for Non-Agriculture land)
- 10 Enter the boundaries of the land East, West, North, South (For both Agriculture and Non-Agriculture land)
11. Proposed building super built up area
12. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = Stamp Duty = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.2.3 Process Abstract

Process Abstract:

Example:

If 2 Person one as owner of land and other as a Developer agrees to develop an apartment, there will be sharing of super built up area. The sharing ratio say about 30:70% i.e. to say landowner may get 30% of super builtup area of building along with number of car parking and any money if agreed to be given and in return and the developer gets 70% of super builtup area and land. The stamp duty is calculated based on total land value of which 70% of land value taken as developer share and total value of building has to be calculated and of which 30% value of building goes to the share of landowner + Value of number of car parking + money if any given has to be taken as another share. The stamp duty and registration fee are calculated on the higher value of the shares.

Brief Description:

1 acre of agriculture land which is to be converted is the contribution of the landowner
Super-builtup area of the building about 10,000 sqm with 100 car-parking is the contribution of the Builder/Developer

Sharing Ratio = 30:70

30% of the super-builtup area + 30% car parking for Landowner + if money given any

70% of the super-builtup area + 70% car parking for Builder

MV of the Land = 1 cr per acre = 1,00,00,000

MV of the Super-builtup area = 10,000 (rate per sqm) * 10,000 (sqm of super-builtup area) = 10,00,00,000

Car Parking Rate = 2 lakh per car parking

Total Cost of Car parking = 2 lakh * 100 = 2,00,00,000

Share of the Landowner = 30% of super-builtup area + 30% of car parking area + if money given any i.e., cost of landowner share = 30% of 10,00,00,000 + 30% of car parking = 3,00,00,000 + 60,00,000 + 0 = 3,60,00,000 say it is share 1

Share of the Builder = 70% of land i.e., cost of the land which goes to the builder = 70% of 1,00,00,000 = 70,00,000 say it is share 2

Now, stamp duty is calculated based on the highest share i.e., 3,60,00,000 (higher value between 3,60,00,000 and 70,000)

Hence Stamp Duty = $3,60,00,000 \times 2\% = 7,20,000$

Registration Fee = $3,60,00,000 \times 1\% = 3,60,000$

27.3 Power of Autonomy (PoA) with JDA (Joint Development Agreement)

Nature of Document: **PoA with JDA**

Article: **41 PoA**

Sub Article: **41(ea) When given to a Developer or Promoter for Development of Property**

Book No.: **4**

27.3.1 Brief Description

(Article 41(ea)): PoA will given to the developer/builder by the landowner along with JDA when an agreement is made for development of multi-unit building (Apartment) or Layout and they share among themselves the developed property. To enable the smooth functioning of development the landowner gives a power of attorney to the developer with JDA and this will be registered in Book 4.

27.3.2 User Input

In order to calculate the Stamp Duty user, need to provide the below information with respect to the property (User Input):

1. No. of Claimants
2. No. of Executants
3. Sharing Ratio of the Landowner
4. Sharing Ratio of the Builder/Developer
5. Nature of the property (Agriculture/Non-Agriculture)
6. Money advanced if any for Landowner
7. Money advanced if any for Developer
8. Enter the extent of the land
9. Enter the Linear measurement of the land East to West, North to South (Only for Non-Agriculture land)
10. Enter the boundaries of the land East, West, North, South (For both Agriculture and Non-Agriculture land)

11. Proposed building super built-up area

12. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = Stamp Duty = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.3.3 Process Abstract

Process Abstract:

If the full stamp duty is paid on the agreement, then denoting is given to the PoA. The maximum duty payable will be 200

Example:

If the stamp duty is not paid on the JDA, then the following process will be followed.

2 Person one as owner of land and other as a Developer agrees to develop an apartment, there will be sharing of super built up area. The sharing ratio say about 30:70% i.e. to say landowner may get 30% of super builtup area of building along with number of car parking and any money if agreed to be given and in return and the developer gets 70% of super builtup area and land. The stamp duty is calculated based on total land value of which 70% of land value taken as developer share and total value of building has to be calculated and of which 30% value of building goes to the share of landowner + Value of number of car parking + money if any given has to be taken as another share. The stamp duty and registration fee are calculated on the higher value of the shares.

Brief Description:

1 acre of agriculture land which is to be converted is the contribution of the landowner

Super-builtup area of the building about 10,000 sqm with 100 car-parking is the contribution of the Builder/Developer

Sharing Ratio = 30:70

30% of the super-builtup area + 30% car parking for Landowner + if money given any

70% of the super-builtup area + 70% car parking for Builder

MV of the Land = 1 cr per acre = 1,00,00,000

MV of the Super-builtup area = 10,000 (rate per sqm) * 10,000 (sqm of super-builtup area) = 10,00,00,000

Car Parking Rate = 2 lakh per car parking

Total Cost of Car parking = 2 lakh * 100 = 2,00,00,000

Share of the Landowner = 30% of super-builtup area + 30% of car parking area + if money given any i.e., cost of landowner share = 30% of 10,00,00,000 + 30% of car parking = 3,00,00,000 + 60,00,000 + 0 = 3,60,00,000 say it is share 1

Share of the Builder = 70% of land i.e., cost of the land which goes to the builder = 70% of 1,00,00,000 = 70,00,000 say it is share 2

Now, stamp duty is calculated based on the highest share i.e., 3,60,00,000 (higher value between 3,60,00,000 and 70,00,000)

Hence Stamp Duty = 3,60,00,000 * 2% = 7,20,000

Registration Fee = 3,60,00,000 * 1% = 3,60,000

27.4 EXCHANGE

Nature of Document: **Exchange**

Article: **26**

Sub Article: **nil**

Book No.: **1**

27.4.1 Brief Description

Exchange means Exchange of Properties between two parties of their respective properties. It comes under Article 26 of Stamp Act, 1957.

For the purpose of calculating the stamp duty, the market value of both the properties of both the parties have to be calculated which are under exchange. The Property which is having higher value in the exchange is considered for the payment and calculation of stamp duty. The other property which is having lower value is exempted.

27.4.2 User Input

In order to calculate the Stamp Duty, the user needs to provide the below information with respect to the property:-

1. No. of Claimants
2. No. of Executants
3. No. of Properties
4. Nature of the property (Agriculture/Non-Agriculture)
5. Property assigned to the parties
6. Enter the extent of the properties
7. Enter the Linear measurement of the share East to West, North to South (Only for Non-Agriculture land)
8. Enter the boundaries of the share East, West, North, South (For both Agriculture and Non-Agriculture land)
9. Market Values of the properties
10. Consideration if any

11. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.4.3 Process Abstract

Process Abstract

Example 1: Say, we have 2 parties - Party 1 and Party 2

Party 1 has got the property C & Party 2 has got the property D

Now, in the Exchange, the property D goes to party 1 and the property C goes to party 2

Supposed to say, property C is 1 acre and property D is 1 acre 10 guntas

Value of property C is Rs.1 crore and Value of property D is Rs.90 lakh

So, the stamp duty is calculated on property C ie., Rs.1 crore (because of higher value between them) and property D is exempted

Though the Article is 26, the rate of stamp duty is as per Conveyance ie., 5%. But as per the property situation ie., Urban Property 2% and Rural property 3% and Cess 10% on the stamp duty.

Hence, Govt stamp duty payable = [Market Value + Amount Paid (if any)]

$$= 1 \text{ crore} * 5\% = \text{Rs.}500000$$

Surcharge = 3% on the stamp duty = Rs.15000

Cess = 10% On stamp duty = Rs.50000

Total stamp duty paid = Rs.500000 + Rs.15000 + Rs.50000 = Rs.565000

Registration Fee = 1% on the [Market Value + Amount Paid (if any)] = Rs.100000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs.565000 + Rs.100000 = Rs.665000

Example 2: Say, we have 2 parties - Party 1 and Party 2

Party 1 has got the property C and has received Rs. 25 lakh from party 2

Party 2 has got the property D and has received Rs. 5 lakh from party 1

Now, in the Exchange, the property D goes to party 1 and the property C goes to party 2

Supposed to say, property C is 1 acre and property D is 1 acre 10 guntas

Value of property C is Rs.1 crore and Value of property D is Rs.90 lakh

Total amount to to be considered for Each Party:

Party 1 = Rs.1 crore + 25 lakh = Rs. 1.25 crore

Party 2 = Rs.90 lakh + 5 lakh = Rs. 0.95 crore

So, the stamp duty is calculated on property C ie., Rs.1.25 crore (because of higher value between them) and property D is exempted

Though the Article is 26, the rate of stamp duty is as per Conveyance ie., 5%. But as per the property situation ie., Urban Property 2% and Rural property 3% and Cess 10% on the stamp duty.

Hence, Govt stamp duty payable = [Market Value + Amount Paid (if any)]

$$= 1.25 \text{ crore} * 5\% = \text{Rs.}6,25,000$$

Surcharge = 3% on the stamp duty = Rs.18,750

Cess = 10% On stamp duty = Rs.62,500

Total stamp duty paid = Rs. 6,25,000 + Rs. 18,750+ Rs. 62,500 = Rs.7,06,250

Registration Fee = 1% on the [Market Value + Amount Paid (if any)] = Rs.1,25,000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs. 7,06,250 + Rs.1,25,000 = Rs.8,31,250

27.5 SETTLEMENT

Nature of Document: **Settlement**

Article: **48**

Sub Article: **48(A)(i), 48(A)(ii)(i), 48(A)(ii)(ii), 48(A)(ii)(iii), 48(A)(ii)(iv)**

Book No.: **1**

27.5.1 Brief Description

Settlement means any non-testamentary disposition in writing, of movable or immovable property made:

1. In consideration of marriage
2. For the purpose of distributing property of the settler among his family or those for whom he deserves to provide, or for the purpose of providing for some dependent on him, or
3. For any religious or charitable purpose; and includes an agreement in writing to make such a disposition, and where any such disposition hasn't been made in writing, any instrument recording whether by way of declaration, of trust or otherwise, the terms of any such disposition

It comes under Article 48 of Stamp Act, 1957.

27.5.2 User Input

In order to calculate the Stamp Duty, the user needs to provide the below information with respect to the property:-

1. No. of Claimants
2. Executant (settler)
3. No. of Properties
4. Nature of the property (Agriculture/Non-Agriculture)
5. Property assigned to the parties
6. Enter the Extent of the properties

7. Enter the Linear measurement of the property East to West, North to South (Only for Non-Agriculture land)
8. Enter the boundaries of the property East, West, North, South (For both Agriculture and Non-Agriculture land)
9. Market Values of the properties
10. Movable (in kind or cash)
11. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.5.3 Process Abstract

Process Abstract

Sub-article 48 (A) (i) - Settlement outside the family members = **Conveyance (Sale) only**

Sub-article 48 (A) (ii) - Settlement within the family members

Example 1:

Sub-article 48 (A) (ii) - Settlement within the family members

Property Jurisdiction among the family members:-

Area	Stamp duty (per share)
48(A)(ii)(i) BBMP	Rs.5000
48(A)(ii)(ii) CMC/TMC	Rs.3000
48(A)(ii)(iii) Other than 1 & 2	Rs.1000
48(A)(ii)(iv) Combination of 1, 2 & 3	Highest among them

Example 1:

Person	1	2	3	1 & 2	1 & 3	2 & 3	1, 2 & 3
A = Settler	BBMP	CMC/TMC	Other than BBMP/CMC/TMC	Combination of 1, 2 & 3 Consider HIGHER value among them			
S1 = son	5000	3000	1000	5000	5000	3000	5000
S2 = son	5000	3000	1000	5000	5000	3000	5000
D1 = dependent	5000	3000	1000	5000	5000	3000	5000
Stamp Duty payable =	15000	9000	3000	15000	15000	9000	15000
Registration Fee =	1000 (fixed)	1000 (fixed)	1000 (fixed)	1000 (fixed)	1000 (fixed)	1000 (fixed)	1000 (fixed)
Total fee to be paid =	16000	10000	4000	16000	16000	10000	16000

--	--	--	--	--	--	--	--

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 48 (A) (i) - Settlement not within the family members = Conveyance (Article 20) ie., the process followed as in case of article conveyance has to be adopted here also

27.6 APARTMENT

Nature of Document: **Apartment**

Article: **20**

Sub Article: **20(2), 20(2A)(i), 20(2A)(ii), 20(3)**

Book No.: **1**

27.6.1 Brief Description

Apartment means (a) “Premises” means and includes undivided interest in the land, building and proportionate share in the common areas;

(b) “Unit” includes flat, apartment, tenement, block or any other unit by whatever name called, constructed or under construction in accordance with the sanctioned plan by the authority competent to sanction a building plan under any law for the time being in force;

It comes under Article 20 of Stamp Act, 1957.

27.6.2 User Input

In order to calculate the Stamp Duty, the user needs to provide the below information with respect to the property:-

1. No. of Claimants
2. No. of Executants
3. Property details
4. Enter the Extent of the properties:-
5. Schedule A - Total land area used for the construction of apartment
6. Schedule B - Undivided share to be given to the unit of apartment purchaser
7. Schedule C - Super-builtup area of the unit of apartment
8. Schedule D - Amenities
9. No. of Car parking
10. Market Value of the super-builtup area
11. Consideration

27.6.3 Process Abstract

Process Abstract

For determination of market value and stamp duty for apartment, the total area of the land used for construction as shown in the schedule A has to be entered. The undivided share of land is to be demarcated as in schedule B. Super-builtup area as in schedule C is considered for calculating the market value with the rate prescribed, along with the no. of car parking area

Article 20 (2) – where it is related to instrument of conveyance executed by a promoter, a land owner or a developer by whatever name called pertaining to the premises of flat or apartment or transfer of share by or in favour of co-operative society or company pertaining to premises or unit and the market value of the property which is the subject matter of conveyance – rate of stamp duty is 5%

Article 20 (2A) (i) - where an instrument of Conveyance relating to the first sale of Flat/Apartment - where the market value of which is Rs.2000000 or less than Rs.2000000 - rate of stamp duty is 2%

Article 20 (2A) (ii) - where an instrument of Conveyance relating to the first sale of Flat/Apartment - where the market value of which is above Rs.2500000 but up to and inclusive of Rs.3500000 - rate of stamp duty is 3%

Article 20 (3) – Sale by BDA/KHB of Flat Flat/Apartment - rate of stamp duty is 5%

Example:

Schedule A

1 acre of total land area = $1089 \times 40 = 43560$ sqft = 4047 sqm

Schedule B

Say about 10000 sqm of super-builtup area

Undivided share per sqm = $4047/10000 = 0.4047 \times 100$ (fixed no. for % calculation) = 40.47 sqm

Schedule C

Super-builtup area = 100 sqm (per unit of apartment)

2 car parking

Article 20 (2A) (i)

Calculation

Market value = super-builtup area * guideline value

$$= 100 \text{ sqm} * 10000$$

$$= \text{Rs.}1000000$$

Amenities = special features as per annexure values

Cost of car parking = 2 * Rs.200000 = Rs.400000

Total Market value = Rs.1000000 + Rs.400000 = Rs.1400000

Govt stamp duty payable = Total Market value * Rate of stamp duty

$$= \text{Rs.}1400000 * 2\%$$

$$= \text{Rs.}28000$$

Surcharge = 3% of Rs.28000 = Rs.840

Cess = 10% of Rs.28000 = Rs.2800

Total stamp duty payable = Rs.28000 + Rs.840 + Rs.2800 = Rs.31640

Registration Fees = 1% on the Market value or Consideration (whichever is higher) = Rs.14000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs.31640 + Rs.14000 = Rs.45640

27.7 LEASE

Nature of Document: **Lease**

Article: **30**

Sub Article: **30(1)(i), 30(1)(ii), 30(1)(iii), 30(1)(iv), 30(1)(v), 30(1)(vi), 30(1)Proviso(i), 30(1)Proviso(ii), 30(1)Proviso(iii), 30(3)(a)(1), 30(3)(a)(2), 30(3)(a)(3), 30(3)(a)(4), 30(3)(b)(1), 30(3)(b)(2), 30(3)(b)(3), 30(3)(b)(4)**

Registration Article: **??**

Book No.: **1**

27.7.1 Brief Description

Lease of Immovable Property including an under-lease or sub-lease and any agreement to let or sub-let whereby such lease the rent is fixed or fine or premium or money advanced or security deposit is paid or delivered. It comes under Article 30 of Stamp Act, 1957.

Note: Here, Consideration Amount = annual average rent + fine or premium or money advanced or security deposit.

27.7.2 User Input

In order to calculate the Stamp Duty, the user needs to provide the below information with respect to the property:-

1. What is the Period of lease?
2. What is the Rent fixed?
3. What is the rate of increase of rent per year?
4. What is the premium or Money advanced?
5. What is the Tax payable?
6. No. of Executants
7. No. of Claimants
8. Extent of the property
9. Enter the Linear measurement of the property East to West, North to South (Only for Non-Agriculture land)

10. Enter the boundaries of the property East, West, North, South (For both Agriculture and Non-Agriculture land)

11. No. of Duplicate copies for calculation of Duplicate stamp duty and fee. i.e., Stamp Duty = No. of Duplicate copies*Fixed Stamp Duty (Rs.500) and Registration Fee = Stamp Duty = No. of Duplicate copies*Fixed Registration Fee (Rs.200)

27.7.3 Process Abstract

Sub-article 30 (1) (i) - where the lease purports to be for a term not exceeding one year in case of residential property

Rate of Stamp Duty = 0.50%

Cap Amount = Max Rs.500

Government Duty = (Annual average rent + fine or premium or money advanced or security deposit) * Rate (Max Rs.500)

Total Stamp Duty = Government Duty

Total Registration Fees = 0.5% with Maximum of Rs.200

Method of Calculation of stamp duty = Total lease amount of the period + any advance amount *0.5% of rate of stamp duty with a maximum of Rs.500

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Example 1: Period of lease 1 year monthly rent of Rs.10000 = Rs.120000

Total stamp duty = (Rs.120000+Rs.10000(advance))*0.5% = 650, but limited to Maximum of Rs.500 = Rs.500 only

Sub-article 30 (1) (ii) - where the lease purports to be for a term not exceeding one year in case of commercial or industrial property

Rate of Stamp Duty = 0.50%

Government Duty = (Annual average rent + fine or premium or money advanced or security deposit) * Rate

Total Stamp Duty = Government Duty

Total Registration Fees = 0.5% with Minimum of Rs.200

Method of Calculation of stamp duty = Total lease amount of the period + any advance amount * 0.5% of the rate of stamp duty

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Example 1: Period of lease 1 year, monthly rent rate of Rs.10000 = Rs.120000

Total stamp duty will be (Rs.120000 + Rs.10000(advance))*0.5% = Rs.650

Example 2: Period of lease 1 year, monthly rent rate of Rs.500 = Rs.6000

Total stamp duty will be Rs.6000*0.5% = Rs.30, but a minimum of Rs.200 = Rs.200 only

Sub-article 30 (1) (iii) - where the lease purports to be for a term exceeding one year and not exceeding ten years

Rate of Stamp Duty = 1%

Government Duty = (Annual average rent + fine or premium or money advanced or security deposit) * Rate

Total Stamp Duty = Government Duty

Total Registration Fees = 0.5% with Minimum of Rs.200

Method of Calculation of stamp duty = (Annual average rent + advance) * rate of stamp duty

Annual average	=	1st year rent at the rate of 10000	=	120000.00
		2nd year 5% increase	=	126000.00
		3rd year 5% increase	=	132300.00
		4th year 5% increase	=	138915.00
		5th year 5% increase	=	145860.75
		6th year 5% increase	=	153153.78
		7th year 5% increase	=	160811.46
		8th year 5% increase	=	168852.03
		9th year 5% increase	=	177294.63
		10th year 5% increase	=	186159.36
		Total	=	1509347.01

Annual average rent = Total/10 = Rs.1509347.01/10 = Rs.150934.70 (should be rounded off to next thousand) = Rs.151000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Example 1: $(151000 + 10000) * 1\% = \text{Rs.1610}$ is the stamp duty

Sub-article 30 (1) (iv) - where the lease purports to be for a term exceeding ten years and not exceeding twenty years

Rate of Stamp Duty of Market value = 2%

Government Duty = (Annual average rent + fine or premium or money advanced or security deposit) * Rate

Total Stamp Duty = Government Duty

Total Registration Fees = 0.5%

Method of Calculation of stamp duty = Same as above explained (sub-article 30(1)(iii)) for 20 years' average + advance * 2% rate

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (1) (v) where the lease purports to be for a term exceeding twenty years and not exceeding thirty years

Rate of Stamp Duty = 3%

Government Duty = (Annual average rent + fine or premium or money advanced or security deposit) * Rate

Total Stamp Duty = Government Duty

Total Registration Fees = 0.5%

Method of Calculation of stamp duty = Same as above explained (sub-article 30(1)(iii)) for 30 years' average + advance * 3% rate

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

30 (1) (vi) where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term

Rate of Stamp Duty = 5%

Government Duty = ((Annual average rent + fine or premium or money advanced or security deposit) or (market value of the property)) whichever is higher * Rate

Surcharge Value = If urban Property, then 2% on Stamp Duty and

If Rural Property 3% on Stamp Duty

Cess Value = 10% on Stamp Duty

Total Stamp Duty = Government Duty + Surcharge Value + Cess Value

Total Registration Fees = 1% * ((Annual average rent + fine or premium or money advanced or security deposit) or (market value of the property)) whichever is higher

Method of Calculation of stamp duty = Same as above explained (sub-article 30(1)(iii)) for the period or Market value of the property, whichever is higher * rate of stamp duty

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Proviso of Article 30

Within Family Members

Sub-article 30 (1) Proviso (i) - If the property is situated within the limits of BBMP or City Corporation

Fixed Stamp Duty = Rs.5000

Government Duty = Rs.5000

Total Stamp Duty = Rs.5000

Total Registration Fees = Rs.1000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs.5000 + Rs.1000 = Rs.6000

Sub-article 30 (1) Proviso (ii) - If the property is situated within the limits of City or Town Municipal Council or Town Panchayat area

Fixed Stamp Duty = Rs.3000

Government Duty = Rs.3000

Total Stamp Duty = Rs.3000

Total Registration Fees = Rs.1000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs.3000 + Rs.1000 = Rs.4000

Sub-article 30 (1) Proviso (iii) - If the property is situated within the limits other than the limits specified in items 30 (1) (i) and (ii)

Fixed Stamp Duty = Rs.1000

Government Duty = Rs.1000

Total Stamp Duty = Rs.1000

Total Registration Fees = Rs.1000

Total Fee to be paid = Total Stamp Duty + Total Registration Fee = Rs.1000 + Rs.1000 = Rs.2000

Mining Lease through AUCTION

Sub-article 30 (3) (a) (1) where the lease purports to be for a term exceeding one year and not exceeding ten years

Rate of Stamp Duty = One rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = $1\% \times \text{Royalty} + \text{Estimate Annual Average Production}$

Registration Fees = $1\% \times \text{Royalty} + \text{Estimate Annual Average Production}$

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (a) (2) where the lease purports to be for a term exceeding ten years and not exceeding twenty years

Rate of Stamp Duty = Two rupees for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan.

Stamp Duty = $2\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Registration Fees = $1\% \times \text{Royalty} + \text{Estimate Annual Average Production}$

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (a) (3) where the lease purports to be for a term exceeding twenty years and not exceeding thirty years

Rate of Stamp Duty = Three rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = 3% * Royalty + Estimated Annual Average Production

Registration Fees = 1% * Royalty + Estimate Annual Average Production

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (a) (4) where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term

Rate of Stamp Duty = Five rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = 5% * Royalty + Estimated Annual Average Production

Surcharge Value = 3% * Stamp Duty

Cess Value = 10% * Stamp Duty

Total Stamp Duty = Government Stamp Duty + Surcharge Value + Cess Value

Total Registration Fees = 1% * Royalty + Estimate Annual Average Production

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Mining Lease through GRANT

Sub-article 30 (3) (b) (1) where the lease purports to be for a term exceeding one year and not exceeding ten years

Rate of Stamp Duty = One rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = 1% * Royalty + Estimate Annual Average Production

Registration Fees = 1% * Royalty + Estimate Annual Average Production

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (b) (2) where the lease purports to be for a term exceeding ten years and not exceeding twenty years

Rate of Stamp Duty = Two rupees for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment

based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = $2\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Registration Fees = $1\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (b) (3) where the lease purports to be for a term exceeding twenty years and not exceeding thirty years

Rate of Stamp Duty = Three rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = $3\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Registration Fees = $1\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

Sub-article 30 (3) (b) (4) where the lease purports to be for a term exceeding thirty years or in perpetuity or does not purport to be for any definite term

Rate of Stamp Duty = Five rupee for every one hundred rupees or part thereof on the total amount or value of; the average annual royalty and average annual payment based on the final price offer obtained in the auction calculated on the estimated average annual production as per the approved mining plan

Stamp Duty = $5\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Surcharge Value = $3\% \times \text{Stamp Duty}$

Cess Value = $10\% \times \text{Stamp Duty}$

Total Stamp Duty = Government Stamp Duty + Surcharge Value + Cess Value

Total Registration Fees = $1\% \times \text{Royalty} + \text{Estimated Annual Average Production}$

Total Fee to be paid = Total Stamp Duty + Total Registration Fee

28 ENDORSEMENT

“Endorsement” and “endorsed” include and apply to an entry in writing by a registering officer on a rider or covering slip to any document tendered for registration under this Act.

28.1 Contents in the Endorsement

Endorsement will have the following details:

1. 10A Certificate - under Karnataka Stamp Act 1957 Section 10A

10A Certificate will have the details of amount of Stamp Duty paid by the Party along with the Challan Number and Date of Remittance. The Certificate will be signed by the proper officer/Deputy Commissioner of Stamps/Sub Registrar

.....ನೀ ಭುಟದ ದಸ್ತಾವೇಜು ಸಂಖ್ಯೆ: 105
20-21

ಉಪ ಸೋಲರಿದರ್ಶಾಧಿಕಾರಿ
ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಮೊಂಡಲೆ ಹಾಗೂ ಮುದ್ರಾಂಕ ಇಲಾಖೆ
Department of Stamps and Registration
ಪ್ರಮಾಣ ಪತ್ರ

1957 ರ ಕರ್ನಾಟಕ ಮುದ್ರಾಂಕ ಕಾಯ್ದೆಯ ಕೆಲಸ 10 ಎ ಅಡಿಯಲ್ಲಿಯ ಪ್ರಮಾಣ ಪತ್ರ

ಶ್ರೀ K. Nuryanagowda S/o H. Kempalah . ಇವರು 5000.00 ರೂಪಾಯಿಗಳನ್ನು ನಿಗದಿತ ಮುದ್ರಾಂಕ ಶುಲ್ಕವಾಗಿ ಪಾವತಿಸಿರುವುದನ್ನು ದೃಢೀಕರಿಸಲಾಗಿದೆ

ಪ್ರಕಾರ	ಮೊತ್ತ (ರೂ.)	ಹಣದ ಪಾವತಿಯ ವಿವರ
ನಗದು ರೂಪ	5000.00	Paid in Cash.
ಒಟ್ಟು:	5000.00	

ಸ್ಥಳ : ಗಾಂಧಿಪುರ
ದಿನಾಂಕ : 22/05/2020

ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಮುದ್ರಾಂಕ ಮತ್ತು ದಸ್ತಾವೇಜು ಇಲಾಖೆಯ ಉಪ ಸೋಲರಿದರ್ಶಾಧಿಕಾರಿ
ಗಾಂಧಿಪುರ, ಬೆಂಗಳೂರು-9

2. Exemption

If **Exemption** is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded

3. Denoting

If **Denoting** is there, Denoting certificate is recorded

4. Presentation Endorsement

Presentation Endorsement will have the Sub Registrar Office name where the Document is presented, Date and Time and Name of the Presenter with the following Fees

- Registration Fee
- Duplicate Fee
- Scanning Fee
- Mutation Fee in case of Agriculture Land
- Miscellaneous

Print Date & Time : 22-05-2020 05:30:16 PM

ದಸ್ತಾವೇಜು ಸಂಖ್ಯೆ : 105


ಗಾಂಧಿವಗರ ದಲ್ಲಿರುವ ಉಪನೋಂದಣಾಧಿಕಾರಿ ಗಾಂಧಿವಗರ ರವರ ಕಛೇರಿಯಲ್ಲಿ ದಿನಾಂಕ 22-05-2020 ರಂದು 05:00:53 PM ಗಂಟೆಗೆ ಈ ಕೆಳಗೆ ವಿವರಿಸಿದ ಶುಲ್ಕದೊಂದಿಗೆ

ಕ್ರಮ ಸಂಖ್ಯೆ	ವಿವರ	ರೂ. ಪೈ
1	ನೋಂದಣಿ ಶುಲ್ಕ	1000.00
2	ಸ್ಕಾನಿಂಗ್ ಫೀ	630.00
3	ವಿವರಣಾ ಶುಲ್ಕ	200.00
	ಒಟ್ಟು :	1830.00


ಶ್ರೀ K. Narayanagowda S/o H. Kempaiah ಇವರಿಂದ ಹಾಜರಾದ ಮಾಹಿತಿಗಾರರು

5. Party Information Endorsement

- Party Information Endorsement will have the Presenter details such as Presenter Name, Photograph and Signature followed by Sub Registrar Signature.
- Execution Admission by the Claiming Parties which includes Claimant Name, Photograph and Signature followed by Sub Registrar Signature.
- Execution Admission by the Executing Parties which includes Executor/s Name, Photograph and Signature followed by Sub Registrar Signature
- If appearance of the Party as per section 88 exemption is given and the particulars of the exemption letter will be recorded

ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು	ಪೋಟೋ	ಹೆಬ್ಬಟುನ ಗುರುತು	ಸಹಿ
	ಶ್ರೀ K. Narayanagowda S/o H. Kempalaih			

ಬರೆದುಕೊಟ್ಟಿದ್ದಾಗಿ(ಮೇಲೆ ಪೂರ್ಣ/ಭಾಗಶಃ ಪ್ರತಿಫಲ ರೂ..... (ರೂಪಾಯಿ)..... ಮುಖ್ಯದ್ದಾಗಿ)
ಒಪ್ಪಿರುತ್ತಾರೆ



ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು	ಪೋಟೋ	ಹೆಬ್ಬಟುನ ಗುರುತು	ಸಹಿ
	K Narayanagowda S/o H. Kempalaih (ಬರೆದುಕೊಟ್ಟವರು)			
2	Mamatha W/o Late H.K. Ramachandra Gowda (ಬರೆದುಕೊಟ್ಟವರು)			Mamathagowda M.V.

6. Identifying Witness (Identifiers) Endorsement

Identifying Witness Endorsement will have the Name, Address and Signature of the two Witness followed by Sub Registrar Signature.

ಗುರುತಿಸುವವರು

...6...ನೇ ಪ್ರಯತ್ನ ಪಡ್ತಾಣೆಂದು ಸಂಖ್ಯೆ: 105
20-21

ಕ್ರಮ ಸಂಖ್ಯೆ	ಹೆಸರು ಮತ್ತು ವಿಳಾಸ	ಸಹಿ
1	Murali, No. 8, Attur Layout, Yelchanka Town, Bangalore.	
2	Ashwath Kumar, K No. 24 6th B Cross, 3rd Main Road, Domlur Layout, Bangalore.	


ಹಿರಿಯ ಉಪನಿರ್ದೇಶಕರಾದ
ಕಾಂತ್ಯಾಚಾರ್, ಬೆಂಗಳೂರು-9

7. Payment before the Sub Registrar

If the Consideration (of amount) of the transaction is paid in front of Sub Registrar either by cash or cheque/DD, the same is to be recorded and signatures of the parties paying and receiving are taken; then the Sub Registrar will sign it

“The Payment is made before me in Cash (in Rupee) or
Cheque/DD Number dated by Sri./Smt.
..... to Sri./Smt.”


Signature of the Parties

Signature of the Sub Registrar

(Note: There shall be fields to capture the payment of consideration before Sub Registrar as shown above)

8. Registration Certificate as per Section 60 of Registration Act, 1908

Registration Certificate will have the Book Number, Document Number which consists of Office name in Trilateral Letters i.e., Abbreviation of the Sub Registrar's Office Name, Book Number and Serial Number of the Document of the year and Date followed by Sub Registrar Signature



Designed and Developed by C-DAC, ACTS, Pune

(Note: The Endorsement is usually printed on the back of the Deed Document; if in case the space isn't available on the back of the deed document, then a separate sheet/s is used for printing the endorsement)

28.2 Endorsement for PENDING DOCUMENTS

Sub Registrar may keep the documents pending due to various reasons which is to be recorded in the Minute Book 6

- i. Pending for determination of undervaluation, referred to District Registrar under section 45A of Karnataka Stamp Act, 1957
- ii. Pending for short levy of Stamp Duty, impounded under section 33 of Karnataka Stamp Act, 1957
- iii. Pending for condonation of delay, under section 25 of Registration Act, 1908, document exceeding 4 months from the date of last execution read with Rule 52 of Registration Rule, 1965
- iv. Pending for appearance of the parties under section 34 of Registration Act, 1908.
- v. Pending for private attendance under section 31 of Registration Act, 1908

28.2.1 Pending for determination of undervaluation, referred to District Registrar under section 45A of Karnataka Stamp Act 1957

The market value or consideration set forth in the document is less than estimated guidance value published under section 45B of Karnataka Stamp Act, 1957, then the party has got option to pay stamp duty as per the guidance value determined by the SR or if he disagrees, the document may be kept pending from registration and referred to the DR for determination of valuation. At this stage, the document is suspended from the further process of registration until the DR Order and payment is made by the party.

For the document kept pending,

“The document is referred u/s 45A of KS Act, 1957 for determination of undervaluation”

should be printed on the Endorsement of the document.

Signature of the Sub Registrar

Also, having kept the document pending, there should be a **record in the Minute Book 6** in the following manner.

Assessed By	Market Valuation in Rs.	Stamp Duty in Rs.	Registration Fee in Rs.	Total in Rs.
Sub Registrar				
Citizen				
Difference				

“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

(Note: 1. The fields in the above table should be auto-fetched when the SR keeps the document kept pending u/s 45A and there should be provision to record remarks by the SR;

2. There should be a provision for payment of stamp duty and registration fee through add challan;

3. There should be provision to record the remarks by the SR;

4. Instead of Certificate u/s 60 of Registration Act, 1908, the pending remarks should be recorded as mentioned above (ie., the remarks made by SR)

After payment of stamp duty (on the Orders of the District Registrar), the document suspended from the further process of registration has to be retrieved from the pending status to continue registration. After continuing the registration, the document gets registered. Having registered the document, there shall be recording in the minute book regarding the valuation assessed by the DR and stamp duty fee paid by the party on the orders of the DR in the following table

Assessed By	Market Valuation in Rs.	Stamp Duty in Rs.	Registration Fee in Rs.	Total in Rs.
Sub Registrar				
Citizen				
District Registrar				

Final Registration Number of the document – should be auto-fetched


Signature of the Sub Registrar

There should be remarks entered in the endorsement recording the stamp duty and registration fee paid by the party on the orders of the DR. The final certificate of registration u/s 60 of RS Act, 1908 shall be printed on the endorsement of the document

Use Case No.1:

The Format of the ENDORSEMENT for Under-valuation in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is referred u/s 45A of KS Act, 1957 for determination of under-valuation"**

Signature of the Sub Registrar

(Note: The above sentence/s should appear in step 8)

Use Case No.2:

The Format of the MINUTE for Under-valuation to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING)

“The document is referred u/s 45A of KS Act, 1957 for determination of under-valuation”

Assessed By	Market Valuation in Rs.	Stamp Duty in Rs.	Registration Fee in Rs.	Total in Rs.
Sub Registrar				
Citizen				
Difference				

“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

Use Case No.3:

The Format of the ENDORSEMENT for the Document Registration after Under-valuation process gets COMPLETED and the registration process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is referred u/s 45A of KS Act, 1957 for determination of under-valuation"


Signature of the Sub Registrar

9. "The document is ordered for registration on payment of stamp duty Rupee..... and registration fee Rupee..... as per the orders of the DR"

Signature of the Sub Registrar

(Note: if possible, please auto-fetch the stamp duty and registration fee from the add challan)

10. Registration Certificate as per Section 60 of Registration Act, 1908



(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9 and 10 should be printed on the endorsement)

Use Case No.4:

The Format of the MINUTE for Under-valuation to be recorded in the MINUTE BOOK 6 after the registration process gets COMPLETED

(Note: After DR Order, the below table show be recorded in the minute book as a contra-entry for the document kept pending earlier)

Assessed By	Market Valuation in Rs.	Stamp Duty in Rs.	Registration Fee in Rs.	Total in Rs.
Sub Registrar				
Citizen				
District Registrar				

"..... (Remarks: (if any, to be made by the SR here))"

Signature of the Sub Registrar

28.2.2 Pending for short levy of Stamp Duty, impounded under section 33 of Karnataka Stamp Act, 1957

The document presented for registration is under-stamped ie., in which the stamp duty isn't paid as per the articles of stamp. Under the provision of section 33 of Karnataka Stamp Act, 1957, the document is impounded. The document is kept pending from registration and impounded for payment of difference of stamp duty and penalty. At this stage, the document is suspended from the further process of registration until the payment of stamp duty and penalty under the Orders of the DR.

For the document kept pending,

"The document is impounded u/s 33 of KS Act, 1957"

should be printed on the Endorsement of the document.

Signature of the Sub Registrar

Also, having kept the document pending, there should be a **record in the Minute Book 6** in the following manner.

Stamp Duty payable in Rs.	
Stamp Duty paid in Rs.	
Difference in Rs.	

"..... (Remarks: (if any, to be made by the SR here))"

Signature of the Sub Registrar

(Note: 1. Instead of Certificate u/s 60 of Registration Act, 1908, the pending remarks should be recorded as mentioned above (ie., the remarks made by SR;

2. There should be a provision for payment of difference of stamp duty and penalty through add challan;

3. There should be provision to record the remarks by the SR)

After payment of stamp duty (on the Orders of the District Registrar), the document suspended from the further process of registration has to be retrieved from the pending status (impound) to continue registration. After continuing the registration, the document gets registered. Having registered the document, there shall be recording in the minute book regarding the stamp duty and penalty paid by the party on the orders of the DR in the following table

Difference of Stamp Duty paid in Rs.	
Penalty paid in Rs.	
Total in Rs.	

"..... (Remarks: (if any, to be made by the SR here))"

Final Registration Number of the document – should be auto-fetched


Signature of the Sub Registrar

There should be remarks entered in the endorsement recording the stamp duty and penalty paid by the party on the orders of the DR. The final certificate of registration u/s 60 of RS Act, 1908 shall be printed on the endorsement of the document

Use Case No.1:

The Format of the ENDORSEMENT for Impound in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is impounded u/s 33 of KS Act, 1957"**

Signature of the Sub Registrar

(Note: The above sentence/s should appear in step 8)

Use Case No.2:

**The Format of the MINUTE for Impound to be recorded in the MINUTE BOOK 6 (ie.,
in case of DOCUMENT KEPT PENDING)**

“The document is impounded u/s 33 of KS Act, 1957”

Stamp Duty payable in Rs.	
Stamp Duty paid in Rs.	
Difference in Rs.	

“ (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

Use Case No.3:

The Format of the ENDORSEMENT for the Document Registration after Impound process gets COMPLETED and the registration process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is impounded u/s 33 of KS Act, 1957"


Signature of the Sub Registrar

9. "The document is ordered for registration on payment of stamp duty Rupee..... and registration fee Rupee..... as per the orders of the DR"

Signature of the Sub Registrar

(Note: if possible, please auto-fetch the stamp duty and penalty from the add challan)

10. Registration Certificate as per Section 60 of Registration Act, 1908



Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9 & 10 should be printed on the endorsement)

Use Case No.4:

The Format of the MINUTE for Impound to be recorded in the MINUTE BOOK 6 after the registration process gets COMPLETED

(Note: After DR Order, the below table show be recorded in the minute book as a contra-entry for the document kept pending earlier)

Difference of Stamp Duty paid in Rs.	
Penalty paid in Rs.	
Total in Rs.	

“..... (Remarks: (if any, to be made by the SR here))”

Final Registration Number of the document – should be auto-fetched

Signature of the Sub Registrar

28.2.3 Pending for Condonation of Delay under section 25 of Registration Act, 1908, document exceeding 4 months from the date of last execution read with Rule 52 of Karnataka Registration Rules, 1965

If the document presented for registration exceeds 4 months from the date of execution, the document may be kept pending from registration and referred to the DR for condonation of delay in presentation. At this stage, the document is suspended from the further process of registration until the Orders of the DR for condonation of delay and payment of fine is made by the party.

For the document kept pending,

“The document is referred u/s 25 of KS Act, 1957 for condonation of delay” should be printed on the Endorsement of the document.

Signature of the Sub Registrar

Also, having kept the document pending, there should be a **record in the Minute Book 6** in the following manner.

After 4 months from the Date of Execution, any one of the following mentioned below (based on the duration of delay) should appear in the minute book 6:

- i. Not exceeding one week – fine equal to registration fee (1 time)
- ii. Exceeding one week not exceeding one month – fine equal to 2 times the registration fees
- iii. Exceeding one month not exceeding two months – fine equal to 5 times the registration fees
- iv. Exceeding two months not exceeding four months – fine equal to 10 times the registration fees

“..... (Remarks: (if any, to be made by the SR here))”

Final Registration Number of the document – should be auto-fetched

Signature of the Sub Registrar

(Note: 1. Only one among the 4 options mentioned above should appear in the minute book 6;

2. There should be a provision for entering the amount of fine to be levied depending upon the duration of delay;

3. There should be a provision for payment of fine through add challan;

4. There should be a provision to record fine paid (to be auto-fetched) from the challan

5. There should be provision to record the remarks by the SR;

6. Instead of Certificate u/s 60 of Registration Act, 1908, the pending remarks should be recorded as mentioned above (ie., the remarks made by SR)


After payment of fine and on the Orders of the DR, the document suspended from the further process of registration has to be retrieved from the pending status to continue registration.

There should be remarks entered in the endorsement recording the fine paid by the party on the orders of the DR. The final certificate of registration u/s 60 of RS Act, 1908 shall be printed on the endorsement of the document

Use Case No.1:

The Format of the ENDORSEMENT for Condonation of Delay in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is referred u/s 25 of KS Act, 1957 for condonation of delay"**

Signature of the Sub Registrar

(Note: the above sentence/s should appear in step 8)

Use Case No.2:

The Format of the MINUTE for Condonation of Delay to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING)

“The document is referred under section 25 of KS Act, 1957 for condonation of delay”

Signature of the Sub Registrar

Any one of the following mentioned below (based on the duration of delay) should appear in the minute book 6:

- i. Not exceeding one week – fine equal to 1 time registration fee of Rupee.....
- ii. Exceeding one week not exceeding one month – fine equal to 2 times the registration fee of Rupee.....
- iii. Exceeding one month not exceeding two months – fine equal to 5 times the registration fee of Rupee.....
- iv. Exceeding two months not exceeding four months – fine equal to 10 times the registration fee of Rupee.....

“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

Use Case No.3:

The Format of the ENDORSEMENT for the Document Registration after Condonation of Delay process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is referred u/s 25 of KS Act, 1957 for condonation of delay"


Signature of the Sub Registrar

9. "The document is ordered for registration on payment of fine Rupee..... as per the orders of the DR"

Signature of the Sub Registrar

(Note: if possible, please auto-fetch the fine from the add challan)

10. Registration Certificate as per Section 60 of Registration Act, 1908



Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9 & 10 should be printed on the endorsement)

Use Case No.4:

The Format of the MINUTE for Condonation of Delay to be recorded in the MINUTE BOOK 6 after the registration process gets COMPLETED

(Note: On receipt of the DR Order, the below said certificate will be recorded)

“On the Orders of the DR, the fine of Rupee..... has been paid through challan number dated is paid there on. Hence document order for registration”

Final Registration Number of the document – should be auto-fetched

Signature of the Sub Registrar

28.2.4 Pending for Appearance of the Parties under section 34 of Registration Act, 1908


28.2.4.1 SCENARIO 1

Party appearing at different time for admission of execution as per the provision u/s 34 of Registration Act, 1908 **if not exceeding 4 months** as per the provisions of section 23, 24, 25 and 26 of Registration Act, 1908, then the document is kept pending for appearance of the party, Endorsement is generated and gets recorded in the Minute Book.

Use Case No.1: (SCENARIO 1)

The Format of the ENDORSEMENT for Appearance of Parties in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"**

Signature of the Sub Registrar

(Note: the above sentence/s should appear in step 8)

Use Case No.2: (SCENARIO 1)

The Format of the MINUTE for Appearance of Parties to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING)

"The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"

"The party has not appeared for admission of execution, on application by the presenter that the party will appear at a later date for admission of execution, hence kept pending"

" (Remarks: (if any, to be made by the SR here))"

Signature of the Sub Registrar

Use Case No.3: (SCENARIO 1)

The Format of the ENDORSEMENT for the Document Registration after Appearance of the Parties after the registration process gets COMPLETED


1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"

Signature of the Sub Registrar

9. "Admission of execution on appearance of the party on the date" (is recorded along with the 2 identifying witnesses and their addresses)

Signature of the Sub Registrar

10. Registration Certificate as per Section 60 of Registration Act, 1908



Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9 & 10 should be printed on the endorsement)

Use Case No.4: (SCENARIO 1)

The Format of the MINUTE for Appearance of Parties to be recorded in the MINUTE BOOK 6 after the registration process gets COMPLETED

"The party has appeared for admission of execution, on appearance of the party, the photo and biometry have been recorded along with 2 witnesses for identification, hence the document ordered for registration as document number (to be auto-fetched)"

" (Remarks: (if any, to be made by the SR here))"

Signature of the Sub Registrar


28.2.4.2 SCENARIO 2

If the party appears not exceeding 4 months **after expiry of 4 months from the date of execution of the document** and appearing within the next 4 months, the DR may direct on payment of fine (as per provisions of condonation of delay) not exceeding 10 times the registration fee for admission of the execution of the document.

Use Case No.1: (SCENARIO 2)

The Format of the ENDORSEMENT for Appearance of Parties in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"**

Signature of the Sub Registrar

Use Case No.2: (SCENARIO 2)

The Format of the MINUTE for Appearance of Parties to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING – 1st time)

“The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties”

“The party has not appeared for admission of execution, on application by the presenter that the party will appear at a later date for admission of execution, hence kept pending”


“ (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

Use Case No.3: (SCENARIO 2)

The Format of the ENDORSEMENT for Appearance of Parties in case of DOCUMENT KEPT PENDING on Appearance of the Parties

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"**

Signature of the Sub Registrar

10. **"Admission of execution on appearance of the party on the date"** (is recorded along with the 2 identifying witnesses and their addresses)

Signature of the Sub Registrar

11. **"Further pending continues for condonation of delay"** (the document is sent to DR for condonation of delay)

Signature of the Sub Registrar

Use Case No.4: (SCENARIO 2)

The Format of the MINUTE for Appearance of Parties to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING – 2nd time further pending)

“Admission of execution on appearance of the party on the date” (is recorded along with the 2 identifying witnesses and their addresses)

Signature of the Sub Registrar

“Further pending continues for condonation of delay” (the document is sent to DR for condonation of delay)


“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

Use Case No.5: (SCENARIO 2)

The Format of the ENDORSEMENT for Appearance of Parties in case of DOCUMENT KEPT PENDING after Orders of Condonation of Delay by DR and after the registration process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending u/s 34 of Registration Act, 1908 for appearance of parties"**
Signature of the Sub Registrar
10. **"Admission of execution on appearance of the party on the date"** (is recorded along with the 2 identifying witnesses and their addresses)
Signature of the Sub Registrar
11. **"Further pending continues for condonation of delay"** (the document is sent to DR for condonation of delay)
Signature of the Sub Registrar
12. **"On the orders of condonation of delay by DR, order number dated , the fine of Rupee..... is paid. Hence the document is ordered for registration"**

13. Registration Certificate as per Section 60 of Registration Act, 1908

1 ನೇ ಪುಸ್ತಕದ ದಸ್ತಾವೇಜು
ನಂಬರ GAN-1-00105-2020-21 ಲಾಗಿ
ಸಿ.ಡಿ. ನಂಬರ GAND681 ನೇ ರ್ತದ್ದಿ
ದಿನಾಂಕ 22-05-2020 ರಂದು ನೋಂದಾಯಿಸಲಾಗಿದೆ

ಉಪನೋಂದಣಾಧಿಕಾರಿ (ಗಾಂಧಿನಗರ, ಬೆಂಗಳೂರು)
ಗಾಂಧಿನಗರ, ಬೆಂಗಳೂರು-9

Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 11 are already printed on the endorsement; hence after the registration is completed, ONLY the step 12 and 13 should be printed on the endorsement)

Use Case No.6: (SCENARIO 2)

The Format of the MINUTE for Appearance of Parties to be recorded in the MINUTE BOOK 6 after Order for Condonation of Delay by DR and payment of fine, and after the registration process gets COMPLETED

**“On the orders of condonation of delay by DR, order number
dated , the fine of Rupee..... is paid. Hence the
document is ordered for registration”**

“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

28.2.5 Pending for Private Attendance under section 31 of Registration Act, 1908

In the exigencies, ill-health or detained in custody, if requested for visiting to private residence on payment of private residence fee and conveyance, the SR visits the private residence of the party or detention place and registers the document.

28.2.5.1 SCENARIO 1


Where the document is Presented and kept pending for private residence attendance

On the presentation of the document, the parties to the document appear before the SR for admission of execution, under special circumstances any of the claimant/s or executant/s due to exigencies, ill-health or detained in custody, on request for private residence attendance, the document will be kept pending to admit the execution at their private residence. So on payment of private residence attendance fee and conveyance, the SR shall visit the place where the party resides. The SR admits the execution recording the address, boundaries of the place, time and takes the photo and biometrics of the party and the witnesses, also records the deposition of the party. The SR after arriving back to the SR office, orders for registration.

Use Case No.1: (SCENARIO 1)

The Format of the ENDORSEMENT for Private Attendance in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending under section 31 of Registration Act, 1908 for private attendance"**

Signature of the Sub Registrar

(Note: The above sentence/s should appear in step 8)

Use Case No.2: (SCENARIO 1)

The Format of the MINUTE for Private Attendance to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING)

“The document is kept pending under section 31 of Registration Act, 1908 for private attendance”

“ (Remarks: (if any, to be made by the SR here)) ”

Signature of the Sub Registrar

Use Case No.3: (SCENARIO 1)

The Format of the ENDORSEMENT for the Document Registration after Private Attendance after the registration process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is kept pending under section 31 of Registration Act, 1908 for private attendance"

Signature of the Sub Registrar

(Note: On the given Document, the above Endorsement (ie., Steps from 1 to 8) have already been printed. After Private Attendance process, the below Endorsement (ie., Steps 9, 10 & 11) ONLY have to be printed on THIS SAME DOCUMENT)

9. Payment of fee for private residence attendance is recorded in the following manner "Payment of private residence fee Challan Number..... dated Amount Rupee..... "

10. Place & Address
Time of visit by SR
Biometry & Photo

Signature of the party
Signature of Sub Registrar

Deposition of the party

Signature of the party
Signature of Sub Registrar

2 Identifying Witnesses – Name, Address & Signature

Signature of Sub Registrar

11. Registration Certificate as per Section 60 of Registration Act, 1908


 1 ನೇ ಪುಸ್ತಕದ ರಾಷ್ಟ್ರವೇಷು
 ನಂಬರ GAN-1-00105-2020-21 ನಾಗಿ
 ಸಿ.ಡಿ. ನಂಬರ GAND681 ನೇ ರೂರಲ್ಲಿ
 ದಿನಾಂಕ 22-05-2020 ರಂದು ಸೇರಿಸಿದಾಯಿತು

 22/5/2020
 ಉಪನಿರ್ದೇಶಕರು, ಗಾಂಧೀನಗರ (ಉಪನಿರ್ದೇಶಕರು)
 ಗಾಂಧೀನಗರ, ಬೆಂಗಳೂರು-9



Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9, 10 and 11 should be printed on the endorsement)

Use Case No.4: (SCENARIO 1)

The Format of the MINUTE for Private Attendance to be recorded in the MINUTE BOOK 6, after attending private residence of the party and after the registration process gets COMPLETED

“Visited the private residence of the party, the party has given admission of execution voluntarily and he is being identified by 2 witnesses. Hence being satisfied having admitted, the document is ordered for registration”

“..... (Remarks: (if any, to be made by the SR here))”

Signature of the Sub Registrar

28.2.5.2 SCENARIO 2


Where the document is Presented and kept pending for private residence attendance; but party residing Outside the Jurisdiction of the SR

On the presentation of the document, the parties to the document appear before the SR for admission of execution, under special circumstances any of the claimant/s or executant/s due to exigencies, ill-health or detained in custody, on request for private residence attendance, the document will be kept pending to admit the execution at their private residence. So on payment of private residence attendance fee and conveyance, if the party is residing outside the jurisdiction of the SR, then the commission for private residence attendance has to be sent to the jurisdictional SR under whose jurisdiction the party resides. The SR of the concerned jurisdiction shall visit the place where the party resides. The SR of the concerned jurisdiction admits the execution recording the address, boundaries of the place, time and takes the photo and biometrics of the party and the witnesses, also records the deposition of the party. The SR of the concerned jurisdiction after arriving back to the SR office will send the commission report to the originating SR for further process registration. After receiving the commission report, the document will be ordered for registration.

Use Case No.1: (SCENARIO 2)

The Format of the ENDORSEMENT for Private Attendance in case of DOCUMENT KEPT PENDING

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. **"The document is kept pending under section 31 of Registration Act, 1908 for private attendance"**

Signature of the Sub Registrar

(Note: The above sentence/s should appear in step 8)

Use Case No.2: (SCENARIO 2)

The Format of the MINUTE for Private Attendance to be recorded in the MINUTE BOOK 6 (ie., in case of DOCUMENT KEPT PENDING)

“The document is kept pending under section 31 of Registration Act, 1908 for private attendance”

“The party is residing outside the jurisdiction of this office, the commission is given to the SR”

Signature of the Sub Registrar

Use Case No.3: (SCENARIO 2)

The Proforma of the COMMISSION sent by the originating SR to the concerned (outside) jurisdiction SR

**To,
The District Registrar/Sub-Registrar.**

Whereas the accompanying power-of-attorney/document, dated the
And purporting to have been executed by A.B. son of residing in your
sub-district has been presented for attestation/registration in this office
and whereas it is necessary that it should be ascertained whether it has been
voluntarily executed by the person by whom it purports to have been examined in
connection.

Executed take ----- you are hereby requested to ----- the
examination of Therewith order upon the interrogatories hereunto attached
and to return this commission with the examination of the said to this
office on or before the day of

Given under my hand and seal this day of 20

**Signature of Registering Officer.
Seal.**

(Note: The above commission should be printed (on a separate sheet) for sending to
the concerned jurisdictional SR)

Use Case No.4: (SCENARIO 2)

The Proforma of the COMMISSION sent by the concerned (outside) jurisdiction SR to the originating SR

(ii) When the commission is for the examination of an executant, and has been executed, the Commissioner shall return the document to the office from which it was issued endorsed as follows.

“Having attended the at residence of A.B., son of C.D., at I have this day examined the said A.B., who has been identified to my satisfaction by E. F., son of G. H., etc., resident of And the said A.B., admitted (or denied) the voluntary execution of this power-ofattorney/the execution of this document.”

Left thumb impression of executant when necessary. Full signature of the executant.

Signature of witnesses.

Commissioner.

(iii) Where receipt of consideration is acknowledged before the Commissioner, he shall add the following clause to this endorsement:

“and acknowledged receipt of Rs. (or goods to be specified) being consideration (in whole or in part).”

(iv) Where consideration is paid in the presence of the Commissioner, he shall add the following to the endorsement.----

“I also certify that Rs. (or goods to be specified) were paid (or delivered) in my presence to the said A.B. by.”

The signature of the payee and payer shall also be taken below this endorsement, as provided in the specimen form in Schedule B.

(v) On receiving the Commissioner’s report, the Registering Officer shall, if satisfied as to the execution of the document, make the following endorsement below the report.-----

“From the foregoing report I am satisfied that this Power-ofAttorney/document has been voluntarily executed by the said A.B.”

Date:

Signature of Registering Officer.

(Note: The above commission should be printed (on a separate sheet) for sending to the originating SR)

Use Case No.5: (SCENARIO 2)


The Format of the ENDORSEMENT for the Document Registration after Private Attendance after the registration process gets COMPLETED

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "The document is kept pending under section 31 of Registration Act, 1908 for private attendance"

Signature of the Sub Registrar

(Note: On the given Document, the above Endorsement (ie., Steps from 1 to 8) have already been printed. After Private Attendance process, the below Endorsement (ie., Steps 9 & 10) ONLY have to be printed on THIS SAME DOCUMENT)

9. **The Commission Report sent by the concerned (other) jurisdictional SR to the originating SR (which is printed on a separate sheet) is attached (pinned) to this document endorsement**
10. **Registration Certificate as per Section 60 of Registration Act, 1908**



Designed and Developed by C-DAC, ACTS, Pune

(Note: The step from 1 to 8 are already printed on the endorsement; hence after the registration is completed, ONLY the steps 9 and 10 should be printed on the endorsement)

Use Case No.6: (SCENARIO 2)

The Format of the MINUTE for Private Attendance to be recorded in the MINUTE BOOK 6, after attending private residence of the party and after the registration process gets COMPLETED

“After having received the commission report from the concerned (other) jurisdictional SR, the document is ordered for registration”

“ (Remarks: (if any, to be made by the SR here)) ”

Signature of the Sub Registrar

28.2.5.3 SCENARIO 3

Where the application is Sent for private attendance (ie., document is YET to be presented)

The applicant submits the application for private residence attendance with the medical certificate by uploading the application and medical certificate and on payment of stamp duty (if any), registration fee and private attendance fee. The SR gives an appointment and visits the place of residence of the party, records the time of visit, date, place, address, gets the document presented by the party, admits the execution of the document identified by 2 witnesses, records the deposition of the party, then comes back to the SRO office and orders for registration if satisfied all the conditions of the Registration Act.

Use Case No.1: (SCENARIO 3)

The Format of the ENDORSEMENT for Private Attendance in this case

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual) (if any, in case of cancellation of will)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. The SR captures the following details as mentioned below on the endorsement

Place & Address

Time of visit by SR

Biometry & Photo

Signature of the party

Signature of Sub Registrar

Deposition of the party


Signature of the party

Signature of Sub Registrar

2 Identifying Witnesses – Name, Address & Signature

Signature of Sub Registrar

5. Registration Certificate as per Section 60 of Registration Act, 1908



Designed and Developed by C-DAC, ACTS, Pune

Use Case No.2: (SCENARIO 3)

The Format of the MINUTE for Private Residence Attendance as recorded in the MINUTE BOOK 6 before leaving the SRO for private residence attendance

The SR records in the Minute Book to proceed for private residence attendance as follows:

The time of leaving the office

The place of visit

Applicant's name

Signature of Sub Registrar

Use Case No.3: (SCENARIO 3)

The Format of the MINUTE for Private Residence Attendance as recorded in the MINUTE BOOK 6 after returning from the attending private residence

The SR records in the Minute Book to proceed for private residence attendance as follows:

The time of reaching the office

The place visited

Whether the registration was accepted (yes/no)

If yes, then mention Document Number

Intimation sent to DR

Signature of Sub Registrar

28.3 Endorsement for DOCUMENT REFUSED for REGISTRATION

The document can be refused for registration if the document is not complying with any one of the following reasons:

- i. Refused document registration for denial of execution u/s 35 of Registration Act 1908
- ii. Refused document registration for property not belonging to jurisdiction of the Sub Registrar u/s 28 of Registration Act 1908
- iii. Refused document registration for document presented by a wrong person u/s 32 of Registration Act 1908
- iv. Refused document registration for exceeding 8 months from the date of execution u/s 25 of Registration Act 1908
- v. Refused document registration for not fulfilling the conditions of section 21 of Registration Act 1908

For the document being refused for registration,

“Registration Refused”

should be printed on the Endorsement of the document.

Signature of the Sub Registrar

Also, having the document being refused for registration, there should be a **record in the Minute Book 2** in any one of the following reasons:

- i. Refused document registration for denial of execution u/s 35 of Registration Act 1908
- ii. Refused document registration for property not belonging to jurisdiction of the Sub Registrar u/s 28 of Registration Act 1908
- iii. Refused document registration for document presented by a wrong person u/s 32 of Registration Act 1908
- iv. Refused document registration for exceeding 8 months from the date of execution u/s 25 of Registration Act 1908
- v. Refused document registration for not fulfilling the conditions of section 21 of Registration Act 1908

“..... (Remarks: (if any, to be made by the SR here))”


Signature of the Sub Registrar

(Note: 1. Instead of Certificate u/s 60 of Registration Act, 1908, the refusal remarks should be recorded as mentioned above (ie., the remarks made by SR); 2. RADIO BUTTONS should be given for the SR to choose one option (only) from among the five options)

Use Case No.1:

The Format of the ENDORSEMENT in case of DOCUMENT REFUSED for Registration

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908 (**SHOULDN'T BE SHOWN ie., REMOVE entire step 8**)



(Note: The above said Certificate u/s 60 of Registration Act, 1908 SHOULDN'T APPEAR on the Endorsement (ie., **Remove step 8**); Instead in its place, the Remarks as shown in the step 9 should appear)

9. "Refused Registration"

Signature of the Sub Registrar

(Note: The above sentence/s should appear in step 8)

Use Case No.2:

The Format of the MINUTE to be recorded in **the MINUTE BOOK 2**

“Registration Refused”

(Note: One (among the 5 reasons) of the below said reasons as chosen by the SR gets recorded)

“Refused document registration for denial of execution u/s 35 of Registration Act 1908”

Signature of the Sub Registrar

OR

“Refused document registration for property not belonging to jurisdiction of the Sub Registrar u/s 28 of Registration Act 1908”

Signature of the Sub Registrar

OR

“Refused document registration for document presented by a wrong person u/s 32 of Registration Act 1908”

Signature of the Sub Registrar

OR

“Refused document registration for exceeding 8 months from the date of execution u/s 25 of Registration Act 1908”

Signature of the Sub Registrar

OR

“Refused document registration for not fulfilling the conditions of section 21 of Registration Act 1908”

Signature of the Sub Registrar

Use Case No.3:

The Format of the ENDORSEMENT in case of DOCUMENT REFUSED for Registration after entry in the minute book giving reasons for the same

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)
2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. "Refused Registration"

Signature of the Sub
Registrar

(Note: The Copy of the reasons recorded in the minute book should be printed and given to the parties SEPARATELY ie., on a separate sheet and NOT on the endorsement)

28.4 Stamp Duty on DUPLICATE DOCUMENT presented along with the original document

Usually in case of Deeds of Partition, Lease, Agreement, Settlement, Duplicate, Counterpart, Supplemental Deeds, Further Charge on Simple Mortgage, Subsidiary, Collateral, Additional and Substituted Security, etc., along with the original deed, the duplicate or triplicate copies of the deed will be presented for registration to enable the parties to have the copy of the document for each one.

Under these circumstances, the stamp duty paid as per the applicable article of stamps is calculated and additional stamp duty for each duplicate copy at the rate of Rs.500 each is also paid. The original stamp duty paid as per the article of the stamp act is certified on the original document under section 10A of Karnataka Stamp Act, 1957. The remaining stamp duty paid for each duplicate shall be recorded on the duplicate copies in 10A Certificate. After 10A certificate of Rs.500 on the duplicate, there shall be denoting of the original stamp duty paid on the original deed to be recorded as follows:

“I hereby certify that on production of the original document, I have satisfied myself that the stamp duty of Rs..... has been paid thereon”

Sub Registrar & Proper Officer

Use Case No.1: (Original Copy)

The Format of the ENDORSEMENT in case of ORIGINAL DOCUMENT

1. 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)

...ನೀ ಭೂದ ದಸ್ತಾವೇಜು ಸಂಖ್ಯೆ: 105
20-21

ಉಬ್ಬ ನೋಂದಣಿದಾಖಲಾತಿ

ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ನೋಂದಣಿ ಹಾಗೂ ಮುದ್ರಾಂಕ ಇಲಾಖೆ
Department of Stamps and Registration
ಪ್ರಮಾಣ ಪತ್ರ

1957 ರ ಕರ್ನಾಟಕ ಮುದ್ರಾಂಕ ಕಾಯ್ದೆಯ ಕೆಲಸ 10 ಎ ಅಡಿಯಲ್ಲಿಯ ಪ್ರಮಾಣ ಪತ್ರ

ಶ್ರೀ K. Nuryanagowda S/o H. Kempaloh . ಇವರು 5000.00 ರೂಪಾಯಿಗಳನ್ನು ನಿಗದಿತ ಮುದ್ರಾಂಕ ಕುಲ್ಯವಾಗಿ ಪಾವತಿಸಿರುವುದನ್ನು ದೃಢೀಕರಿಸಲಾಗಿದೆ

ಪ್ರಕಾರ	ಮೊತ್ತ (ರೂ.)	ಹಣದ ಪಾವತಿಯ ವಿವರ
ನಗದು ರೂಪ	5000.00	Paid in Cash.
ಒಟ್ಟು :	5000.00	

ಸ್ಥಳ : ಗಾಂಧಿನಗರ
ದಿನಾಂಕ : 22/05/2020

ನೋಂದಣಿ ಮತ್ತು ಮುದ್ರಾಂಕ ಇಲಾಖೆ
ಉಬ್ಬ ನೋಂದಣಿದಾಖಲಾತಿ
ಗಾಂಧಿನಗರ, ಬೆಂಗಳೂರು-9

(Note: This 10A Certificate shall have the stamp duty to be paid as per the article of the stamp)

2. If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
3. If Denoting is there, Denoting certificate is recorded (as usual)
4. Presentation Endorsement (as usual)
5. Party Information Endorsement (as usual)
6. Identifying Witness (Identifiers) Endorsement (as usual)
7. Payment before the Sub Registrar (if any) (as usual)
8. Registration Certificate as per Section 60 of Registration Act, 1908


 1 ನೇ ಪುಸ್ತಕದ ರಾಷ್ಟ್ರವೇಷು
 ನಂಬರ GAN-1-00105-2020-21 ಆಗಿ
 ಸಿ.ಡಿ. ನಂಬರ GAND681 ನೇ ರೂಪದಲ್ಲಿ
 ದಿನಾಂಕ 22-05-2020 ರಂದು ಸೇವಾಂವಾಯಿತಾಗಿದೆ.




 22/5/2020
 ಉಪನಿರ್ದೇಶಕರಾದ ಗಾಂಧಿನಗರ (ಉರಬರು) ಸಬ್ ರೆಜಿಸ್ಟ್ರಾರ್, ಬೆಂಗಳೂರು-9

Designed and Developed by C-DAC, ACTS, Pune

Use Case No.2: (Duplicate Copy)

The Format of the ENDORSEMENT in case of DUPLICATE COPY (if any)

- 10A Certificate - under Karnataka Stamp Act, 1957 Section 10A (as usual)

...ನೀ ಭುಟದ ದಸ್ತಾವೇಜು ಸಂಖ್ಯೆ: 105
20-21

ಉಬ್ಬರ ನೋಂದಣಿ ದಾಖಲೆ
ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ನೋಂದಣಿ ಹಾಗೂ ಮುದ್ರಾಂಕ ಇಲಾಖೆ
Department of Stamps and Registration
ಪ್ರಮಾಣ ಪತ್ರ

1957 ರ ಕರ್ನಾಟಕ ಮುದ್ರಾಂಕ ಕಾಯ್ದೆಯ ಕೆಲಸ 10 ಎ ಅಡಿಯಲ್ಲಿಯ ಪ್ರಮಾಣ ಪತ್ರ

ಶ್ರೀ K. Nuryanagowda S/o H. Kempaloh . ಇವರು 5000.00 ರೂಪಾಯಿಗಳನ್ನು ನಿಗದಿತ ಮುದ್ರಾಂಕ
ಕುಲುವಾಗಿ ಪಾವತಿಸಿರುವುದನ್ನು ದೃಢೀಕರಿಸಲಾಗಿದೆ

ಪ್ರಕಾರ	ಮೊತ್ತ (ರೂ.)	ಹಣದ ಪಾವತಿಯ ವಿವರ
ನಗದು ರೂಪ	5000.00	Paid in Cash.
ಒಟ್ಟು :	5000.00	

ಸ್ಥಳ : ಗಾಂಧಿನಗರ
ದಿನಾಂಕ : 22/05/2020

...ನೀ ಭುಟದ ದಸ್ತಾವೇಜು ಸಂಖ್ಯೆ: 105
20-21

(Note: This 10A Certificate shall have stamp duty of Rs.500 only)

- If Exemption is there, Exemption particulars (both Stamp Duty as well as Registration Fee) are recorded (as usual)
- If Denoting is there, Denoting certificate is recorded (as usual)

(Note: After 10A Certificate, the **Denoting** of the Original stamp duty on the duplicate or triplicate, etc., shall record the denoting as below)

"I hereby certify that on production of the original document, I have satisfied myself that the stamp duty of Rs..... has been paid thereon"

Sub Registrar & Proper Officer

(Note: 1. The original stamp duty on the original document shall be fetched in the above sentence (ie., stamp duty of Rs.....); 2. Minute Book concept does not appear here)

- Presentation Endorsement (as usual)
- Party Information Endorsement (as usual)
- Identifying Witness (Identifiers) Endorsement (as usual)
- Payment before the Sub Registrar (if any) (as usual)
- Registration Certificate as per Section 60 of Registration Act, 1908


 1 ನೇ ಪುಸ್ತಕದ ರಾಷ್ಟ್ರವೇಷು
 ನಂಬರ GAN-1-00105-2020-21 ಆಗಿ
 ಸಿ.ಡಿ. ನಂಬರ GAND681 ನೇ ರೂಪ
 ದಿನಾಂಕ 22-05-2020 ರಂದು ಸೇವಾದಾಯವಾಗಿದೆ




 22/5/2020
 ಉಪನಿರ್ದೇಶಕರಾದಿಗಳ ಕಛೇರಿ (ಉಪನಿರ್ದೇಶಕರಾದಿಗಳ ಕಛೇರಿ)
 ಬೆಂಗಳೂರು, ಬೆಂಗಳೂರು-9

Designed and Developed by C-DAC, ACTS, Pune

29 CANCELLATION DEED

29.1 Brief Description

i. Brief Description

Cancellation, etc, of a registered document. ----

(i) On the registration of a document which revokes or cancels or rectifies an error, in, or modifies the terms of a document previously registered in the same class or Register book or of a return of lands acquired under the Land Acquisition Act or of a document received and filed under Section 89 (vide Rule 17), or on the receipt of a communication from a Revenue Officer or from a Court which intimates a similar revocations, cancellation, rectification or modification, a note shall be entered at the foot of the entry of the latter document of communication as under.---

“This Document/Communication revokes (cancels, rectifies or modifies) Document No. of Copied/the document filed/ the return filed at pages Volume of book/supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered or filed a note shall be entered as shown below”

“This document/return has been revoked (cancelled, rectified or modified by Document No..... of copied/the document filed/ the return filed at pages..... Volume of book/ supplement to Book No.1(part)/file book”

(ii) When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I,II,III or IV, a note of rectification shall also be entered in the respective index against the particular item rectified.

29.2 Functional Step by step Approach

ii. Functional Step by Step Process

Use Case No.1:

14(a) of Cancellation Deed - Any instrument previously executed on which stamp duty has been paid

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (NOT APPLICABLE)
4. Document Information
 - a. The applicant shall enter (from among) the following details:

- i. Nature of Document – ‘Cancellation Deed’
 - i. Article – ‘14 Cancellation Deed’
 - ii. Sub-article – ‘14(a) Any instrument previously executed on which stamp duty has been paid’
 - iii. Book Number – 1 (to be auto-fetched)
 - 5. Property Schedule (NOT APPLICABLE)
 - Note: Here, the system shall capture/retrieve the below said details:**
 - a. The applicant shall enter the previous document number
 - b. The system shall fetch the particulars of the property
 - c. The system shall also fetch the stamp duty paid on the previous document
 - 6. Party Details (usual flow)
 - 7. MV, Stamp Duty & Fee Calculation
 - a. **Calculation of MV isn’t required**
 - b. **The stamp duty paid on the previous document shall be fetched**
 - c. **Registration Fee = Rs.200 (fixed)**
 - 8. Online Document Summary (usual flow)
 - 9. SRO Confirmation (usual flow)
 - 10. Payment (usual flow)
 - 11. Appointment Scheduler (usual flow)
 - 12. Document Summary/Signature (usual flow)
 - 13. Document Registration
 - a. At the time of ‘Check & Register’, the SR shall be given a button (option) for **adding ‘Cross Reference’**
 - b. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘Previous Document’**

“This document/return has been revoked (cancelled, rectified or modified by Document No..... of copied/the document filed/ the return filed at pages..... Volume of book/ supplement to Book No.1(part)/file book”
 - c. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘New Document’**

“This Document/Communication revokes (cancels, rectifies or modifies) Document No. of Copied/ the document filed/ the return filed at pages Volume of book/supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered”
- (Note: The above cross reference as mentioned in steps b & c should be in case of document manually registered **prior to computerisation**)
- d. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**

- e. The below mention sentences (paragraph) should be printed on the **Endorsement of 'Previous Document'**

"This document/ return has been revoked (cancelled, rectified or modified by Document No..... of scanned and stored in database/ the document filed/ the return filed at database..... / supplement to Book No.1(part)/ file book"

- f. The below mention sentences (paragraph) should be printed on the **Endorsement of 'New Document'**

"This Document/ Communication revokes (cancels, rectifies or modifies) Document No. of scanned and stored in database/ the document filed/ the return filed and stored in database supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered"

(Note: The above cross reference as mentioned in steps e & f should be in case of document manually registered **after computerisation**)

- g. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- h. The SR sends to DEO to print the Endorsement
- i. The DEO prints the endorsement on the New Document and shall send it to SR for
- j. The DEO shall get the signatures of the parties and 2 witness (related to the New Document); Seal and Signature of the SR
- k. The DEO shall scan and upload the new document and the enclosures and shall send it for digital signature of the SR
- l. The Sakala gets updated having completed the document registration process
- m. The system shall generate the J-Slip in the XML format and sends it to the concerned aligned data base (bhoomi, e-sathu, e-asthi, etc)
- n. The SR digitally signs, encrypts and uploads to SDC
- o. The SR shall send to FDA/SDA for printing of Acknowledgement and shall physically handover the new document to the parties

Use Case No.2:

14(b) of Cancellation Deed - Any instrument executed by or on behalf of the central government or a local authority or other authority

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (NOT APPLICABLE)
4. Document Information
 - a. The applicant shall enter (from among) the following details:
 - i. Nature of Document – **‘Cancellation Deed’**
 - ii. Article – **‘14 Cancellation Deed’**
 - iii. Sub-article – **‘14 (b) - any instrument executed by or on behalf of the central government or a local authority or other authority’**
 - iv. Book Number – 1 (to be auto-fetched)
5. Property Schedule (NOT APPLICABLE)

Note: Here, the system shall capture/retrieve the below said details:

- a. The applicant shall enter the previous document number
 - b. The system shall fetch the particulars of the property
 - c. The system shall also fetch the stamp duty paid on the previous document
6. Party Details (usual flow)
7. MV, Stamp Duty & Fee Calculation
 - a. **Calculation of MV isn't required**
 - b. **Stamp Duty = Rs.100 (fixed)**
 - c. **Registration Fee = Rs.200 (fixed)**
8. Online Document Summary (usual flow)
9. SRO Conformation (usual flow)
10. Payment (usual flow)
11. Appointment Scheduler (usual flow)
12. Document Summary/Signature (usual flow)
13. Document Registration
 - a. At the time of ‘Check & Register’, the SR shall be given a button (option) for **adding ‘Cross Reference’**
 - b. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘Previous Document’**

“This document/return has been revoked (cancelled, rectified or modified by Document No..... of copied/the document filed/ the return filed at pages..... Volume of book/ supplement to Book No.1(part)/file book”

- c. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘New Document’**

“This Document/Communication revokes (cancels, rectifies or modifies) Document No. of Copied/ the document filed/ the return filed at pages Volume of book/supplement to Book No. 1. (Part)/file book

and at the foot of the previous entry or of the document previously registered”

(Note: The above cross reference as mentioned in steps b & c should be in case of document manually registered **prior to computerisation**)

- d. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- e. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘Previous Document’**

“This document/ return has been revoked (cancelled, rectified or modified by Document No..... of scanned and stored in database/ the document filed/ the return filed at database..... / supplement to Book No.1(part)/ file book”

- f. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘New Document’**

“This Document/ Communication revokes (cancels, rectifies or modifies) Document No. of scanned and stored in database/ the document filed/ the return filed and stored in database supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered”

(Note: The above cross reference as mentioned in steps e & f should be in case of document manually registered **after computerisation**)

- g. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- h. The SR sends to DEO to print the Endorsement
- i. The DEO prints the endorsement on the New Document and shall send it to SR for
- j. The DEO shall get the signatures of the parties and 2 witness (related to the New Document); Seal and Signature of the SR
- k. The DEO shall scan and upload the new document and the enclosures and shall send it for digital signature of the SR
- l. The Sakala gets updated having completed the document registration process

- m. The system shall generate the J-Slip in the XML format and sends it to the concerned aligned data base (bhoomi, e-sathu, e-asthi, etc)
- n. The SR digitally signs, encrypts and uploads to SDC
- o. The SR shall send to FDA/SDA for printing of Acknowledgement and shall physically handover the new document to the parties

Use Case No.3:

14(c) of Cancellation Deed - In any other case

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (NOT APPLICABLE)
4. Document Information
 - a. The applicant shall enter (from among) the following details:
 - i. Nature of Document – **‘Cancellation Deed’**
 - ii. Article – **‘14 Cancellation Deed’**
 - iii. Sub-article – **‘14 (c) In any other case’**
 - iv. Book Number – 1 (to be auto-fetched)
5. Property Schedule (NOT APPLICABLE)

Note: Here, the system shall capture/retrieve the below said details:

- a. The applicant shall enter the previous document number
 - b. The system shall fetch the particulars of the property
 - c. The system shall also fetch the stamp duty paid on the previous document
6. Party Details (usual flow)
7. MV, Stamp Duty & Fee Calculation
 - a. **Calculation of MV isn't required**
 - b. **Stamp Duty = Rs.100 (fixed)**
 - c. **Registration Fee = Rs.200 (fixed)**
8. Online Document Summary (usual flow)
9. SRO Conformation (usual flow)
10. Payment (usual flow)
11. Appointment Scheduler (usual flow)
12. Document Summary/Signature (usual flow)
13. Document Registration
 - a. At the time of 'Check & Register', the SR shall be given a button (option) for **adding 'Cross Reference'**
 - b. The below mention sentences (paragraph) should be printed on the **Endorsement of 'Previous Document'**

“This document/return has been revoked (cancelled, rectified or modified by Document No..... of copied/the document filed/ the return filed at pages..... Volume of book/ supplement to Book No.1(part)/file book”

- c. The below mention sentences (paragraph) should be printed on the **Endorsement of 'New Document'**

“This Document/Communication revokes (cancels, rectifies or modifies) Document No. of Copied/ the document filed/ the return filed at pages Volume of book/supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered”

(Note: The above cross reference as mentioned in steps b & c should be in case of document manually registered **prior to computerisation**)

- d. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- e. The below mention sentences (paragraph) should be printed on the **Endorsement of 'Previous Document'**

"This document/ return has been revoked (cancelled, rectified or modified by Document No..... of scanned and stored in database/ the document filed/ the return filed at database..... / supplement to Book No.1(part)/ file book"

- f. The below mention sentences (paragraph) should be printed on the **Endorsement of 'New Document'**

"This Document/ Communication revokes (cancels, rectifies or modifies) Document No. of scanned and stored in database/ the document filed/ the return filed and stored in database supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered"

(Note: The above cross reference as mentioned in steps e & f should be in case of document manually registered **after computerisation**)

- g. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- h. The SR sends to DEO to print the Endorsement
- i. The DEO prints the endorsement on the New Document and shall send it to SR for
- j. The DEO shall get the signatures of the parties and 2 witness (related to the New Document); Seal and Signature of the SR
- k. The DEO shall scan and upload the new document and the enclosures and shall send it for digital signature of the SR
- l. The Sakala gets updated having completed the document registration process
- m. The system shall generate the J-Slip in the XML format and sends it to the concerned aligned data base (bhoomi, e-sathu, e-asthi, etc)
- n. The SR digitally signs, encrypts and uploads to SDC
- o. The SR shall send to FDA/SDA for printing of Acknowledgement and shall physically handover the new document to the parties

Use Case No.4:

14(d) of Cancellation Deed - Cancellation of Sale Deed

1. User Registration (usual flow)
2. Document Information (usual flow)
3. Property Search (NOT APPLICABLE)
4. Document Information (usual flow)
 - a. The applicant shall enter (from among) the following details:
 - i. Nature of Document – **‘Cancellation Deed’**
 - ii. Article – **‘14 Cancellation Deed’**
 - iii. Sub-article – **‘14(d) Cancellation of Sale Deed’**
 - iv. Book Number – 1 (to be auto-fetched)

5. Property Schedule (NOT APPLICABLE)

Note: Here, the system shall capture/retrieve the below said details:

- a. The applicant shall enter the previous document number
 - b. The system shall fetch the particulars of the property
 - c. The system shall also fetch the stamp duty paid on the previous document
6. Party Details (usual flow)
7. MV, Stamp Duty & Fee Calculation
 - a. **Present market value (MV) shall be calculated**
 - b. **At this point, the property information of the previously registered document which is under cancellation should be fetched from the database of kaveri**
 - c. **The stamp duty = 5% on the MV**
 - d. **Surcharge = either 2% or 3% on the stamp duty depending upon whether the property is situated in urban or rural respectively**
 - e. **Cess = 10% on the stamp duty**
 - f. **Registration Fee = 1% on the MV**
8. Online Document Summary (usual flow)
9. SRO Conformation (usual flow)
10. Payment (usual flow)
11. Appointment Scheduler (usual flow)
12. Document Summary/Signature (usual flow)
13. Document Registration
 - a. At the time of ‘Check & Register’, the SR shall be given a button (option) for **adding ‘Cross Reference’**
 - b. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘Previous Document’**

“This document/return has been revoked (cancelled, rectified or modified by Document No..... of copied/the document filed/ the return filed at pages..... Volume of book/ supplement to Book No.1(part)/file book”

- c. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘New Document’**

“This Document/Communication revokes (cancels, rectifies or modifies) Document No. of Copied/ the document filed/ the return filed at pages Volume of book/supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered”

(Note: The above cross reference as mentioned in steps b & c should be in case of document manually registered **prior to computerisation**)

- d. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- e. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘Previous Document’**

“This document/ return has been revoked (cancelled, rectified or modified by Document No..... of scanned and stored in database/ the document filed/ the return filed at database..... / supplement to Book No.1(part)/ file book”

- f. The below mention sentences (paragraph) should be printed on the **Endorsement of ‘New Document’**

“This Document/ Communication revokes (cancels, rectifies or modifies) Document No. of scanned and stored in database/ the document filed/ the return filed and stored in database supplement to Book No. 1. (Part)/file book and at the foot of the previous entry or of the document previously registered”

(Note: The above cross reference as mentioned in steps e & f should be in case of document manually registered **after computerisation**)

- g. When the revocation, cancellation rectification or modification is of a document relating to immovable property, a corresponding note shall also be entered in Index No. II and when it relates to the rectification of any particular item entered Index, I, II, III or IV, **a note of rectification shall also be entered in the respective index against the particular item rectified.**
- h. The SR sends to DEO to print the Endorsement
- i. The DEO prints the endorsement on the New Document and shall send it to SR for
- j. The DEO shall get the signatures of the parties and 2 witness (related to the New Document); Seal and Signature of the SR

- k. The DEO shall scan and upload the new document and the enclosures and shall send it for digital signature of the SR
- l. The Sakala gets updated having completed the document registration process
- m. The system shall generate the J-Slip in the XML format and sends it to the concerned aligned data base (bhoomi, e-sathu, e-asthi, etc)
- n. The SR digitally signs, encrypts and uploads to SDC
- o. The SR shall send to FDA/SDA for printing of Acknowledgement and shall physically handover the new document to the parties

30 REGISTRATION AND CANCELLATION OF WILL

30.1 Registration of Will

30.1.1 Brief Description

iii. **Brief Description:**

Will is a Testamentary Document executed by the testator with respect to his/her will to distribute his/her property after his/her demise. Will may be either Registered in the Office of the Sub-Registrar or Deposited in the Office of the District-Registrar. Will might either be Registered or Not. It has its own validity.

For Registration of Will, the testator may get registered as below:

30.1.2 SCENARIO 1

The Testator gets his Will Registered

27.1.2.1 Brief Description

i. **Brief Description:**

Registration of Will

27.1.2.2 Process Flow

ii. **Process Flow Diagram:**




Figure 1: Process Flow Diagram for Will Registration (by the Testator)

27.1.2.3 Functional Step by Step Process

iii. Functional Step by Step Process:

For Registration of Will, the testator may get registered as below:

14. User Registration (usual flow)

Applicant Login

- To file the application online, the applicant shall browse for **Kaveri Online Services** ie., Kaveri2.0
- The applicant shall register as a user by creating user id and password
- The applicant shall now login in the Kaveri2.0 portal

15. Document Information (usual flow)

- The applicant shall click on '**Start a New Application**'
- The applicant shall select '**Document Registration**' from among the '**Type of Service**' option on the screen

16. Property Search (NOT APPLICABLE)

- The applicant shall select '**Will/Miscellaneous**' from among the '**Type of Document**' option
- The applicant shall select '**Will**' from within the '**Will/Miscellaneous**' option
- Property Search isn't required

17. Document Information (usual flow)

- The applicant shall select the following details from the dropdown menu
 - Nature of Document as '**Will**'
 - Article – Not Applicable '**Will**'

- iii. Sub-article – Not Applicable '**Will**'
 - iv. Book Number as '**3**' (will be auto-fetched)
- 18. Property Schedule (NOT APPLICABLE)
 - a. Property Schedule isn't required
- 19. Party Details
 - a. The Presenter – the presenter will be Testator only
 - b. The Executant – the Presenter himself/herself is the Executant
 - c. Claimant - there shall be No Claimant
 - d. Witness – 2 witnesses shall be required

(Note: The can be more than one executants; In case the applicant (testator) applies for **Private Residence Attendance** by clicking on the private attendance checkbox, then the flow should follow the private attendance procedure)
- 20. MV, Stamp Duty & Fee Calculation
 - a. No MV (Market Valuation) and No SD (Stamp Duty)
 - b. RF (Registration Fee) = Rs.200 (fixed)
 - c. Scanning Fee (Rs.35/- per page of scanning)

(Note: The concept of Condonation Delay isn't applicable in Registration of Will ie., the will document can be registered even after 8 months from the date of execution of will document)
- 21. Online Document Summary (usual flow)
 - a. (Note: As Will is a Confidential Document, the copy of the document shall be uploaded, but only the SR shall have the access to view it)
- 22. SRO Confirmation (usual flow)
 - a. Follow the usual flow, but the SR and FDA/SDA shall verify only the Total Payable Amount
- 23. Payment (usual flow)
- 24. Appointment Scheduler (usual flow)
- 25. Document Summary/Signature (usual flow)
- 26. Document Registration (usual flow)
 - a. (Note: The Registered Will goes to Book 3 (for Testamentary documents))
- 27. Exceptional Cases (usual flow)
 - a. (Note: In case the applicant (testator) applies for **Private Residence Attendance** by clicking on the private attendance checkbox in the Party Details screen, then the flow should follow the private attendance procedure)

30.1.3 SCENARIO 2

The Will Registration after the death of the Testator

27.1.3.1 Brief Description

i. Brief Description:

If the Will is returned by the Testator, and not registered till his/her demise, the beneficiary or the legal heirs may present the will for registration after the demise of the Testator.

In addition to the information above, please find a detailed requirements document attached:

<https://csgkarnataka.sharepoint.com/sites/ULMS/Knowledge%20Base/Forms/AllItems.aspx?id=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS%2FStatus%20Tracking%20Module%20FRS%20V%2E02%2Epdf&parent=%2Fsites%2FULMS%2FKnowledge%20Base%2FFRS>

Please use the above link to access Will after death of testator detailed FRS.

27.1.3.2 Process Flow Diagram

ii. Process Flow Diagram:




Figure 2: Process Flow Diagram for Will Registration (by the beneficiary/legal heirs)

27.1.3.3 Functional Step by Step Process

iii. **Functional Step by Step Process:**

After the demise of the Testator, the beneficiary or the legal heirs may present the will for registration as below:

1. User Registration (usual flow)
Applicant Login
 - a. To file the application online, the applicant shall browse for **Kaveri Online Services** ie., Kaveri2.0
 - b. The applicant shall register as a user by creating user id and password
 - c. The applicant shall now login in the Kaveri2.0 portal
2. Document Information (usual flow)
 - a. The applicant shall click on '**Start a New Application**'
 - b. The applicant shall select '**Document Registration**' from among the '**Type of Service**' option on the screen
3. Property Search (NOT APPLICABLE)
 - a. The applicant shall select '**Will/Miscellaneous**' from among the '**Type of Document**' option
 - b. The applicant shall select '**Will**' from within the '**Will/Miscellaneous**' option
 - c. Property Search isn't required
4. Document Information (usual flow)
 - a. The applicant shall select the following details from the dropdown menu
 - i. Nature of Document as '**Will**'
 - ii. Article – Not Applicable '**Will**'
 - iii. Sub-article – Not Applicable '**Will**'
 - iv. Book Number as '**3**' (will be auto-fetched)
5. Property Schedule (NOT APPLICABLE)
6. Party Details
 - a. The Presenter is either a beneficiary or a legal heir
 - b. The Executant can either be the Authority Adopted, Executors (2 Witnesses), and Scribe (Lawyer/Deed Writer), (as the Testator who was supposed to the executant is demised)
(Note: The applicant has to upload the Death Certificate of the Testator in the upload section)
 - c. The Beneficiary (as called here in this case, instead of Claimant) is the beneficiary or legal heirs
7. MV, Stamp Duty & Fee Calculation
 - a. No MV (Market Valuation) and No SD (Stamp Duty)
 - b. RF (Registration Fee) = Rs.200 (fixed)
 - c. Scanning Fee (Rs.35/- per page of scanning)
8. Online Document Summary (usual flow)
 - a. In the Upload Section, the following documents have to be uploaded:
 - i. Death Certificate

- ii. Deed Document
 - iii. Annexures/Enclosures – ID Proof & Address Proof of Beneficiary/
Legal heirs, Witnesses and Scribe (Lawyer/Deed Writer), etc.
- 9. SRO Confirmation (usual flow)
- 10. Payment (usual flow)
- 11. Appointment Scheduler (usual flow)
- 12. Document Summary/Signature
 - a. On the day of Appointment, only the Presenter and the Beneficiary (ie., the claimant/s) shall appear before the Sub-Registrar at SRO
 - b. The Executant (Executors (2 Witnesses) or Authority Adopted) shall be SUMMONED by the Sub-Registrar at DIFFERENT TIMES (for each executant) to take their Deposition (by SR), Photo & Thumb Impression (by DEO)
 - c. The Generation & Print of Summary must be done for each executor separately. An option has to be provided for the same
- 13. Document Registration (usual flow)
 - a. (Note: The Registered Will goes to Book 3 (for Testamentary documents))

30.2 Will including Cancellation

27.1.2.1 Brief Description

iv. Brief Description:

Cancellation and then Registration of Will

27.1.2.2 Process Flow

v. Process Flow Diagram:




Figure 1: Process Flow Diagram for Will Registration (by the Testator)

27.1.2.3 Functional Step by Step Process

vi. Functional Step by Step Process:

For Registration of Will, the testator may get registered as below:

1. User Registration (usual flow)

Applicant Login

- To file the application online, the applicant shall browse for **Kaveri Online Services** ie., Kaveri2.0
- The applicant shall register as a user by creating user id and password
- The applicant shall now login in the Kaveri2.0 portal

2. Document Information (usual flow)

- The applicant shall click on '**Start a New Application**'

- b. The applicant shall select '**Document Registration**' from among the '**Type of Service**' option on the screen
- 3. Property Search (NOT APPLICABLE)
 - a. The applicant shall select '**Will/Miscellaneous**' from among the '**Type of Document**' option
 - b. The applicant shall select '**Will**' from within the '**Will/Miscellaneous**' option
 - c. Property Search isn't required
- 4. Document Information (usual flow)
 - a. The applicant shall select the following details from the dropdown menu
 - i. Nature of Document as '**Will including Cancellation**'
 - ii. Article – Not Applicable '**Cancellation**'
 - iii. Sub-article – Not Applicable '**Cancellation**'
 - iv. Book Number as '**3**' (will be auto-fetched)
- 5. Property Schedule (NOT APPLICABLE)
 - a. Property Schedule isn't required
- 6. Party Details
 - a. The Presenter – the presenter will be Testator only
 - b. The Executant – the Presenter himself/herself is the Executant
 - c. Claimant - there shall be No Claimant
 - d. Witness – 2 witnesses shall be required

(Note: There can be more than one executants; In case the applicant (testator) applies for **Private Residence Attendance** by clicking on the private attendance checkbox, then the flow should follow the private attendance procedure)

- 7. MV, Stamp Duty & Fee Calculation
 - a. No MV (Market Valuation) and No SD (Stamp Duty)
 - b. RF (Registration Fee) = Rs.200 (fixed)
 - c. Scanning Fee (Rs.35/- per page of scanning)
- (Note: The concept of Condonation Delay isn't applicable in Registration of Will i.e., the will document can be registered even after 8 months from the date of execution of will document)
- 8. Online Document Summary (usual flow)
 - a. (Note: As Will is a Confidential Document, the copy of the document shall be uploaded, but only the SR shall have the access to view it)
 - 9. SRO Confirmation (usual flow)
 - a. Follow the usual flow, but the SR and FDA/SDA shall verify only the Total Payable Amount
 - 10. Payment (usual flow)
 - 11. Appointment Scheduler (usual flow)
 - 12. Document Summary/Signature (usual flow)
 - 13. Document Registration (usual flow)
 - a. (Note: The Registered Will goes to Book 3 (for Testamentary documents))

14. Exceptional Cases (usual flow)

- a. (Note: In case the applicant (testator) applies for **Private Residence Attendance** by clicking on the private attendance checkbox in the Party Details screen, then the flow should follow the private attendance procedure)

1. Property Search (NOT APPLICABLE)
 - a. The applicant shall select '**Will/Miscellaneous**' from among the '**Type of Document**' option
 - b. The applicant shall select '**Will**' from within the '**Will/Miscellaneous**' option
 - c. Property Search isn't required
 - d. '**Document Search**' instead of 'Property Search' will happen
 - i. Enter the Document Number
 - ii. Search the Document
2. Document Information (usual flow)
 - a. The applicant shall select the following details from the dropdown menu
 - i. Nature of Document as '**Cancellation of Will**'
 - ii. Article as '**Cancellation**'
 - iii. Sub-article – '**Cancellation**'
 - iv. Book Number as '**3**' (will be auto-fetched)
3. Property Schedule (NOT APPLICABLE)
4. Party Details (usual flow)
 - a. The Presenter – the presenter will be Testator only
 - b. The Executant – the Presenter himself/herself is the Executant
 - c. Claimant - there shall be No Claimant
 - d. Witness – 2 witnesses shall be required
5. MV, Stamp Duty & Fee Calculation
 - a. MV (Market Valuation) isn't applicable
 - b. SD (Stamp Duty) = Rs.100 (fixed)
 - c. RF (Registration Fee) = Rs.200 (fixed)
 - d. Scanning Fee (Rs.35/- per page of scanning)
6. Online Document Summary (usual flow)
7. SRO Confirmation (usual flow)
8. Payment (usual flow)
9. Appointment Scheduler (usual flow)
10. Document Summary/Signature (usual flow)
11. Document Registration (usual flow)
 - a. The Sub-Registrar **shall first get the document registered** following the usual process of registration
 - b. After registration of cancellation deed is complete, the Sub-Registrar shall:
 - i. **Enter the Document Number** which is to be cancelled for Cross-Reference
 - ii. **Search** the Document

- iii. Option has to be **given to link** the **Cross-Reference Module**
- iv. Follow the due process to **update** the Cross-Reference in **BOTH the documents (old & new documents)**
- v. Reference must be made (in the below said manner)

Say, "This Document cancels Document No. of Copied at pages Volume of Book No. 3. at the foot of the previous entry or of the document previously registered a note shall be entered as shown below"

"This document has been cancelled by Document No..... of copied Volume of book"

<u>NoD</u>	<u>Art.</u>	<u>Sub Art</u>	<u>(SD, RT)</u>
1. Will	(i) Will	Will	(10, 100)
2. Will incl. Cancellation	Cancellation	Cancellation	(100, 100)
3. Cancellation of Will	Cancellation	Cancellation	(100, 100)
4. Pay	(i) Deposit of Will @ DR → safe custody (ii) Will prevent w/ after the death of testator. (iii) Will prevent w/ after the death of testator. (Ex- Ardy)		

30.3

30.4 Cancellation of Will

30.4.1 Brief Description

i. Brief Description:

Cancellation of Will means that the Will which is registered previously by the testator may be cancelled by himself/herself by following the due process

30.4.2 Process Flow

ii. Process Flow Diagram:




Figure 3: Process Flow Diagram for Cancellation of Will

30.4.3 Functional Step by Step Process

iii. Functional Step by Step Process:

For Cancellation of Will Registered, the testator shall get registered will cancelled as below:

12. User Registration (usual flow)

Applicant Login

- To file the application online, the applicant shall browse for **Kaveri Online Services** ie., Kaveri2.0

- b. The applicant shall register as a user by creating **User ID and Password**
 - c. The applicant shall now login in the Kaveri2.0 portal
- 13. Document Information (usual flow)
 - a. The applicant shall click on '**Start a New Application**'
 - b. The applicant shall select '**Document Registration**' from among the '**Type of Service**' option on the screen
- 14. Property Search (NOT APPLICABLE)
 - a. The applicant shall select '**Will/Miscellaneous**' from among the '**Type of Document**' option
 - b. The applicant shall select '**Will**' from within the '**Will/Miscellaneous**' option
 - c. Property Search isn't required
 - d. '**Document Search**' instead of 'Property Search' will happen
 - i. Enter the Document Number
 - ii. Search the Document
- 15. Document Information (usual flow)
 - a. The applicant shall select the following details from the dropdown menu
 - i. Nature of Document as '**Cancellation of Will**'
 - ii. Article as '**14 Cancellation**'
 - iii. Sub-article – '**14(c) In any other case**' ie., '**Cancellation**'
 - iv. Book Number as '**3**' (will be auto-fetched)
- 16. Property Schedule (NOT APPLICABLE)
- 17. Party Details (usual flow)
 - a. The Presenter – the presenter will be Testator only
 - b. The Executant – the Presenter himself/herself is the Executant
 - c. Claimant - there shall be No Claimant
 - d. Witness – 2 witnesses shall be required
- 18. MV, Stamp Duty & Fee Calculation
 - a. MV (Market Valuation) isn't applicable
 - b. SD (Stamp Duty) = Rs.100 (fixed)
 - c. RF (Registration Fee) = Rs.200 (fixed)
 - d. Scanning Fee (Rs.35/- per page of scanning)
- 19. Online Document Summary (usual flow)
- 20. SRO Confirmation (usual flow)
- 21. Payment (usual flow)
- 22. Appointment Scheduler (usual flow)
- 23. Document Summary/Signature (usual flow)
- 24. Document Registration (usual flow)
 - a. The Sub-Registrar **shall first get the document registered** following the usual process of registration
 - b. After registration of cancellation deed is complete, the Sub-Registrar shall:
 - i. **Enter the Document Number** which is to be cancelled for Cross-Reference
 - ii. **Search** the Document

- iii. Option has to be **given to link** the **Cross-Reference Module**
- iv. Follow the due process to **update** the Cross-Reference in **BOTH the documents (old & new documents)**
- v. Reference must be made (in the below said manner)

Say, "This Document cancels Document No. of Copied at pages Volume of Book No. 3. at the foot of the previous entry or of the document previously registered a note shall be entered as shown below"

"This document has been cancelled by Document No..... of copied Volume of book"

31 MARRIAGE REGISTRATION MODULE

31.1 Brief Description

In addition to the information below, please find a detailed requirements document attached:

https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Submitted/Marriage%20Registration%20Module_V3.0.docx?d=wd99ada19c4b64b21a7a44903e47c72ad&csf=1&web=1&e=20yNOJ

Please use the above link to access Marriage registration detailed FRS.

i. **Brief Description**

Marriage is “a religious sacrament in which a man and a woman are bound in a permanent relationship for the physical, social, spiritual, procreation and sexual needs; a formal union and social and legal contract between two individuals that unites their lives legally, economically, and emotionally”. The contractual marriage agreement usually implies that the couple has legal obligations to each other throughout their lives or until they decide to divorce. Being married also gives legitimacy to sexual relations within the marriage.

Overview

Any citizen can avail the service. This service generates a certificate which is accepted as legal proof for marriage. The SR is the person authorized to issue Marriage certificate and also solemnize the marriage as the case may be. This service can be availed at the SRO.

Marriages are registered under following acts:

1. Hindu Marriage Act, 1955
2. Special Marriage Act, 1954
3. Parsi Marriage and Divorce Act, 1936
4. Karnataka Marriage (Registration and miscellaneous provision) Act, 1976

Marriage under Hindu Marriage Act can be registered in the office of the Registrar of Marriages situated in the jurisdiction of which marriage has taken place or where bride or bride-groom resides. Though actual marriage rituals can be performed outside, the filing or registration of marriage is done at SRO. When it is a special marriage it is done through notice for intended marriage and the SR solemnizes the marriage in his presence in his office.

Actors

1. Bride and Groom – Presents the relevant records/documents for registration
2. Witnesses – witnessing the marriage
3. Objector – one who objects to the marriage (special marriage intended notice & special marriage of other forms)
4. SRO – Scrutinizes document, admits for registration, signs the marriage certificate
5. Operators (FDA/SDA) – Enters data, captures/attaches photo, generates registration number scans and archives documents
6. Kaveri 2.0 – Software used for registration

Inputs

1. Age proof
2. Proof of residence (both Permanent & Current)
3. Place of marriage (Marriage card)
4. Application in prescribed form for Marriage Registration
5. Declaration by the Bride and Groom
6. Memorandum of Marriages containing details of bride, groom and witnesses
7. Enclosures

Output

1. The Marriage Certificate is issued by the Sub Registrar (SR/MO/RoM)

31.2 Stakeholder – Role & Responsibilities

Applicant

1. Submits application along with necessary documents, photo, etc.
2. Pays requisite fees
3. Schedules (books) an appointment with SR/MO/RoM
4. Signs and Submits declaration and final certificate

FDA/SDA

1. Initial scrutiny of application and enclosures
2. Verifies application and enclosures
3. Edit application in system
4. Captures digital photograph of the couple
5. Prints certificate after Marriage Officer's approval
6. Obtains bridegroom, bride and witnesses signature
7. Obtains Marriage Officer's seal and signature
8. Scan and upload documents and annexures
9. Issues certificate and updates the system

Marriage Officer (MO) / Registrar of Marriage (RoM) (here, SR acts as MO/RoM)

1. Allocates application to FDA/SDA
2. Sends back to the applicant after verification of application and enclosures by FDA/SDA
3. Administers oath in case of special marriage
4. Approves/Send back to applicant with reason/Rejects registration in system
5. Signs and puts seal on printed certificate
6. Enquiry of Objections

Objector

1. Files an objection to the marriage registration
2. Submits application form along with necessary documents
3. Pays requisite fees

System

1. Records application (online as well as manually entered)
2. Accepts payment and captures payment detail
3. Allows modification/deletion of entered data before registration/ after registration with orders from concerned Marriage Officer
4. Notifies Marriage Officer /FDA/Applicants if rejected
5. Records notice of intended marriage/declaration
6. Displays notice for public on the portal/office notice board
7. Generates marriage certificate
8. Captures delivery details
9. Shows status of application
10. Displays application on query
11. Displays marriage records on query
12. Displays available date and time for solemnization
13. Books a slot for solemnization
14. Enrols the applicants for optional services during solemnization
15. Captures photographs of couple
16. Generates MIS
17. Generates Acknowledgement of receipt of certificates

Process Triggers

1. Application by applicants in case of hindu marriage
2. Notice of intended marriage in case of special marriages
3. Data/ Information requirements
4. Age proof (Optional only for Hindu Marriage)

5. Proof of residence or place of marriage (marriage Invitation card) (Optional only for Hindu Marriage)
6. Application in prescribed form for Marriage Registration
7. Declaration by the Bride and Groom (in case of Special Marriage)
8. Memorandum of Marriages containing details of bride, groom and witnesses

Key Performance Indicators

1. Number of channels for service access
2. Waiting time for citizens
3. Cost of service access by citizen
4. Cost of service delivery by department

Interfaces and Purpose

System	Information Received	Information Sent
Marriage registration system	Marriage Application Marriage Objections	Query for marriage records and data, Search Results
Marriage registers	Marriage Certificate	

Designed Forms and Registers

1. Form for application of marriage registration
2. Form for filing notice of intended marriage
3. Form for requesting duplicate copies
4. Declaration Forms
5. Certificate of Marriage

MIS Reports

1. Marriages registered under various categories
2. Marriages registered in various SRO's
3. Marriages registered date wise
4. Revenue generated on various days in various SRO's
5. Marriage applications coming through various channels
6. Information services through various channels
7. Rejected applications in various SRO's
8. Any other if required

Roles, Hierarchy and Responsibilities

1. MO: Verifies and Approves/Rejects applications; Puts Seal and Signs on certificates

2. FDA/SDA: Checks completeness of application and documents and then enters Application in the system; Prints approved certificates; Delivers Certificate and updates the system

31.3 Types of Marriage

Type of Marriage	Hindu Marriage	Special Marriage (Intended Notice)	Special Marriage of Other Forms
1. Religion of Bride & Bridegroom	Both of them should be hindus	Of religion other than hindus	Of religion other than hindus
2. When to Apply	Post-marriage	Pre-marriage	Post-marriage
3. Age (years)	18 for Bride, 21 for Bridegroom	18 for Bride, 21 for Bridegroom	21 for both
4. Notice Period	Not applicable	30 days allowable for any objections to be raised	30 days allowable for any objections to be raised
5. Objection	Not applicable	Applicable	Applicable
6. Objection Period	Not applicable	Ruling has to be given by SR within 30 days from the objection being raised	Ruling has to be given by SR within 30 days from the objection being raised
7. Oath & Solemnisation by SR	Not applicable	Applicable	Not applicable
8. No. of Payments	1	2	2
9. Photo upload by Applicant	Joint photo of Bride & Bridegroom	Individual photos of intended Bride & Bridegroom	Joint photo of Bride & Bridegroom
10. No. of Witnesses	3	3	3
11. No. of Objectors	Not applicable	≥ 0	≥ 0
12. Location of Marriage	Not applicable	Either at SRO or outside SRO	Not applicable
13. Selection of SRO	SRO falling within the limits of the place of marriage, permanent address of bridegroom and permanent address of bride	SRO falling within the limits of the permanent address of bridegroom, permanent address of bride and current address of the applicant	SRO falling within the limits of the place of marriage, permanent address of bridegroom, permanent address of bride and current address of the applicant
14. Marriage Code	HM	SM	OM
15. Photo capture by FDA/SDA	Not Applicable	Not Applicable	Not Applicable
16. Physical Presence of Bridegroom & Bride to submit Marriage Notice Form	Not Applicable	Have to personally appear and submit the Signed Application Form of Notice at SRO, BEFORE Sub-Registrar ONLY (as per the Rule Book)	Have to personally appear and submit the Signed Application Form of Notice at SRO, BEFORE Sub-Registrar ONLY (as per the Rule Book)
17. Solemnisation Period	Not Applicable	Within 90 days	Not Applicable

31.3.1 Hindu Marriage

i. **Brief Description:**

The applicant chooses the 'Hindu Marriage' from among the three types of marriages if the following conditions are satisfied:

- If the applicants (both bride & bridegroom) are of hindu religion, and
- Marriage has already occurred (post-marriage)

ii. **Process Flow:**




Figure 1: Registration of Hindu Marriage (Page 1)

7. The applicant shall select '**Hindu Marriage**' from among the 3 options (mandatory field)

(Note: The applicant shall choose the 'Hindu Marriage' from among the three options if the following conditions are satisfied:

- i. If the applicants (both bride & bridegroom) are hindu and
- ii. Marriage has already taken place (post-marriage))

8. The system requests the applicant to fill in the following entry fields (in general):

9. The applicant has to fill the following entry fields for **Marriage Details**:

- a. Date of Marriage (signifies the date on which the marriage took place) (mandatory field)
- b. Address of Marriage Venue (Place of Marriage) - House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- c. **Joint Photo** of the Bridegroom and Bride (upload) (mandatory field)

(Note: 1. B2 size (500mm*707 mm) Joint photo of the bridegroom and the bride should be in **jpg format**; size shouldn't exceed 2 MB; 2. The uploaded Joint photo of the bridegroom and the bride shall be manually verified by the SR/MO/ FDA/SDA before proceeding for the payment and booking appointment and also physically during the day of appointment at SRO)

10. The applicant has to fill the following entry fields for **Bridegroom Details**:

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 21 years for bridegroom) (mandatory field)

(Note: 1. The age of the bridegroom must be greater than or equal to 21 years; 2. The age must be rounded off to the lower whole number ie., if the age is 21.3 years, then then system should take 21 years only; if the age is 21.9 years, then then system should take 21 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3. If the applicant doesn't know his DoB, then the applicant must enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section))

- e. Mobile Number (mandatory field)
- f. Email ID (mandatory field)
- g. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

- h. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Status of Marriage (at the time of marriage) – Unmarried/ Divorcee/ Widow(er) (mandatory field)
(Note: 1. If any one of Divorcee/Widow is chosen, it should say 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Document' screen) ie., for Unmarried – no need to upload any document; for Divorcee – certificate of divorce from the court; for Widow(er) – widow(er)/death certificate of spouse)
- j. Father's Details – Salutation, First Name, Middle Name, Last Name
- k. Mother's Details - Salutation, First Name, Middle Name, Last Name

11. The applicant has to fill the following entry fields for **Bride Details**:

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18 years for bridegroom) (mandatory field)
(Note: The age of the bridegroom must be greater than or equal to 18 years; 2. The age must be rounded off to the lower whole number ie., if the age is 18.3 years, then then system should take 18 years only; if the age is 18.9 years, then then system should take 18 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3. If the applicant doesn't know his DoB, then the applicant must enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section))
- e. Mobile Number (mandatory field)
- f. Email ID (mandatory field)
- g. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

- h. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Status of Marriage at the time of marriage – Unmarried/ Divorcee/ Widow (mandatory field)
(Note: If any one of Divorcee/Widow is chosen, a pop up message (dialogue box)(flash message) should appear which says 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Document' screen) ie., for Unmarried – no need to upload any document; for Divorcee – divorce certificate; for Widow(er) – widow(er)/death certificate of spouse)
- j. Father's Details – Salutation, First Name, Middle Name, Last Name
- k. Mother's Details - Salutation, First Name, Middle Name, Last Name

12. The applicant has to fill the following entry fields for **Witnesses Details:**

(Note: 3 witnesses are mandatory)

Witness 1

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=18) (mandatory field)
- e. Mobile Number (mandatory field)
- f. Email ID (optional field)
- g. Current Place of Residence (Current Address) (mandatory field)
- h. Permanent Place of Residence (Permanent Address) (mandatory field)
(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Whether related to bride or bridegroom; also specify the relation (as others) (mandatory field)

Witness 2

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18) (mandatory field)
- e. Mobile Number (mandatory field)
- f. Email ID (optional field)
- g. Current Place of Residence (Current Address) (mandatory field)
- h. Permanent Place of Residence (Permanent Address) (mandatory field)
(Note: A 'Checkbox' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Whether related to bride or bridegroom; also specify the relation (as others) (mandatory field)

Witness 3

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18) (mandatory field)
- e. Mobile Number (mandatory field)
- f. Email ID (optional field)
- g. Current Place of Residence (Current Address) (mandatory field)
- h. Permanent Place of Residence (Permanent Address) (mandatory field)
(Note: A 'Checkbox' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Whether related to bride or bridegroom; also specify the relation (as others) (mandatory field)

(Note: 1. The age of the witnesses must be greater than or equal to 18 years;
2. **3 witnesses are mandatory** for every marriage application)

SRO Selection

13. The applicant shall select the SRO as mentioned in step 14
14. The applicant selects the jurisdictional SRO (Marriage Office) by selecting the required SRO from the dropdown menu
 - a. **Select SRO:** the applicant shall select the SRO from the dropdown list
 - b. **The Option in the dropdown menu are:**
 - i. SRO falling within Address (Place) of Marriage
 - ii. SRO falling within Permanent Address of Bridegroom
 - iii. SRO falling within Permanent Address of Bride

Generation of Application Summary and Forms I & I-A

15. The applicant after filling up the application form, the **Application Summary** is shown by the system
16. The applicant shall enter the **Number of Additional Copies** (of the Final Marriage Registration Certificate) if required
(Note: For each additional copy of marriage registration certificate, Rs.10 per copy will be charged; which gets reflected in the Display of Fee Structure page)
17. The applicant either Accepts the '**Declaration**' and clicks on '**View Form I and Form I-A**'; or the '**Edit**' option to make any changes to the application
18. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the marriage details screen (Keep all previously filled data)
19. When clicked on '**View Form I and Form I-A**', the Form I (marriage application) & I-A (memorandum of marriage) shall be auto-fetched in the below said format (which should be auto-fetched from the data entry captured earlier) to the applicant by the system

Form I

(See Rule : 4)

MEMORANDUM OF MARRIAGE

(B2 size)
(500mm *707 mm)
(Joint photo of bride and bridegroom)

Joint photo of the bride and bridegroom

(To be attested by bride and bridegroom)

1. Date of Marriage	
2. Place of Marriage (with sufficient particulars to locate the place):	
3. (a) Full name of the bridegroom	
(b) Name of the Father	
(c) Name of the Mother	
(d) His age	
(e) Usual place of residence	
(f) Address	
(g) Status of the bridegroom at the time of Marriage. Whether unmarried/ widower/ divorced:	
(h) Signature of the bridegroom, with date:	
4. (a) Full name of the bride	
(b) Name of the Father	
(c) Name of the Mother	
(d) Her age	
(e) Usual place of residence	
(f) Address	
(g) Status of the bride at the time of Marriage. Whether unmarried / widow / divorced:	
(h) Signature of the bride, with date:	

5. (a) Full name of witness: (Specify the Blood relation if any with bride or bridegroom)	
(b) His / her age	
(c) Usual place of residence	
(d) Address	
(e) Signature of the witness with date:	
6. (a) Full name of witness: (Specify the Blood relation if any with bride or bridegroom)	
(b) His / her age	
(c) Usual place of residence	
(d) Address	
(e) Signature of the witness with date:	
7. (a) Full name of witness: (Specify the Blood relation if any with bride or bridegroom)	
(b) His / her age	
(c) Usual place of residence	
(d) Address	
(e) Signature of the witness with date:	

(Note: Marriage Application Form (ie., Memorandum of Marriage) (Form I))

(Note: Usual place of residence = Current Address; Address = Permanent Address)

FORM I-A

(See rule 4(2))

Application for filling of Marriage Memorandum

To:

The Registrar of Marriage,

Under Hindu Marriage Act,

.....(say, **SRO Rajajinagar**)

Sir,

Marriage in accordance with the provisions of Hindu Marriage Act, 1955 (Act No.25 of 1955) has been solemnized between us, the undersigned parties on 12-7-2000 and we request that the following particulars of our marriage be entered in the Hindu Marriages Register.

We hereby declare,

(I) That a valid marriage was solemnized between us and that the marriage is, capable of being registered under section 8 of the marriage is, capable of being registered under section 8 of the Hindu Marriage Act, 1955 (Central Act 25 of 1955)

(II) That the conditions laid down in section 5 of the said Act have been satisfied and

(III) That the particulars given in application are true to the best of our knowledge and belief.

Signature

1) Husband (Name)

2) Wife (Name)

(Note: Declaration of Memorandum (ie., Application for filing of Marriage Memorandum) signed by bride and bridegroom (Form I-A))

Print of Form I & I-A, and Affix of Signatures

20. The applicant shall take the Print of the filled application forms of Forms I & I-A by clicking on the '**Print**' option
(Note: 1. The details entered by the applicant gets auto-filled in proforma 1 and 1A and these 2 filled application have to get printed when 'Print' button is pressed)
21. The bride, bridegroom and 3 witnesses will authenticate through their **Signatures** along with date on the printed Forms I and I-A (wherever required)

Scan & Upload of Signed Application Form(s) & Annexures/Enclosures by the Applicant

22. The applicant shall **Scan and Upload** the below mentioned documents:
- i. Signed Form I - Marriage Application Form (ie., Memorandum of Marriage)
 - ii. Signed Form I-A - Declaration of Memorandum (ie., Application for filing of Marriage Memorandum) signed by bride and bridegroom
 - iii. For Bridegroom
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (optional) (if mentioned earlier while filling the Bridegroom details) (dropdown menu) (mandatory filed)
 - iv. For Bride
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (optional) (if mentioned earlier while filling the Bride details) (dropdown menu) (mandatory filed)
 - v. For Marriage
 - a. Marriage Proof (dropdown menu) (mandatory filed)

(Note: List of permitted documents for **Age proof**:

- 1. Birth Certificate
- 2. School Leaving Certificate (SSLC)
- 3. School Cumulative Record
- 4. Doctor Certificate with Affidavit
- 5. Others

List of permitted documents for **ID proof**:

- 1. Employee ID
- 2. Ration Card
- 3. Driving License
- 4. Passport
- 5. PAN
- 6. Bank Passbook
- 7. Voter ID (EPIC Card)

8. Aadhar Card

List of permitted documents for **Address proof**:

1. Employee ID
2. Ration Card
3. Driving License
4. Passport
5. Bank Passbook
6. Voter ID (EPIC Card)
7. Aadhar Card

List of permitted documents for **Marriage proof**:

1. Wedding Invitation Card
2. Temple Marriage Receipt
3. Choultry/Marriage Hall/Kalyana Mantapa Receipt
4. Others (relevant document only)

(Note: 1. All the uploaded documents should be in pdf format and their size shouldn't exceed 5 MB for each document (except for Divorce Certificate which can run for pages as it is a court order); 2. Scanning Fee is calculated for All the documents uploaded (including Enclosures); 3. System should Auto-calculate number of pages for All the documents uploaded)

Display of Fee Structure

23. The system Calculates the Fee and shall display on the screen:

- a. Application Fee = Rs.5 (fixed)
- b. Marriage Certificate Fee = Rs.20 (fixed)
- c. Scanning Fee = Rs.35 (per page of scanning)
(Note: Shall show the Names of the Forms and Annexures that need to be scanned)
- d. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
- e. Total Payable Amount = Rs..... (= a + b + c + d)

(Note: At this stage, the system has to just show the calculation of (breakup of) the fee and the applicant doesn't make any payment; at a later stage, after verification and approval of data entered by the applicant by FDA/SDA/SR/RoM only, the applicant has to make the payment; the breakup fee calculation is being shown to ensure that the applicant has to be kept informed about the fee he/she is supposed to pay (transparency))

Submission of Application Form

24. The applicant clicks on '**Submit**' button to submit the application online. The applicant will get an application number generated as acknowledgement and receives an email/sms as notification

25. On submission of application, a dialogue box/ flash message should appear stating 'Your application has been successfully submitted'

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0; the application gets logged in in order in the SR login)

Steps taken by SR/RoM at SR Office to Register Marriage and to secure Marriage Certificate to the Applicant(s)

SR/RoM Login and Allocation/Verification by SR/RoM

26. The Sub Registrar (SR)/ Registrar of Marriage (RoM) shall login to the Kaveri 2.0 system

27. From the menu on his dashboard, the SR/RoM shall click on '**Marriage Application**'

28. The SR/RoM receives the marriage applications irrespective of their types in one place. Table is supposed to be FIFO

29. The SR/RoM can take the following actions:

- a. **View** - The SR/RoM views the firm application by clicking on '**View**' button, and then allocates to FDA/SDA/Self

- b. **Allocate** – The SR/RoM can allocate the firm application to FDA/SDA/Self by clicking on '**Allocate**' button

(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/RoM has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

(Note: If the SR/RoM allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Verify**' and NOT '**Allocate**'. In this case, there are NO FDA/SDA Remarks on the UI. The SR/RoM himself/herself verifies (the application and enclosures) and sends back to the applicant by clicking on '**Send to Applicant**' button)

FDA/SDA Login and Verification by the FDA/SDA

30. The FDA/SDA shall login

31. All the applications regardless of their type that the SR/RoM allocates are supposed to show on FDA/SDA dashboard. Table is supposed to be FIFO.

32. The FDA/SDA shall start the verification process by selecting '**Start Verification**' button

33. The FDA/SDA Application Verification screen is split into 2 sides:

- a. **LHS** (Left hand side of the page) – the Summary sheet containing all the details which the applicant has entered (marriage details, bridegroom details, bride details, witness details, fee details), a section to add his Remarks and a button to send it back to the SR/RoM

- b. **RHS** (Right hand side of the page) – contains the Uploads by the applicant which are Form I and 1-A and the Enclosures/Annexures
34. The FDA/SDA shall crosscheck the applications and the enclosures thoroughly; FDA/SDA fills a **Checklist mentioning Remarks** for each category – marriage details, bridegroom details, bride details, witnesses' details, uploaded documents; sends it back to the SR/RoM with Remarks by clicking on '**Send back to SR**' button

Verification & Approval by the SR/RoM

35. After the application is received from FDS/SDA, the SR/RoM shall login and shall view the remarks made by FDA/SDA by clicking on '**View**' (to view the remarks) and shall add his/her own remarks and shall send it back to the applicant for either to attend to the remarks made and resend the application (in the applicant login, 'Your application cannot be registered as it is, Kindly Refer to the Sub Registrar Remarks to know more' message shall be displayed) or to proceed to 'Make Payment'
36. The SR/RoM has **additional checkbox** which if ticked, then it takes the applicant to '**Make Payment**' option; ifn't ticked will request the applicant to make changes (as per remarks made by SR/RoM) in the application and re-submit the application (Note: 1. When the changes (attend to SR/RoM remarks) are requested by the SR/RoM to the applicant, the system takes the applicant to the 'Marriage Details' screen with the pre-filled data being retained as earlier over which he can over-write to make changes and then shall send back to the SR/RoM by pressing the 'Submit' button; 2. If the applicant wants to change the type of marriage, then he/she has to re-apply)
37. On the Remarks section, there is a checklist - If the checkbox in the checklist is ticked, the remarks are voluntary; ifn't ticked, then the remarks are mandatory (Note: 1. In either case, the applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0; 3. Until unless '**Can Proceed to Make Payment**' is checked, the applicant can't proceed to make the payment)

(Note: 1. If the applicant is willing to attend to the remarks made by SR/RoM, then resend the application after corrections are made. If not willing to attend to the remarks made by SR/RoM, then the system shall generate the Endorsement with Reason for Rejection; 2. Based on the remarks made by the FDA/SDA, the SR/RoM has the option to change (make modification) to the number of pages to be scanned)

Payment of Fee by the Applicant

38. After SR/RoM accepts and approves the application, the applicant shall login in the Kaveri 2.0 portal and make the Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button

(Note: The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' option)

- a. Application Fee = Rs.5 (fixed)
- b. Marriage Certificate Fee = Rs.20 (fixed)
- c. Scanning Fee = Rs.35 (per page of scanning)
(Note: Shall show the Names of the Forms and Annexures that need to be scanned)
- d. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
- e. Total Payable Amount = Rs..... (= a + b + c + d)

- 39. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
- 40. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
- 41. The applicant can choose '**Print Challan**', '**Go to Home**' or '**Book Appointment**'.
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login) on Kaveri2.0)

Scheduling an Appointment with the SR/MO by the Applicant

- 42. Once payment is being made, the applicant shall Schedule an Appointment (date & time) with the SR/RoM by clicking on '**Schedule Appointment**' button
- 43. The applicant shall select the Date and Time
- 44. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the office 15 minutes early for a smooth registration experience'
- 45. The screen displays the applicant's date, time and venue; and two buttons:
 - a. Cancel Appointment and
 - b. Re-schedule Appointment
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0)

Marriage Registration at SRO on the Day of Appointment

On the day of appointment, the **Applicants (bridegroom, bride) along with witnesses** shall appear before SR/RoM and shall present the physical application forms and memorandum of declaration

Allocation & Approval by SR/RoM for Registration

46. The SR/RoM shall login to the Kaveri 2.0 system
47. From the menu on his dashboard, the SR/RoM shall click on '**Marriage Application**'
48. The SR/RoM shall click on '**Marriage Appointment**' button
(Note: All the marriage appointments irrespective of their types for the day are listed in a table)
49. The SR/RoM can take the following actions:
 - a. **Allocate** – the SR/RoM can allocate the firm appointments to FDA/SDA/Self by clicking on '**Allocate**' button so that they can verify, capture/edit the required details and generate the necessary forms/documents needed for registration
(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/RoM has the option allocate to a particular FDA/SDA of his choice from the dropdown list)
 - b. **Approve** – after the FDA/SDA has generated the required forms, they are sent to the SR/RoM for approval; The SR/RoM shall approve by clicking on the '**Approve**' button and only after his/her approval, the marriage registration number shall be generated by the system and shall be sent back to the FDA/SDA for further processing
(Note: Generally, the SR/RoM shall allocate to FDA/SDA to verify, capture/edit the required details and generate the necessary forms/documents needed for registration. But in an **extra-ordinary situation where there are NO FDA/SDAs** (either absent on that particular day or permanently position is absent), the SR/RoM allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Start Registration**' and NOT '**Allocate**'. Then the SR/RoM himself/herself verifies, captures/edits the required details and generates the necessary forms/documents and shall approve the application in the system by clicking on the '**Check & Register**' button)

Steps taken by the FDA/SDA to Process the Marriage Registration Certificate

50. The marriage appointments allocated to the FDA/SDA by the SR/RoM have to be displayed on the FDA/SDA dashboard. The table shall be in FIFO
51. The FDA/SDA shall click on the '**Start Registration**' button
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0)

52. The FDA/SDA shall **Review the Physical Documents, Application Summary** and if everything is in order
53. The FDA/SDA shall Capture/Modify/Edit the basic details of the 3 Witnesses (ifn't captured earlier or if change is required)
(Note: 1. The age of the witnesses should be ≥ 18 years; 2. Capture the details of 3 witnesses at the beginning (ie., during filling up the application form of notice); but later SDA/FDA should be given an 'Edit Option' to change the witness details keeping in mind the exigencies (death, cancellation, busy schedule, not showing up on the particular day, etc.))
(Note: In the case where the FDA/SDA edits the witness(es)' details, then the marriage application form (Form 1) (if any & if required) has to be printed again and signatures of the bridegroom, bride and 3 witnesses have to be taken again)
54. The FDA/SDA Screen displays the following:
- a. **Application Details** – Application Number, Date of Submission, Application (Marriage) Type, Date of Marriage (whichever is applicable)
 - b. **Marriage Details** – Date and Place (Address) of Marriage
 - c. **Applicant Details** – Bridegroom Details, Bride Details, Witness Details
 - d. A '**Generate Certificate and Forms**' button to generate the required forms – the details of the applicants have to be auto-fetched in the set format to generate the required forms
- (Note: Marriage registration number isn't generated yet)
(Note: Required Forms – Marriage Registration Certificate (without Registration Number, Fee Payment Receipt)
(Note: Here, the SDA/FDA has to be given an **edit option** to edit the details (if and wherever required))
55. The FDA/SDA shall **Generate the Summary Report** by clicking the '**Generate Certificate and Forms**' button
56. The FDA/SDA shall send it (above mentioned certificate and forms) to the SR/RoM for Approval (Check & Register) by clicking on '**Send back to SR/RoM**' button
57. The SR/RoM shall view the certificate and forms generated by the FDA/SDA, and shall approve the application in the system by clicking on the '**Check & Register**' button
58. The system generates Marriage Registration Certificate with Registration Number
(Note: pop up message should appear once he clicks on '**Check and Register**' saying that 'Are you sure to Register? You cannot change later' for which the SR/RoM has to confirm)
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))
59. In the back end, the Index of Marriage are stored in **Index Register** (Forms V & VI for wife and husband separately)

60. After **Approval by SR/RoM**, the firm registration certificate is pushed back to the FDA/SDA dashboard
61. The FDA/SDA shall click on the '**Print Certificate and Forms**' button to **Print** the Marriage Certificate (with Registration Number) (and other forms wherever required) and shall get them signed by the applicants and the witnesses (if/wherever required)
62. The FDA/SDA shall **physically affix the colour joint-photo of the couple** and get the **cross-signatures of bridegroom and bride on the pasted joint photo** of the couple (as the joint photo of the couple isn't captured by the FDA/SDA)
63. The FDA/SDA shall get **Seal and Signature** affixed by the SR/RoM on the Marriage Certificate (with Registration Number) (and other forms wherever required)
64. The FDA/SDA shall click on the '**Upload**' button
65. The FDA/SDA upload screen shall display the following:
 - a. **Details:** Application Number, Application Type, Date of Marriage
 - b. **Scan and Preview buttons:** to scan and preview Certificate & Forms, Annexures/Enclosures
 - c. '**Save and Send back to SR/RoM**' button
66. The FDA/SDA shall **Scan and Preview** (by clicking the '**Scan**' and '**Preview**' buttons respectively) the following documents:
 - a. Marriage Application Form (ie., Memorandum of Marriage) (Form I)
 - b. Declaration of Memorandum (ie., Application for filing of Marriage Memorandum) signed by bride and bridegroom (Form I-A)
 - c. Form II (Endorsement – having received memorandum of marriage by SRO and having registered in the system)
 - d. Form II-A Signed Marriage Certificate (ie., Certificate of Registration of Hindu Marriage)
 - e. Form III (Certificate Affixed to Memorandum – to be sent to RGoM)
 - f. Enclosures/Annexures
67. The FDA/SDA shall click on the '**Save and Send back to SR/RoM**' button and shall forward it to the SR
68. The SR shall view the documents uploaded by FDA/SDA, then shall click on '**Digital Sign & Complete**' button to put his digital signature, encrypt and to upload all the saved documents
(Note: pop up message should appear once he clicks on '**Digital Sign & Complete**' button saying that 'Are you sure to digitally sign and upload? Once uploaded, the details cannot be changed' for which the SR/RoM has to confirm)
(Note: An option may be provided for the SR/RoM if re-scan is required; on clicking on the '**Send for Re-scan**' button by SR/RoM, it would request the SDA/FDA to re-scan and send it back to SR/RoM; and then SR/RoM shall view the scanned documents and shall proceed further by clicking on the '**Digital Sign & Complete**' button)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))

69. Any **Additional Payment** by the applicant(s)/objector(s) is made through Cash; the applicant(s)/objector(s) receives an Acknowledgement (a copy of Fee Receipt has to be generated by the FDA/SDA on receipt of cash)
70. The scanned documents are sent to RGoM (Registrar General of Marriage)
71. The **Marriage Registration Certificate** is handed over physically to the applicant after receiving the acknowledgement and the applicant shall collect the Marriage Certificate
72. The **Sakala** is updated

(Note: 1. If applied for **CC (Certified Copy)** for Marriage Certificate, then **Digitally/Physically Signed Copy** from SR/RoM may be issued by filling appropriate form; 2. In case any changes to be done to the Registration of Marriage due to erroneous data entry, the same shall be done in the system with approval from SR)

FORM II

[Karnataka Rule 4 (4) under Hindu Marriage Act, 1955]

Endorsement to be made on the reverse of the memorandum and duplicate

The memorandum was received by me on19 and this memorandum is filed at Serial No..... on page..... of volumeof the Register of Marriage maintained under the Hindu Marriage Act, 1955 (25 of 1955).
Date.....

(Signature)
Registrar of Marriage

1. Inserted by Registration of Hindu Marriages (Karnataka) (Amendment) Rules, 1999 w.e.f. 8-6-2000

(Note: Form II (Endorsement – having received memorandum of marriage by SRO, stored in SRO and having registered in the system))

(Note: Binding Book – serial no., page no., volume will be mentioned)



GOVERNMENT OF KARNATAKA
FORM II-A
(See rule 4(5))
CERTIFICATE OF REGISTRATION OF MARRIAGE
(Under the Hindu Marriage Act, 1955)
(Central Act, XXV of 1955)

(B2 size)
(500mm * 707 mm)
(Joint photo of bride and bridegroom)

This is to certify that Smt.....
D/o..... and Sri
S/o. have furnished the particulars in memorandum declaring that
their marriage has been solemnised on and that the same has been
registered this dayof200.....

Station:	Registrar of Marriage,
Marriage Number:	Seal
Date:	

(Note: Form II-A Signed Marriage Certificate (ie., Certificate of Registration of Hindu Marriage))

FORM III
[Karnataka Rule 5(1) under Hindu Marriage Act, 1955]
Certificate affixed to memorandum

Certified that the above which contains Sl. No..... to Sl No..... are duplicate copies of all the Memoranda filed in the Register maintained by me under the Hindu Marriage Act, 1955 (25 of 1955) during the month of19

Dated theday of19

Registrar of Marriage.

1. Inserted by Registration of Hindu Marriages (Karnataka) (Amendment) Rules, 1999 w.e.f. 8-6-2000

(Note: Form III (Certificate Affixed to Memorandum – to be sent to RGoM))

(Note: Form III – to be sent to RGoM on 5th of every month)

Form IV
Index of Register
(See Rule 5(2) and Rule 6)
Index No. I
HUSBAND

Name of Husband	Place of Residence	Name of Wife	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Ram		Asha				YPR-HM11- 2022-23 6-Apr-2022
Shyam		Usha				
Bhim		Nisha				

Form V
Index of Register
(See Rule 5(2) and Rule 6)
Index No. II
WIFE

Name of Wife	Place of Residence	Name of Husband	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Asha		Ram				YPR-HM11- 2022-23 6-Apr-2022
Usha		Shyam				
Nisha		Bhim				

(Note: Form V & VI - Index of Register Forms – wife & husband wise separately)

31.3.2 Special Marriage (Intended Marriage Notice)

i. Brief Description:

The applicant chooses the 'Special Marriage (Intended Marriage Notice)' from among the three options if the following conditions are satisfied:

- a. If the applicant/s (bride &/or bridegroom) are of different religion (other than hindu religion) or combination of hindu with other religion, and
- b. Marriage hasn't happened yet (pre-marriage)

ii. Process Flow:




Figure 3: Registration of Special Marriage (Intended Marriage Notice) (Page 1)




Figure 4: Registration of Special Marriage (Intended Marriage Notice) (Page 2)

iii. Functional Step by Step Process:

Steps taken by Citizen/ Applicant to file a Marriage Registration Online

Applicant Login

1. To file the application online, the applicant shall browse for **Kaveri Online Services** i.e., Kaveri2.0
2. The applicant shall register as a user by creating user id and password
3. The applicant shall now login in the Kaveri2.0 portal
4. The applicant shall click on **'Start a New Application'**
5. The applicant shall click on **'Marriage Registration'** on the screen
6. The applicant shall select the **'Type of Marriage'**
(Note: The applicant shall select among the three types of marriage options as per the requirement (satisfying certain conditions). The following types of marriage options are available to the applicant:

- i. Hindu Marriage,
 - ii. Special Marriage (Intended Marriage Notice) and
 - iii. Special Marriage of Other Forms
7. The applicant shall select '**Special Marriage (Intended Marriage Notice)**' from among the 3 options (mandatory field)

(Note: The applicant shall choose the 'Special Marriage (Intended Marriage Notice)' from among the three options if the following conditions are satisfied:

- i. If the applicant/s (bride &/or bridegroom) are of different religion (other than hindu religion) or combination of hindu with other religion, and
 - ii. Marriage is yet to happened (pre-marriage)
8. The system requests the applicant to fill in the following entry fields (in general):
9. The applicant has to fill the following entry fields for **Marriage Details**:
- a. Whether the Applicant is Bridegroom or Bride? (Radio button) (mandatory field)
 - b. Date of Marriage (signifies the date on which the marriage took place) – NOT APPLICABLE as the marriage hasn't yet happened
 - c. Address of Marriage Venue (Place of Marriage) - House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields) – NOT APPLICABLE as the marriage hasn't yet happened
 - d. Photo of the Bridegroom (upload) (mandatory field)
 - e. Photo of the Bride (upload) (mandatory field)

(Note: 1. Passport size (51mm*51mm) photos of the bridegroom and the bride should be in **jpg format**; size shouldn't exceed 2 MB; 2. The uploaded photos of the bridegroom and the bride shall be manually verified by the SR/MO/ FDA/SDA before proceeding for the payment and booking appointment and also physically during the day of appointment at SRO)

10. The applicant has to fill the following entry fields for **Bridegroom Details**:
- a. Salutation (mandatory field)
 - b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Date of Birth (DoB) (optional field)
 - d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=21 years for bridegroom) (mandatory field)

(Note: 1. The age of the bridegroom must be greater than or equal to 21 years; 2. The age must be rounded off to the lower whole number ie., if the age is 21.3 years, then then system should take 21 years only; if the age is 21.9 years, then then system should take 21 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3. If the applicant doesn't know his DoB, then the applicant must

enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section)

- e. Occupation (mandatory field)
- f. Mobile Number (mandatory field)
- g. Email ID (mandatory field)
- h. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- i. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)

- j. Duration of Residence at Current Address (Length of Residence) (calendar) (in days/months/years) (mandatory field)
- k. Status of Marriage (at the time of marriage) – Unmarried/ Divorcee/ Widow(er) (mandatory field)

(Note: If any one of Divorcee/Widow is chosen, a pop up message (dialogue box)(flash message) should appear which says 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen) ie., for Unmarried – no need to upload any document; for Divorcee – divorce certificate; for Widow(er) – widow(er)/death certificate of spouse)

- l. Father's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)
- m. Mother's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)

11. The applicant has to fill the following entry fields for **Bride Details**:

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18 years for bridegroom) (mandatory field)

(Note: The age of the bridegroom must be greater than or equal to 18 years; 2. The age must be rounded off to the lower whole number ie., if the age is 18.3

years, then then system should take 18 years only; if the age is 18.9 years, then then system should take 18 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3. If the applicant doesn't know his DoB, then the applicant must enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section))

- e. Occupation (mandatory field)
- f. Mobile Number (mandatory field)
- g. Email ID (mandatory field)
- h. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- i. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)

- j. Duration of Residence at Current Address (Length of Residence) (calendar) (in days/months/years) (mandatory field)
- k. Status of Marriage at the time of marriage – Unmarried/ Divorcee/ Widow (mandatory field)

(Note: If any one of Divorcee/Widow is chosen, a pop up message (dialogue box)(flash message) should appear which says 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen) ie., for Unmarried – no need to upload any document; for Divorcee – divorce certificate; for Widow – widow/death certificate of spouse)

- n. Father's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)
- o. Mother's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)

12. The applicant has to fill the following entry fields for **Witnesses Details:**

(Note: 3 witnesses are mandatory)

Witness 1

- a. Salutation (mandatory field)

- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Date of Birth (DoB) (optional field)
 - d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=18) (mandatory field)
 - e. Mobile Number (mandatory field)
 - l. Email ID (optional field)
 - f. Current Place of Residence (Current Address) (mandatory field)
 - g. Permanent Place of Residence (Permanent Address) (mandatory field)
- (Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- h. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

Witness 2

- a. Salutation (mandatory field)
 - b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Date of Birth (DoB) (optional field)
 - d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=18) (mandatory field)
 - e. Mobile Number (mandatory field)
 - m. Email ID (optional field)
 - f. Current Place of Residence (Current Address) (mandatory field)
 - g. Permanent Place of Residence (Permanent Address) (mandatory field)
- (Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- h. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

Witness 3

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=18) (mandatory field)
- e. Mobile Number (mandatory field)

- n. Email ID (optional field)
- f. Current Place of Residence (Current Address) (mandatory field)
- g. Permanent Place of Residence (Permanent Address) (mandatory field)
(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- h. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

(Note: Although the marriage hasn't yet happened, an option to capture the details of 3 witnesses must be provided at the beginning (ie., during filling up the application form of notice); but the SDA/FDA must be given with an 'Edit Option' to change the witnesses' details keeping in mind the objection period of 30 days (in case of exigencies (death, cancellation, busy schedule, etc.)) at a later date when the party along with witnesses are physically present at SRO during the appointment date and time)

SRO Selection

- 13. The applicant shall select the SRO as mentioned in step 14
- 14. The applicant selects the jurisdictional SRO (Marriage Office) by selecting the required SRO from the dropdown menu
 - a. **Select SRO:** the applicant shall select the SRO from the dropdown list
 - b. **The Option in the dropdown menu are:**
 - i. SRO falling within Permanent Address of Bridegroom
 - ii. SRO falling within Permanent Address of Bride
 - iii. SRO falling within Current Address of Applicant (ie., may be bridegroom or bride which is asked in the Marriage Details screen)

(Note: If the Applicant chooses SRO falling within the Current Address, then the condition that the applicant must have stayed for at least 30 days prior to the submission of the application applies and the applicant must produce (upload) the corresponding document supporting the same at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen)

Generation of Application Summary and Notice of Intended Marriage Form

- 15. The applicant after filling up the application form, the **Application Summary** is shown by the system
- 16. The applicant either Accepts the '**Declaration**' and clicks on '**View Application Form of Notice**'; or the '**Edit**' option to make any changes to the application

17. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the marriage details screen (Keep all previously filled data)
18. When clicked on '**View Application Form of Notice**', the Application Form of Notice (ie., the 2nd schedule ie., Notice of Intended Marriage Form) shall be auto-fetched in the below said format (which should be auto-fetched from the data entry captured earlier) to the applicant by the system

Application form of Notice for Special Marriage (Intended Marriage)

THE SECOND SCHEDULE

(See Section 5)

NOTICE OF INTENDED MARRIAGE

To,

The Marriage Officer ,District

We, hereby notify to your kind self that under the provision of Special Marriage Act, 1954, we both desire to get solemnized our marriage within three months from this notification submitted.

Bride
(Passport
size)

Bride
groom
(Passport
size)

Name	Status of marriage	Occupation	Age	Place of residence	Permanent address	Length of residence
Bridegroom	Unmarried Widower Divorcee					
Bride	Unmarried Widow Divorcee					

Witnessed this day of date month year

Signature of bridegroom

Signature of bride

Print of filled Application Form of Notice and Affix of Signatures

19. The applicant shall take the Print of the filled Application Form of Notice by clicking on the '**Print**' option
(Note: 1. The details entered by the applicant gets auto-filled in Notice of Intended Marriage Form and the filled application have to get printed when 'Print' button is pressed)
20. The bridegroom and the bride will authenticate through their **Signatures** along with date on the printed Application Form of Notice Form (wherever required)

Scan & Upload of Signed Application Form of Notice & Annexures/Enclosures by the Applicant

21. The applicant shall **Scan and Upload** the below mentioned documents:
 - i. Notice of Intended Marriage (Signed Application Form of Notice)
 - ii. For Bridegroom
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (mandatory, if mentioned earlier while filling the Bridegroom details)
 - iii. For Bride
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (mandatory, if mentioned earlier while filling the Bride details)
 - iv. For Marriage
 - a. Marriage Proof (dropdown menu) (NOT APPLICABLE as the marriage is yet to happen)

(Note: List of permitted documents for **Age proof**:

1. Birth Certificate
2. School Leaving Certificate (SSLC)
3. School Cumulative Record
4. Doctor Certificate with Affidavit
5. Others

List of permitted documents for **ID proof**:

1. Employee ID
2. Ration Card
3. Driving License
4. Passport
5. PAN

6. Bank Passbook
7. Voter ID (EPIC Card)
8. Aadhar Card

List of permitted documents for **Address proof**:

1. Employee ID
2. Ration Card
3. Driving License
4. Passport
5. Bank Passbook
6. Voter ID (EPIC Card)
7. Aadhar Card

List of permitted documents for **Marriage proof**: (NOT APPLICABLE as the marriage is yet to happen)

1. Wedding Invitation Card
2. Temple Marriage Receipt
3. Choultry/Marriage Hall/Kalyana Mantapa Receipt
4. Others (relevant document only)

(Note: 1. All the uploaded documents should be in pdf format and their size shouldn't exceed 5 MB for each document (except for Divorce Certificate which can run for pages as it is a court order); 2. Scanning Fee is calculated for All the documents uploaded (including Enclosures); 3. System should Auto-calculate number of pages for All the documents uploaded)

Display of Fee Structure of 1st Payment

22. The system displays the breakup of the Total Payable Fee:

- a. Application Form of Notice Fee (or just Notice Fee) = Rs.3
- b. Marriage Registration Fee = Rs.10 (fixed)
- c. Marriage Outside the Marriage Office Fee = Rs.15 (fixed) (if required)
- d. Scanning Fee = Rs.35 (per page of scanning)

(Note: Shall show the Names of the Forms and Annexures that need to be scanned)

- e. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
- f. Total Payable Amount = Rs..... (a + b + c + d + e)

(Note: At this stage, the system has to just show the calculation (breakup of the fee and the applicant doesn't make any payment; at a later stage, after verification and approval of data entered by the applicant by FDA/SDA/SR/MO only, the applicant has to make the payment; the fee calculation is being shown to ensure that the applicant has to be kept informed about the fee he/she is supposed to pay (transparency))

1st Payment of Fee by the Applicant

23. The system shall show the Calculation of Fee and shall display on the screen, for the applicant before making the payment:
- a. Application Form of Notice Fee = Rs.3 (fixed)
 - b. Total Payable Amount = Rs..... (=a) (freeze the fee)
- (Note: 1. The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' button; 2. At this stage, the system has to just show the application form of notice fee for which the applicant has to make payment before submitting the SR/MO; at a later stage, after verification and approval of data entered by the applicant by FDA/SDA/SR/MO and after the end of objection period (with NO objection being sustained) only, the applicant has to make the remaining payment)
24. The applicant makes the 1st Payment of Fee (Application Form of Notice Fee only) online to the SR/MO through K2 portal by clicking on '**Make Payment**' button
25. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
26. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
- (Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

Submission of Application Form of Notice

27. The applicant clicks on '**Submit**' button to submit the application online.
28. On submission of application form of notice, a dialogue box/ flash message should appear stating 'Your application has been successfully submitted'
29. The applicant will get an Application Number generated as Acknowledgement
- (Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant (and department) login/dashboard on Kaveri2.0; the application gets logged in in order in the SR login)
- (Note: Once the applicant submits the application and after the application being verified & approved by FDA/SDA/SR/MO, the '**URL and Barcode**' should be generated on the Application Form of Notice so that later, it would be helpful for the Objector to file an Objection on payment of Objection Fee)

Steps taken by SR/MO at SR Office to Register Marriage and to secure Marriage Certificate to the Applicant(s)

SR/MO Login and Allocation/Verification by SR/MO

30. Sub Registrar (SR)/ Marriage Officer (MO) shall login to the Kaveri 2.0 system
31. From the menu on his dashboard, the SR/MO shall click on '**Marriage Application**'
32. The SR/MO receives the marriage applications irrespective of their types in one place. Table is supposed to be FIFO
33. The SR/MO can take the following actions:
 - a. **View** - The SR/ MO views the firm application by clicking on '**View**' button, and then allocates to FDA/SDA/Self
 - b. **Allocate** – The SR/ MO can allocate the firm application to FDA/SDA/Self by clicking on '**Allocate**' button

(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/MO has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

(Note: If the SR/MO allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Verify**' and NOT '**Allocate**'. In this case, there are NO FDA/SDA Remarks on the UI. The SR/MO himself/herself verifies (the application and enclosures) and sends back to the applicant by clicking on '**Send to Applicant**' button)

FDA/SDA Login and Verification by the FDA/SDA

34. The FDA/SDA shall login
35. All the applications regardless of their type that the SR/MO allocates are supposed to show on FDA/SDA dashboard. Table is supposed to be FIFO.
36. The FDA/SDA shall start the verification process by selecting '**Start Verification**' button
37. The FDA/SDA Application Verification screen is split into 2 sides:
 - a. **LHS** (Left hand side of the page) – the Summary sheet containing all the details which the applicant has entered (marriage details, bridegroom details, bride details, witness details, fee details), a section to add his Remarks and a button to send it back to the SR/MO
 - b. **RHS** (Right hand side of the page) – contains the Uploads by the applicant which are Application Form and the Enclosures/Annexures
38. The FDA/SDA shall crosscheck the applications and the enclosures thoroughly; FDA/SDA fills a **checklist mentioning Remarks** for each category – marriage details, bridegroom details, bride details, witnesses' details, uploaded documents; sends it back to the SR/MO with Remarks by clicking on '**Send back to SR/MO**' button

Verification & Approval by the SR/MO

39. After the application is received from FDS/SDA, the SR/MO shall login and shall view the remarks made by FDA/SDA by clicking on '**View**' (to view the remarks) and shall add his/her own remarks and shall send it back to the applicant for either to attend to the remarks made and resend the application (in the applicant login, 'Your application cannot be registered as it is, Kindly Refer to the Sub Registrar Remarks to know more' message shall be displayed) or to proceed to '**Schedule an Appointment**' to physically handover the application form of notice to the SR/MO at SR Office (SRO)
40. The SR/MO has **additional checkbox** which if ticked, then it takes the applicant to make '**Schedule an Appointment**' option; ifn't ticked will request the applicant to make changes (as per remarks made by SR/MO) in the application and re-submit the application
(Note: 1. When the changes (attend to SR/MO remarks) are requested by the SR/MO to the applicant, the system takes the applicant to the 'Marriage Details' screen with the pre-filled data being retained as earlier over which he can over-write to make changes and then shall send back to the SR/MO by pressing the 'Submit' button; 2. If the applicant wants to change the type of marriage, then he/she has to re-apply)
41. On the Remarks section, there is a checklist - If the checkbox in the checklist is ticked, the remarks are voluntary; ifn't ticked, then the remarks are mandatory
(Note: 1. In either case, the applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0; 3. Until unless '**Schedule an Appointment**' is checked, the applicant can't proceed to book an appointment)
(Note: 1. If the applicant is willing to attend to the remarks made by SR/MO, then resend the application after corrections are made. If not willing to attend to the remarks made by SR/MO, then the system shall generate the Endorsement with Reason for Rejection; 2. Based on the remarks made by the FDA/SDA, the SR/MO has the option to change (make modification) to the number of pages to be scanned)

Scheduling 1st Appointment with the SR/MO by the Applicant

42. Once the application form of notice is approved by the SR/MO, the applicant shall Schedule an Appointment (date & time) with the SR/MO by clicking on '**Schedule Appointment**' button
43. The applicant shall select the Date and Time
44. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the SR office 15 minutes early for a smooth registration experience and physically handover the application form of notice to the SR/MO'

45. The screen displays the applicant's date, time and venue; and two buttons:

- a. Cancel Appointment and
- b. Re-schedule Appointment

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0)

Physical Submission of Application Form of Notice by the Applicant at SRO on the Day of 1st Appointment and the Acceptance of the same by SR/MO

46. On the day of appointment, the **Applicant (bridegroom and/or bride)** shall appear before SR/MO and shall physically handover the Application Form of Notice to the SR/MO

47. The SR/MO shall accept the Application Form of Notice submitted physical by the applicant

48. The SR/MO shall login to the Kaveri 2.0 system

49. From the menu on his dashboard, the SR/MO shall click on '**Accept Application Form of Notice**' button

(Note: The '**Accept Application Form of Notice**' button acts as a trigger button to (i) accept the application form of notice, and to (ii) send the notice to the **Concerned Jurisdictional SR/MOs**, in case the domicile of applicant(s) is other than the approached SR/MO)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

50. Once the SR/MO accepts the application, the applicant shall be directed to '**Can Proceed to Make Payment**' option.

51. The applicant can login in the Kaveri 2.0 portal and make the Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button **ONLY AFTER** the end of the 30 days (objection notice period), and in case (i) if no objection is filed or (ii) objection is over-ruled (Refer step 83)

Generation of URL/Barcode and Display of Notice

52. After the application being verified & approved by FDA/SDA/SR/MO, the '**URL and Barcode**' should be generated on the **Application Form of Notice** (so that it would be helpful for the Objector to file an Objection on payment of Objection Fee)

53. Once verified & approved by the SR/MO, the **Notice (with URL & Barcode)** is displayed on the **notice board** (by FDA/SDA) in the marriage office and website (if possible in the **IGR website**); and a copy of the notice is **also sent to the Concerned Jurisdictional SR/MOs** (the notice shall be displayed on these concerned jurisdictional SR/MOs' notice boards too), in case the domicile of applicant(s) is other than the approached SR/MO

(Note: 1. In either case, the applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

Filing of Objection by the Objector(s)

54. **Objections, if any shall be filed within 30 days**, from date of filing the notice considering processing time taken by K2 to generate payment confirmation receipt
55. In case someone wants to object to the marriage, then the objector (said person) shall use **URL/QR-Code** mentioned on the Notice (application form of notice)
56. A form shall be displayed with the following:
- i. Applicants' Name and Application Number
 - ii. Form: the objector shall fill in the following details:
 - a. Salutation, First Name, Middle Name, Last Name, Alias (only Salutation and First Name are mandatory fields)
 - b. Date of Birth and Age (in years) (only Age is mandatory field)
(Note: Age should auto-fetch once DoB is entered)
 - c. Mobile Number and Email ID (mandatory fields)
 - d. Occupation (optional field)
 - e. Address - House No./Building Name, Street Address, State, District, Taluka, Hobli, City/Village, Pincode (all are mandatory fields)
 - f. A textbox for Objection (mandatory field)
 - g. A section to Upload supporting documents (this may be a photo, document, video) (mandatory field)
 - iii. Proceed button
57. The objector after filling up the application form, the **Objection Application Summary** is shown by the system (mentioning i, ii, iii)

Display of Fee Structure of 1st Payment

58. The system displays the breakup of the Total Payable Fee:
- a. Marriage Objection Fee = Rs.2 (fixed)
 - b. Enquiry Fee = Rs.50 (fixed)
 - c. Fee for issuing Summons to the Witnesses to be paid by Objector = Rs.0.50 (for each witness) (if required, at a later point of time)
 - d. Total Payable Amount = Rs..... (a + b + c)
(Note: The breakup of fee calculation is being shown to ensure that the objector has to be kept informed about the fee he/she is supposed to pay (transparency purpose))

1st Payment of Fee by the Objector

59. The system shall show the Calculation of Fee and shall display on the screen, for the objector before making the payment:
 - a. Marriage Objection Fee = Rs.2 (fixed)
 - b. Enquiry Fee = Rs.50 (fixed)
 - c. Total Payable Amount = Rs..... (= a + b)
60. The system shall show the Calculation of Fee and shall display on the screen, for the applicant before making the payment:
61. The Objector has the option to either '**Edit**' or '**Proceed to Payment**' option
62. The Objector should make Payment of Objection Fee (Total Payable Amount) online to the SR/MO through K2 portal by clicking on '**Make Payment**' button
63. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
64. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
65. The objection is pushed to the concerned SR/MO and the objector receives an Email/SMS from the system ie., On submission of application, a dialogue box/ flash message should appear stating 'Your Objection has been successfully submitted'
(Note: 1. The objector receives an email/sms as notification; 2. The objection application gets logged in in order in the SR login; 3. Also, the status gets updated in the applicant (and department) login after SR review and if objection is sustained; 4. In case of many objectors, each objector has to make Individual Payment (Total Payable Amount) **separately** ie., if there are 3 objectors, each of them have to make the payment separately after filling the objection form & before submission to SR/MO)

SR Receives & Reviews the Objection

66. The objection is received from the objector on the SR's login ie., the marriage application screen
67. The objection has to be resolved by the SR/MO within 30 days of date of receiving the objection
68. The SR reviews the objection; SR has the option to either '**Reject**' or '**Start Enquiry**'
69. The SR/MO checks if the objection is valid
70. If **objection is valid**, then SR/MO shall start an Enquiry
71. Both the applicants & the objector(s) receive an Email/SMS (notification) from the system that objection has been raised by the objector (mentioning objector details) citing the reasons for objection
72. The SR/MO shall **Schedule a Date and Time** and shall **Generate Form I Notice**
(Note: The Form I Notice generated has to be sent to the Applicants and Objector(s) through Post & Email/SMS calling for all the concerned parties (the Applicants, Objector(s) and their Witness(es)) to be present for the Enquiry)
73. If **objection is not valid**, then shall follow step 83

(Note: The applicants & objector(s) receive an email/sms as notification; also the status gets updated in the applicant login)

(Note: After the end of the 30 days (objection notice period), and in case (i) if no objection is filed or (ii) objection is over-ruled, then the SR/MO shall approve the application and the applicant receives an email/sms as notification and can proceed to make payment option

Form I

See. Rule 6 (4)

Notice

(Place)

Before the Marriage Officer in the matter of the special Marriage Act 1954.

In the matter of the intended Marriage between.

between : Application to register the Marriage

AB

and

CD (Give names and Address)

and

EF

OBJECTOR

To.....

whereas notice of an Intended marriage an application for the registration of the marriage between AB and CD was received by the Marriage Officer on.....

Whereas EF has preferred certain objections (Setout overleaf) to the Solemnization of the marriage; whereas the Marriage Officer registration.

Will hold an enquiry into the matter of the said objections on day of19..... A.M./P.M on the said day together with all documents on which you rely and any witness or witnesses whom you may desire to be examined on your behalf.

Take notice that in default of your appearance on the aforesaid day, the inquiry will be made and decided in your absence.

(Set-Out the objections on the reverse of this notice) should you apprehend that your witness will not attend unless summoned by the Marriage Officer, you should apply to the Marriage Officer for the issue of such summons sufficiently early together with the prescribed process fee and the reasonable expense of travelling and subsistence allowance of the witness.

Given under my hand and seal

Station :

Date :

Signature

Marriage Officer (Seal)

(Note: this form is sent by SR to the bridegroom & bride)

SR Issues Notice/Summons and Conducts Enquiry

74. If objection is valid, then **SR/MO shall Schedule a Date and Time for an Enquiry** and shall **Generate Form I Notice**
(Note: The Form I Notice generated has to be sent to the Applicants and Objector(s) through Post & Email/SMS calling for all the concerned parties (the Applicants, Objector(s) and their Witness(es)) to be present for the Enquiry)
75. On the scheduled date and time summoned by the SR/MO, in the presence of both Applicants & Objector(s), the **SR/MO Conducts an Enquiry**
76. Both the Applicants & the Objector(s) are given an opportunity to put forth their defence
77. '**Appointment for Enquiry**' is on the marriage appointment screen
78. He clicks on '**Start Enquiry**' button
79. The screen displays the following:
- Objection Number
 - Objector Name
 - Applicant Number
 - Applicant Name
 - Two Textboxes – one for each of the Depositions (Objector(s) & Applicants)
 - One Textbox for SR Order
 - Two buttons – Over-rule Objection, Sustain Objection
 - An option to Print (and download) Enquiry Order
80. If the witnesses won't turn up on the scheduled date and time summoned by the SR/MO or if the party/objector(s) request for official summons to be issued by the SR/MO for the witness(es) to be present for the enquiry, then the SR/MO issues summons to the required/requested witness(es) (see Form II – Summons to Witness(es))
81. On request, the SR/MO can issue summons to witness(es) from either/both party and objector side; 3. The party/objector should first make a payment i.e., **Fee for issuing Summons to the Witnesses to be paid by Objector = Rs.0.50 (for each witness)** through K2 and should inform the SR/MO, then only the SR/MO will **Issue Summons** to the witness(es) and schedules for another date and time calling them for an Enquiry; for this enquiry (2nd sitting), no official form I notice will be sent again to the applicants and the objector(s)
82. After the enquiry, the SR/MO writes the **Inquiry Results (Inquiry Order/ Speaking Order)** based on the merits and Records Inquiry Results & Scans the Order. The SR/MO can either Over-rule or Sustain the objection
- If the objection is sustained, then the marriage application can't be registered; the marriage shall not be solemnized, **Refusal Order (Inquiry Results)** shall be printed by FDA/SDA and given to the parties.
(Note: 1. The marriage applications status in the system to be changed to 'Objection Raised and Sustained' with an option to view the 'Inquiry Order')

- b. If the objection is over-ruled, then the marriage application is unaffected; then step 83 shall be followed

(Note: 1. The applicant & objector receive an email/sms as notification; also status gets updated in the applicant login; 2. Both the applicants and the objector(s) receive a scanned copy of the Inquiry Order via email (downloadable form) and/or post and/or physically handed over just after the enquiry)

(Note: After the end of the 30 days (objection notice period), and in case no objections are filed, the applicants along with 3 witnesses shall appear before the SR/MO for solemnization of their marriage within the next 2 calendar months (Total period shall not exceed 3 calendar months from the date of filing of notice))

- 83. After **the end of the 30 days (objection notice period)**, and in case **no objections are filed** or in case the **objection is over-ruled (ie., not sustained)**, then the SR/MO shall approve the application and the applicant receives an email/sms as notification and can proceed to make payment option

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login) on Kaveri2.0)

Form II
(see. Rule 6(4))
Summons to Witness

Before the Marriage Officer (place) in the matter of the Special Marriage Act, 1954, and in the matter of the intended Marriage between/application to register the Marriage between :

AB

CD (Give names and addresses)

and

EF objector

To

whereas your attendance is required to give evidence on behalf of in the above matter, you are hereby required to appear personally before me or to cause to be produced before me the document specified hereunder on the day of19 A.M/P.M. A sum of Rs. being your travelling and other expenses for one day is herewith sent.

If you fail to comply with this summons without lawful>

Take notice that in default of your appearance on the aforesaid day, the inquiry will be made and decided in your absence.

Given under my hand and seal.

Station :

(Seal) Marriage Officer.

Date :

2nd Payment of Fee by the Applicant

84. The applicant shall enter the **Number of Additional Copies** (of the Final Marriage Registration Certificate) if required. Hence an option must be provided for the same (Note: For each additional copy of marriage registration certificate, Rs.10 per copy will be charged; which gets reflected in the Display of Fee Structure page)
85. After SR/MO accepts and approves the application, the applicant logs in the Kaveri 2.0 portal and makes the 2nd Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button
(Note: The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' option)
- a. Marriage Registration Fee = Rs.10 (fixed)
 - b. Marriage Outside the Marriage Office Fee = Rs.15 (fixed) (optional)
 - c. Scanning Fee = Rs.35 (per page of scanning)
(Note: Shall show the Names of the Forms and Annexures that need to be scanned)
 - d. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
 - e. Total Payable Amount = Rs..... (= a + b + c + d)
- (Note: If '**Marriage Outside the Marriage Office Fee**' is chosen (if checked in the checkbox), then Location of Marriage (as requested by the parties) has to be mentioned). Hence an option must be provided for the same)
86. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
87. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login on Kaveri2.0)
88. The applicant can choose '**Print Challan**', '**Go to Home**' or '**Book Appointment**'.

Scheduling 2nd Appointment with the SR/MO by the Applicant

89. Once payment is being made, the applicant shall Schedule an Appointment (for Oath & Solemnisation) with the SR/MO by clicking on '**Schedule Appointment**' button
90. The applicant shall select the Date and Time
91. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the office 15 minutes early for a smooth registration experience'
92. The screen displays the applicant's date, time and venue; and two buttons:
- a. Cancel Appointment and
 - b. Re-schedule Appointment

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant (department) login on Kaveri2.0)

Steps taken by SRO (SR/MO) to Register Marriage and to secure Marriage Certificate to the Applicant(s)

On the day of appointment, the **Applicants (bridegroom, bride) along with witnesses** shall appear before SR/MO and shall present the physical application forms and memorandum of declaration

Oath & Solemnisation of Marriage by SR/MO

93. The parties (bridegroom, bride) along with 3 witnesses shall appear before SR/MO and shall get the marriage Solemnized as per the prescribed procedures:

- a. SR/MO will seek to confirm that the applicants are about to enter into a marriage on their own free will,
- b. Applicants will take the Solemn and Binding Marriage Oaths,
- c. The Marriage Oath is signed by bride, bridegroom and counter-signed by SR/MO, and
- d. The Marriage Declaration Document is signed by bride, bridegroom, 3 witnesses and counter-signed by SR/MO

(Note: The venue can either at SR Office (SRO) or at any other place (outside SRO) as requested by the applicant/parties by paying an additional charge (ie., **fee for marriage outside the marriage office = Rs.15**). The SR has the option either to accept or reject to visit the venue requested (any place outside SRO) based on his/her availability; if SR accepts (obliges), then the SR/MO would visit that venue to solemnise the marriage (the applicant has to arrange for transportation from and back to SRO office); if SR rejects to visit that venue, then the parties along with witnesses have to personally visit that SRO only on the given date and time of appointment)

Allocation & Approval by SR/MO for Registration

94. The SR/MO shall login to the Kaveri 2.0 system

95. From the menu on his dashboard, the SR/MO shall click on '**Marriage Application**'

96. The SR/MO shall click on '**Marriage Appointment**' button

(Note: All the marriage appointments irrespective of their types for the day are listed in a table)

97. The SR/MO can take the following actions:

- a. **Allocate** – the SR/MO can allocate the firm appointments to FDA/SDA/Self by clicking on '**Allocate**' button so that they can verify, capture/edit the required details and generate the necessary forms/documents needed for registration

(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/MO has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

- b. **Approve** – after the FDA/SDA has generated the required forms, they are sent to the SR/MO for approval; The SR/MO shall approve by clicking on the '**Approve**' button and only after his/her approval, the marriage registration number shall be generated by the system and shall be sent back to the FDA/SDA for further processing

(Note: Generally, the SR/MO shall allocate to FDA/SDA to verify, capture/edit the required details and generate the necessary forms/documents needed for registration. But in an **extra-ordinary situation where there are NO FDA/SDAs** (either absent on that particular day or permanently position is absent), the SR/MO allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Start Registration**' and NOT 'Allocate'. Then the SR/MO himself/herself verifies, captures/edits the required details and generates the necessary forms/documents and shall approve the application in the system by clicking on the '**Check & Register**' button)

Steps taken by the FDA/SDA to Process the Marriage Registration Certificate

98. The marriage appointments allocated to the FDA/SDA by the SR/MO have to be displayed on the FDA/SDA dashboard. The table shall be in FIFO
99. The FDA/SDA shall click on the '**Start Registration**' button
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login on Kaveri2.0)
100. The FDA/SDA shall **Review the Physical Documents, Application Summary** and if everything is in order
101. The FDA/SDA shall Capture/Modify/Edit the basic details of the 3 Witnesses (ifn't captured earlier or if change is required)
(Note: 1. The age of the witnesses should be ≥ 18 years; 2. Capture the details of 3 witnesses at the beginning (ie., during filling up the application form of notice); but later SDA/FDA should be given an 'Edit Option' to change the witness details keeping in mind the objection period of 30 days (in case of exigencies (death, cancellation, busy schedule, not showing up on the particular day, etc.))
(Note: In the case where the FDA/SDA edits the witness(es)' details, then the marriage application form (if any & if required) has to be printed again and signatures of the bridegroom, bride and 3 witnesses have to be taken again)
102. The FDA/SDA Screen displays the following:
 - a. **Application Details** – Application Number, Date of Submission, Application (Marriage) Type, Date of Marriage (whichever is applicable)
 - b. **Marriage Details** – Date and Place (Address) of Marriage
 - c. **Applicant Details** – Bridegroom Details, Bride Details, Witness Details
 - d. A '**Generate Certificate and Forms**' button to generate the required forms – the details of the applicants have to be auto-fetched in the set format to generate the required forms
(Note: Marriage registration number isn't generated yet)
(Note: Required Forms – Marriage Registration Certificate (without Registration Number, Fee Payment Receipt)
(Note: Here, the SDA/FDA has to be given an **edit option** to edit the details (if and wherever required))
103. The FDA/SDA shall **Generate the Summary Report** by clicking the '**Generate Certificate and Forms**' button
104. The FDA/SDA shall send it (above mentioned form) to the SR/MO for approval (check & register) by clicking on '**Send back to SR/MO**' button
105. The SR/MO shall view the certificate and forms generated by the FDA/SDA, and shall approve the application in the system by clicking on the '**Check & Register**' button
106. The system generates Marriage Registration Certificate with Registration Number

(Note: pop up message should appear once he clicks on '**Check and Register**' saying that 'Are you sure to Register? You cannot change later' for which the SR/MO confirm)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))

107. In the back end, the Index of Marriage are stored in **Index Register** (Forms V & VI for wife and husband separately)
108. After **Approval by SR/MO**, the firm registration certificate is pushed back to the FDA/SDA dashboard
109. After approval, the FDA/SDA shall click on the '**Print Certificate and Forms**' button to **Print** the Marriage Certificate (with Registration Number) (and other forms wherever required) and shall get them signed by the applicants and the witnesses (if/wherever required)
110. The FDA/SDA shall **physically affix the colour joint-photo of the couple** if required and get the **cross-signatures of bridegroom and bride on the pasted joint photo** of the couple (as the joint photo of the couple isn't captured by the FDA/SDA)
111. The FDA/SDA shall get **Seal and Signature** affixed by the SR/MO on the Marriage Certificate (with Registration Number) (and other forms wherever required)
112. The FDA/SDA shall click on the '**Upload**' button
113. The FDA/SDA upload screen shall display the following:
 - d. **Details:** Application Number, Application Type, Date of Marriage
 - e. **Scan and Preview buttons:** to scan and preview Certificate & Forms, Annexures/Enclosures
 - f. '**Save and Send back to SR/MO**' button
114. The FDA/SDA shall **Scan and Preview** (by clicking the '**Scan**' and '**Preview**' buttons respectively) the following documents:
 - a. Application Form of Notice
 - b. Declaration & Oath
 - c. Signed Marriage Certificate
 - d. Enclosures/Annexures
115. The FDA/SDA shall click on the '**Save and Send back to SR/MO**' button and shall forward it to the SR
116. The SR shall view the documents uploaded by FDA/SDA, then shall click on '**Digital Sign & Complete**' button to put his digital signature, encrypt and to upload all the saved documents

(Note: pop up message should appear once he clicks on '**Digital Sign & Complete**' button saying that 'Are you sure to digitally sign and upload? Once uploaded, the details cannot be changed' for which the SR/MO has to confirm)

(Note: An option may be provided for the SR/MO if re-scan is required; on clicking on the '**Send for Re-scan**' button by SR/MO, it would request the SDA/FDA to re-

scan and send it back to SR/MO; and then SR/MO shall view the scanned documents and shall proceed further by clicking on the '**Digital Sign & Complete**' button)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))

117. Any **Additional Payment** by the applicant(s)/objector(s) is made through Cash; the applicant(s)/objector(s) receives an Acknowledgement (a copy of Fee Receipt has to be generated by the FDA/SDA on receipt of cash)
118. The scanned documents are sent to RGoM (Registrar General of Marriage)
119. The **Marriage Registration Certificate** is handed over physically to the applicant after receiving the acknowledgement and the applicant shall collect the Marriage Certificate
120. The **Sakala** is updated

(Note: 1. If applied for **CC (Certified Copy)** for Marriage Certificate, then **Digitally/Physically Signed Copy** from SR/MO may be issued by filling appropriate form; 2. In case any changes to be done to the Registration of Marriage due to erroneous data entry, the same shall be done in the system with approval from SR)

THE THIRD SCHEDULE
(See Section 11)
DECLARATION TO BE MADE BY THE BRIDEGROOM

I, A.B., hereby declare as follow :-

1. I am at the present time unmarried (or a widower or a divorcee, as the case may be).
2. I have completed..... years of age.
3. I am not related to C.D. (the bride) within the degrees of prohibited relationship.
4. I am aware that, if any statement in this declaration is false, and if in making such statement I either know or believe it to be false or do not believe it to be true, I am liable to imprisonment and also to fine.

(Signature)
A.B.(the Bridegroom)

DECLARATION TO BE MADE BY THE BRIDE

I, C.D., hereby declare as follows :-

1. I am at the present time unmarried (or a widow or a divorcee, as the case may be)
2. I have completed.....years of age.
3. I am not related to A.B. (the bridegroom) within the degrees of prohibited relationship
4. I am aware that, if any statement in this declaration is false, and if in making such statement I either know or believe it to be false or do not believe it to be true, I am liable to imprisonment and also to fine.

(Signature)
C.D. (the Bride).

Signed in our presence by the above-named A.B. and C.D. so far as we are aware there is no lawful>

(Signature)
G.H.

(Signature)
I.J.

(Signature)
K.L.
Three witnesses.

Countersigned E.F.,
Marriage Officer.

Dated the day of 20.....



THE FOURTH SCHEDULE

(See section 13)

CERTIFICATE OF MARRIAGE

(B2 size)

(500mm *707 mm)

(Joint photo of bride and
bridegroom)

I, E.F., hereby certify that on the day of 20.....,
A.B. and C.D. * appeared before me and that each of them, in my presence and in
the presence of three witnesses who have signed hereunder, made the
declarations required by section 11 and that a marriage under this Act was
solemnized between them in my presence.

(Signature) E.F.,
Marriage Officer for

(Signature) A.B.,
Bridegroom

(Signature) C.D.,
Bride

(Signature)
G.H.

(Signature)
I.J.

(Signature)
K.L.
Three witnesses

Dated theday of 20.....

* Herein give particulars of the parties

Form IV

Index of Register

(See Rule 5(2) and Rule 6)

Index No. I

HUSBAND

Name of Husband	Place of Residence	Name of Wife	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Ram		Asha				YPR-HM11-2022-23 6-Apr-2022
Shyam		Usha				
Bhim		Nisha				

Form V

Index of Register

(See Rule 5(2) and Rule 6)

Index No. II

WIFE

Name of Wife	Place of Residence	Name of Husband	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Asha		Ram				YPR-HM11-2022-23 6-Apr-2022
Usha		Shyam				
Nisha		Bhim				

(Note: Form V & VI - Index of Register Forms – wife & husband wise separately)

31.3.3 Special Marriage of Other Forms

iv. Brief Description:

The applicant chooses the 'Special Marriage of Other Forms' from among the three options if the following conditions are satisfied:

- If the applicant/s (bride &/or bridegroom) are of different religion (other than hindu religion) or combination of hindu with other religion, and
- Marriage has already occurred (post-marriage)

v. Process Flow:




Figure 5: Registration of Special Marriage of Other Forms (Page 1)




Figure 6: Registration of Special Marriage of Other Forms (Page 2)

vi. Functional Step by Step Process:

Steps taken by Citizen/ Applicant to file a Marriage Registration Online

Applicant Login

1. To file the application online, the applicant shall browse for **Kaveri Online Services** i.e., Kaveri2.0
2. The applicant shall register as a user by creating user id and password
3. The applicant shall now login in the Kaveri2.0 portal
4. The applicant shall click on '**Start a New Application**'
5. The applicant shall click on '**Marriage Registration**' on the screen
6. The applicant shall select the '**Type of Marriage**'
(Note: The applicant shall select among the three types of marriage options as per the requirement (satisfying certain conditions). The following types of marriage options are available to the applicant:

- iv. Hindu Marriage,
 - v. Special Marriage (Intended Marriage Notice) and
 - vi. Special Marriage of Other Forms
7. The applicant shall select '**Special Marriage of Other Forms**' from among the 3 options (mandatory field)

(Note: The applicant shall choose the 'Special Marriage of Other Forms' from among the three options if the following conditions are satisfied:

- i. If the applicant/s (bride &/or bridegroom) are of different religion (other than hindus) or combination of hindu with other religion, and
- ii. Marriage is yet to happened (pre-marriage)

8. The system requests the applicant to fill in the following entry fields (in general):

9. The applicant has to fill the following entry fields for **Marriage Details**:

- a. Whether the Applicant is Bridegroom or Bride? (Radio button) (mandatory field)
- b. Date of Marriage (signifies the date on which the marriage took place)
- c. Address of Marriage Venue (Place of Marriage) - House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- a. **Joint Photo** of the Bridegroom and Bride (upload) (mandatory field)

(Note: 1. B2 size (500mm*707mm) Joint photo of the bridegroom and the bride should be in **jpg format**; size shouldn't exceed 2 MB; 2. The uploaded Joint photo of the bridegroom and the bride shall be manually verified by the SR/MO/FDA/SDA before proceeding for the payment and booking appointment and also physically during the day of appointment at SRO)

10. The applicant has to fill the following entry fields for **Bridegroom Details**:

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=21 years for bridegroom) (mandatory field)

(Note: 1. The age of the bridegroom must be greater than or equal to 21 years; 2. The age must be rounded off to the lower whole number ie., if the age is 21.3 years, then then system should take 21 years only; if the age is 21.9 years, then then system should take 21 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3. If the applicant doesn't know his DoB, then the applicant must enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section)

- e. Occupation (mandatory field)
- f. Mobile Number (mandatory field)
- g. Email ID (mandatory field)
- h. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- i. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)

- j. Duration of Residence at Current Address (Length of Residence) (calendar) (in days/months/years) (mandatory field)
- k. Status of Marriage (at the time of marriage) – Unmarried/ Divorcee/ Widow(er) (mandatory field)

(Note: If any one of Divorcee/Widow is chosen, a pop up message (dialogue box)(flash message) should appear which says 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen) ie., for Unmarried – no need to upload any document; for Divorcee – divorce certificate; for Widow(er) – widow(er)/death certificate of spouse)

- l. Father's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)
- m. Mother's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)

11. The applicant has to fill the following entry fields for **Bride Details**:

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18 years for bridegroom) (mandatory field)

(Note: 1. The age of the bridegroom must be greater than or equal to 21 years; 2. The age must be rounded off to the lower whole number ie., if the age is 21.3 years, then then system should take 21 years only; if the age is 21.9 years, then then system should take 21 years only ie., the system must always take the lower side value until it is a whole number; 2. If DoB is fed, then the age should auto-fetch; 3.

If the applicant doesn't know his DoB, then the applicant must enter the age directly and must get a Doctor Certificate with Affidavit (or Other Supporting Document) and upload it in the upload document section)

- e. Occupation (mandatory field)
- f. Mobile Number (mandatory field)
- g. Email ID (mandatory field)
- h. Current Place of Residence (Current Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- i. Permanent Place of Residence (Permanent Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)

- j. Duration of Residence at Current Address (Length of Residence) (calendar) (in days/months/years) (mandatory field)
- k. Status of Marriage at the time of marriage – Unmarried/ Divorcee/ Widow (mandatory field)

(Note: If any one of Divorcee/Widow is chosen, a pop up message (dialogue box)(flash message) should appear which says 'please upload the supporting document in the upload page' while uploading the other documents (then corresponding document supporting the same should be uploaded at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen) ie., for Unmarried – no need to upload any document; for Divorcee – divorce certificate; for Widow – widow/death certificate of spouse)

- l. Father's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)
- m. Mother's Details – Salutation, First Name, Middle Name, Last Name (Salutation and First Name are mandatory fields)

12. The applicant has to fill the following entry fields for **Witnesses Details:**

(Note: 3 witnesses are mandatory)

Witness 1

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age>=18) (mandatory field)

- e. Mobile Number (mandatory field)
 - f. Email ID (optional field)
 - g. Current Place of Residence (Current Address) (mandatory field)
 - h. Permanent Place of Residence (Permanent Address) (mandatory field)
- (Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

Witness 2

- a. Salutation (mandatory field)
 - b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Date of Birth (DoB) (optional field)
 - d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18) (mandatory field)
 - e. Mobile Number (mandatory field)
 - f. Email ID (optional field)
 - g. Current Place of Residence (Current Address) (mandatory field)
 - h. Permanent Place of Residence (Permanent Address) (mandatory field)
- (Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)
- i. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

Witness 3

- a. Salutation (mandatory field)
- b. First Name, Middle Name, Last Name (only First Name is mandatory field)
- c. Date of Birth (DoB) (optional field)
- d. Age (in years) (should auto-fetch once DoB is entered; system should register only if age $\geq$ 18) (mandatory field)
- e. Mobile Number (mandatory field)
- f. Email ID (optional field)
- g. Current Place of Residence (Current Address) (mandatory field)
- h. Permanent Place of Residence (Permanent Address) (mandatory field)

(Note: A '**Checkbox**' saying 'Permanent address is same as Current address' has to be given after Current Place of Residence (and before Permanent Place of Residence); if checked, then the same details as entered in the Current Place of Residence should be auto-filled in place of Permanent Place of Residence; ifn't checked, then the applicant has to manually entered the required details)

- i. Whether related to bride or bridegroom; also specify the relation (as others) (Radio button & dropdown; also have to manually enter the relation if 'Others' is chosen) (mandatory field)

(Note: Although the applicant has to fill in the details of 3 witnesses at the beginning (ie., during filling up the application form of notice); an option must be given for the SDA/FDA with an 'Edit Option' to change the witnesses' details keeping in mind the objection period of 30 days (in case of exigencies (death, cancellation, busy schedule, etc.)) at a later date when the party along with witnesses are physically present at SRO during the appointment date and time)

SRO Selection

13. The applicant shall select the SRO as mentioned in step 14
14. The applicant selects the jurisdictional SRO (Marriage Office) by selecting the required SRO from the dropdown menu
 - c. **Select SRO:** the applicant shall select the SRO from the dropdown list
 - d. **The Option in the dropdown menu are:**
 - i. SRO falling within Address (Place) of Marriage
 - ii. SRO falling within Permanent Address of Bridegroom
 - iii. SRO falling within Permanent Address of Bride
 - iv. SRO falling within Current Address of Applicant (ie., may be bridegroom or bride which is asked in the Marriage Details screen)

(Note: If the Applicant chooses SRO falling within the Current Address, then the condition that the applicant must have stayed for at least 30 days prior to the submission of the application applies and the applicant must produce (upload) the corresponding document supporting the same at a later stage while uploading the forms and enclosures in the 'Upload Documents' screen)

Generation of Application Summary and Notice of Intended Marriage Form

15. The applicant after filling up the application form, the **Application Summary** is shown by the system
16. The applicant either Accepts the '**Declaration**' and clicks on '**View Application Form of Notice**'; or the '**Edit**' option to make any changes to the application
17. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the marriage details screen (Keep all previously filled data)

18. When clicked on '**View Application Form of Notice**', the Application Form of Notice (Form III ie., Application form of Notice for Special Marriage of Other Forms) shall be auto-fetched in the below said format (which should be auto-fetched from the data entry captured earlier) to the applicant by the system

Application form of Notice for Special Marriage of Other Forms

Form III

(See. Rule 7 (1))

Application for Registration of a Marriage Under Sec. 15 of The Special Marriage Act, 1954 (Central Act 43 of 1954)

1. Name of the parties:

A.B (husband)

C.D (wife)

2. Age or date of Birth:

A.B (husband)

C.D (wife)

3. Permanent dwelling place, if any,

4. Present dwelling place

5. Relationship, if any, of parties before marriage (Unmarried/Divorced/Widow(er))

6. A ceremony of marriage was performed between AB and CD on atand AB declare that we have been living together as husband and wife ever since the date noted above

(B2 size)

(500mm *707 mm)

(Joint photo of bride and
bridegroom)

We hereby declare that:-

(i) Neither of us has more than one spouse living on the date mentioned in this application.

(ii) Neither of us, is an idiot or lunatic.

(iii) Both of us have completed the age of 21 years on the date of this application.

(iv) We are not within the degree of prohibited relationship; our marriage was celebrated before the commencement of the Special Marriage Act, 1954 (Central Act 43 of 1954) and according to law, custom or usage having the force of law, governing each of us, a marriage between us is permitted, though we are within the degrees of prohibited relationship according to the act as aforesaid.

NOTE : Score out whichever is not applicable.

(v) We have been residing within the jurisdiction ofMarriage Officer at for a period of not less than thirty days immediately preceding the date of this application.

We also declare that all the above particulars are true to the best of our knowledge and belief.

Station:

Date:

Signature: (A.B) Husband
(C.D) Wife

Print of filled Application Form of Notice and Affix of Signatures

19. The applicant shall take the Print of the filled Application Form of Notice by clicking on the '**Print**' option
(Note: 1. The details entered by the applicant gets auto-filled in Notice of Intended Marriage Form and the filled application have to get printed when 'Print' button is pressed)
20. The bridegroom and the bride will authenticate through their **Signatures** along with date on the printed Application Form of Notice Form (wherever required)

Scan & Upload of Signed Application Form of Notice & Annexures/Enclosures by the Applicant

21. The applicant shall **Scan and Upload** the below mentioned documents:
 - i. Notice of Intended Marriage (Signed Application Form of Notice)
 - ii. For Bridegroom
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (mandatory, if mentioned earlier while filling the Bridegroom details)
 - iii. For Bride
 - a. Identity proof (dropdown menu) (mandatory filed)
 - b. Age proof (dropdown menu) (mandatory filed)
 - c. Address proof (dropdown menu) (mandatory filed)
 - d. Proof of Divorcee/Widow (mandatory, if mentioned earlier while filling the Bride details)
 - iv. For Marriage
 - a. Marriage Proof (dropdown menu)

(Note: List of permitted documents for **Age proof**:

1. Birth Certificate
2. School Leaving Certificate (SSLC)
3. School Cumulative Record
4. Doctor Certificate with Affidavit
5. Others

List of permitted documents for **ID proof**:

1. Employee ID
2. Ration Card
3. Driving License
4. Passport
5. PAN
6. Bank Passbook

7. Voter ID (EPIC Card)
8. Aadhar Card

List of permitted documents for **Address proof**:

1. Employee ID
2. Ration Card
3. Driving License
4. Passport
5. Bank Passbook
6. Voter ID (EPIC Card)
7. Aadhar Card

List of permitted documents for **Marriage proof**: (NOT APPLICABLE as the marriage is yet to happen)

1. Wedding Invitation Card
2. Temple/Nosque/Church/etc. Marriage Receipt
3. Choultry/Marriage Hall/Kalyana Mantapa Receipt
4. Others (relevant document only)

(Note: 1. All the uploaded documents should be in pdf format and their size shouldn't exceed 5 MB for each document (except for Divorce Certificate which can run for pages as it is a court order); 2. Scanning Fee is calculated for All the documents uploaded (including Enclosures); 3. System should Auto-calculate number of pages for All the documents uploaded)

Display of Fee Structure of 1st Payment

22. The system displays the breakup of the Total Payable Fee:

- a. Application Form of Notice Fee (or just Notice Fee) = Rs.3
- b. Marriage Registration Fee = Rs.10 (fixed)
- c. Scanning Fee = Rs.35 (per page of scanning)
(Note: Shall show the Names of the Forms and Annexures that need to be scanned)
- d. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
- e. Total Payable Amount = Rs..... (a + b + c + d)

(Note: At this stage, the system has to just show the calculation (breakup of the fee and the applicant doesn't make any payment; at a later stage, after verification and approval of data entered by the applicant by FDA/SDA/SR/MO only, the applicant has to make the payment; the fee calculation is being shown to ensure that the applicant has to be kept informed about the fee he/she is supposed to pay (transparency))

1st Payment of Fee by the Applicant

23. The system shall show the Calculation of Fee and shall display on the screen, for the applicant before making the payment:

- a. Application Form of Notice Fee = Rs.3 (fixed)
- b. Total Payable Amount = Rs..... (=a) (freeze the fee)

(Note: 1. The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' button; 2. At this stage, the system has to just show the application form of notice fee for which the applicant has to make payment before submitting the SR/MO; at a later stage, after verification and approval of data entered by the applicant by FDA/SDA/SR/MO and after the end of objection period (with NO objection being sustained) only, the applicant has to make the remaining payment)

- 24. The applicant makes the 1st Payment of Fee (Application Form of Notice Fee only) online to the SR/MO through K2 portal by clicking on '**Make Payment**' button
 - 25. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
 - 26. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
- (Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

Submission of Application Form of Notice

- 27. The applicant clicks on '**Submit**' button to submit the application online.
 - 28. On submission of application form of notice, a dialogue box/ flash message should appear stating 'Your application has been successfully submitted'
 - 29. The applicant will get an Application Number generated as Acknowledgement
- (Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant (and department) login/dashboard on Kaveri2.0; the application gets logged in in order in the SR login)

(Note: Once the applicant submits the application and after the application being verified & approved by FDA/SDA/SR/MO, the '**URL and Barcode**' should be generated on the Application Form of Notice so that later, it would be helpful for the Objector to file an Objection on payment of Objection Fee)

Steps taken by SR/MO at SR Office to Register Marriage and to secure Marriage Certificate to the Applicant(s)

SR/MO Login and Allocation/Verification by SR/MO

30. Sub Registrar (SR)/ Marriage Officer (MO) shall login to the Kaveri 2.0 system
31. From the menu on his dashboard, the SR/MO shall click on '**Marriage Application**'
32. The SR/MO receives the marriage applications irrespective of their types in one place. Table is supposed to be FIFO
33. The SR/MO can take the following actions:
 - a. **View** - The SR/ MO views the firm application by clicking on '**View**' button, and then allocates to FDA/SDA/Self
 - b. **Allocate** – The SR/ MO can allocate the firm application to FDA/SDA/Self by clicking on '**Allocate**' button

(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/MO has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

(Note: If the SR/MO allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Verify**' and NOT '**Allocate**'. In this case, there are NO FDA/SDA Remarks on the UI. The SR/MO himself/herself verifies (the application and enclosures) and sends back to the applicant by clicking on '**Send to Applicant**' button)

FDA/SDA Login and Verification by the FDA/SDA

34. The FDA/SDA shall login
35. All the applications regardless of their type that the SR/MO allocates are supposed to show on FDA/SDA dashboard. Table is supposed to be FIFO.
36. The FDA/SDA shall start the verification process by selecting '**Start Verification**' button
37. The FDA/SDA Application Verification screen is split into 2 sides:
 - a. **LHS** (Left hand side of the page) – the Summary sheet containing all the details which the applicant has entered (marriage details, bridegroom details, bride details, witness details, fee details), a section to add his Remarks and a button to send it back to the SR/MO
 - b. **RHS** (Right hand side of the page) – contains the Uploads by the applicant which are Application Form and the Enclosures/Annexures
38. The FDA/SDA shall crosscheck the applications and the enclosures thoroughly; FDA/SDA fills a **checklist mentioning Remarks** for each category – marriage details, bridegroom details, bride details, witnesses' details, uploaded documents; sends it back to the SR/MO with Remarks by clicking on '**Send back to SR/MO**' button

Verification & Approval by the SR/MO

39. After the application is received from FDS/SDA, the SR/MO shall login and shall view the remarks made by FDA/SDA by clicking on '**View**' (to view the remarks) and shall add his/her own remarks and shall send it back to the applicant for either to attend to the remarks made and resend the application (in the applicant login, 'Your application cannot be registered as it is, Kindly Refer to the Sub Registrar Remarks to know more' message shall be displayed) or to proceed to '**Schedule an Appointment**' to physically handover the application form of notice to the SR/MO at SR Office (SRO)
40. The SR/MO has **additional checkbox** which if ticked, then it takes the applicant to make '**Schedule an Appointment**' option; ifn't ticked will request the applicant to make changes (as per remarks made by SR/MO) in the application and re-submit the application
(Note: 1. When the changes (attend to SR/MO remarks) are requested by the SR/MO to the applicant, the system takes the applicant to the 'Marriage Details' screen with the pre-filled data being retained as earlier over which he can over-write to make changes and then shall send back to the SR/MO by pressing the 'Submit' button; 2. If the applicant wants to change the type of marriage, then he/she has to re-apply)
41. On the Remarks section, there is a checklist - If the checkbox in the checklist is ticked, the remarks are voluntary; ifn't ticked, then the remarks are mandatory
(Note: 1. In either case, the applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0; 3. Until unless '**Schedule an Appointment**' is checked, the applicant can't proceed to book an appointment)
(Note: 1. If the applicant is willing to attend to the remarks made by SR/MO, then resend the application after corrections are made. If not willing to attend to the remarks made by SR/MO, then the system shall generate the Endorsement with Reason for Rejection; 2. Based on the remarks made by the FDA/SDA, the SR/MO has the option to change (make modification) to the number of pages to be scanned)

Scheduling 1st Appointment with the SR/MO by the Applicant

42. Once the application form of notice is approved by the SR/MO, the applicant shall Schedule an Appointment (date & time) with the SR/MO by clicking on '**Schedule Appointment**' button
43. The applicant shall select the Date and Time
44. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the SR office 15 minutes early for a smooth registration experience and physically handover the application form of notice to the SR/MO'

45. The screen displays the applicant's date, time and venue; and two buttons:

- c. Cancel Appointment and
- d. Re-schedule Appointment

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0)

Physical Submission of Application Form of Notice by the Applicant at SRO on the Day of 1st Appointment and the Acceptance of the same by SR/MO

46. On the day of appointment, the **Applicant (bridegroom and/or bride)** shall appear before SR/MO and shall physically handover the Application Form of Notice to the SR/MO

47. The SR/MO shall accept the Application Form of Notice submitted physical by the applicant

48. The SR/MO shall login to the Kaveri 2.0 system

49. From the menu on his dashboard, the SR/MO shall click on '**Accept Application Form of Notice**' button

(Note: The '**Accept Application Form of Notice**' button acts as a trigger button to (i) accept the application form of notice, and to (ii) send the notice to the **Concerned Jurisdictional SR/MOs**, in case the domicile of applicant(s) is other than the approached SR/MO)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

50. Once the SR/MO accepts the application, the applicant shall be directed to '**Can Proceed to Make Payment**' option.

51. The applicant can login in the Kaveri 2.0 portal and make the Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button **ONLY AFTER** the end of the 30 days (objection notice period), and in case (i) if no objection is filed or (ii) objection is over-ruled (Refer step 83)

Generation of URL/Barcode and Display of Notice

52. After the application being verified & approved by FDA/SDA/SR/MO, the '**URL and Barcode**' should be generated on the Application Form of Notice (so that it would be helpful for the Objector to file an Objection on payment of Objection Fee)

53. Once verified & approved by the SR/MO, the **Notice (with URL & Barcode)** is displayed on the **notice board** (by FDA/SDA) in the marriage office and website (if possible in the **IGR website**); and a copy of the notice is **also sent to the Concerned Jurisdictional SR/MOs** (the notice shall be displayed on these concerned jurisdictional SR/MOs' notice boards too), in case the domicile of applicant(s) is other than the approached SR/MO

(Note: 1. In either case, the applicant receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant (and department) login/dashboard on Kaveri2.0)

Filing of Objection by the Objector(s)

54. **Objections, if any shall be filed within 30 days**, from date of filing the notice considering processing time taken by K2 to generate payment confirmation receipt
55. In case someone wants to object to the marriage, then the objector (said person) shall use **URL/QR-Code** mentioned on the Notice (application form of notice)
56. A form shall be displayed with the following:
- iv. Applicants' Name and Application Number
 - v. Form: the objector shall fill in the following details:
 - a. Salutation, First Name, Middle Name, Last Name, Alias (only Salutation and First Name are mandatory fields)
 - b. Date of Birth and Age (in years) (only Age is mandatory field)
(Note: Age should auto-fetch once DoB is entered)
 - c. Mobile Number and Email ID (mandatory fields)
 - d. Occupation (optional field)
 - e. Address - House No./Building Name, Street Address, State, District, Taluka, Hobli, City/Village, Pincode (all are mandatory fields)
 - f. A textbox for Objection (mandatory field)
 - g. A section to Upload supporting documents (this may be a photo, document, video) (mandatory field)
 - vi. Proceed button
57. The objector after filling up the application form, the **Objection Application Summary** is shown by the system (mentioning i, ii, iii)

Display of Fee Structure of 1st Payment

58. The system displays the breakup of the Total Payable Fee:
- e. Marriage Objection Fee = Rs.2 (fixed)
 - f. Enquiry Fee = Rs.50 (fixed)
 - g. Fee for issuing Summons to the Witnesses to be paid by Objector = Rs.0.50 (for each witness) (if required, at a later point of time)
 - h. Total Payable Amount = Rs..... (a + b + c)
(Note: The breakup of fee calculation is being shown to ensure that the objector has to be kept informed about the fee he/she is supposed to pay (transparency purpose))

1st Payment of Fee by the Objector

59. The system shall show the Calculation of Fee and shall display on the screen, for the objector before making the payment:
- d. Marriage Objection Fee = Rs.2 (fixed)
 - e. Enquiry Fee = Rs.50 (fixed)
 - f. Total Payable Amount = Rs..... (= a + b)
60. The system shall show the Calculation of Fee and shall display on the screen, for the applicant before making the payment:
61. The Objector has the option to either '**Edit**' or '**Proceed to Payment**' option
62. The Objector should make Payment of Objection Fee (Total Payable Amount) online to the SR/MO through K2 portal by clicking on '**Make Payment**' button
63. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
64. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
65. The objection is pushed to the concerned SR/MO and the objector receives an Email/SMS from the system ie., On submission of application, a dialogue box/ flash message should appear stating 'Your Objection has been successfully submitted' (Note: 1. The objector receives an email/sms as notification; 2. The objection application gets logged in in order in the SR login; 3. Also, the status gets updated in the applicant (and department) login after SR review and if objection is sustained; 4. In case of many objectors, each objector has to make Individual Payment (Total Payable Amount) **separately** ie., if there are 3 objectors, each of them have to make the payment separately after filling the objection form & before submission to SR/MO)

SR Receives & Reviews the Objection

66. The objection is received from the objector on the SR's login ie., the marriage application screen
67. The objection has to be resolved by the SR/MO within 30 days of date of receiving the objection
68. The SR reviews the objection; SR has the option to either '**Reject**' or '**Start Enquiry**'
69. The SR/MO checks if the objection is valid
70. If **objection is valid**, then SR/MO shall start an Enquiry
71. Both the applicants & the objector(s) receive an Email/SMS (notification) from the system that objection has been raised by the objector (mentioning objector details) citing the reasons for objection
72. The SR/MO shall **Schedule a Date and Time** and shall **Generate Form I Notice** (Note: The Form I Notice generated has to be sent to the Applicants and Objector(s) through Post & Email/SMS calling for all the concerned parties (the Applicants, Objector(s) and their Witness(es)) to be present for the Enquiry)
73. If **objection is not valid**, then shall follow step 83

(Note: The applicants & objector(s) receive an email/sms as notification; also the status gets updated in the applicant login)

(Note: After the end of the 30 days (objection notice period), and in case (i) if no objection is filed or (ii) objection is over-ruled, then the SR/MO shall approve the application and the applicant receives an email/sms as notification and can proceed to make payment option

Form I
See. Rule 6 (4)
Notice

(Place)

Before the Marriage Officer in the matter of the special Marriage Act 1954.

In the matter of the intended Marriage between.

between : Application to register the Marriage

AB

and

CD (Give names and Address)

and

EF

OBJECTOR

To.....

whereas notice of an Intended marriage an application for the registration of the marriage between AB and CD was received by the Marriage Officer on.....

Whereas EF has preferred certain objections (Setout overleaf) to the Solemnization of the marriage; whereas the Marriage Officer registration.

Will hold an enquiry into the matter of the said objections on day of19..... A.M./P.M on the said day together with all documents on which you rely and any witness or witnesses whom you may desire to be examined on your behalf.

Take notice that in default of your appearance on the aforesaid day, the inquiry will be made and decided in your absence.

(Set-Out the objections on the reverse of this notice) should you apprehend that your witness will not attend unless summoned by the Marriage Officer, you should apply to the Marriage Officer for the issue of such summons sufficiently early together with the prescribed process fee and the reasonable expense of travelling and subsistence allowance of the witness.

Given under my hand and seal

Station :

Date :

Signature
Marriage Officer (Seal)

(Note: this form is sent by SR to the bridegroom & bride)

SR Issues Notice/Summons and Conducts Enquiry

74. If objection is valid, then **SR/MO shall Schedule a Date and Time for an Enquiry** and shall **Generate Form I Notice**
(Note: The Form I Notice generated has to be sent to the Applicants and Objector(s) through Post & Email/SMS calling for all the concerned parties (the Applicants, Objector(s) and their Witness(es)) to be present for the Enquiry)
75. On the scheduled date and time summoned by the SR/MO, in the presence of both Applicants & Objector(s), the **SR/MO Conducts an Enquiry**
76. Both the Applicants & the Objector(s) are given an opportunity to put forth their defence
77. **'Appointment for Enquiry'** is on the marriage appointment screen
78. He clicks on **'Start Enquiry'** button
79. The screen displays the following:
- i. Objection Number
 - j. Objector Name
 - k. Applicant Number
 - l. Applicant Name
 - m. Two Textboxes – one for each of the Depositions (Objector(s) & Applicants)
 - n. One Textbox for SR Order
 - o. Two buttons – Over-rule Objection, Sustain Objection
 - p. An option to Print (and download) Enquiry Order
80. If the witnesses won't turn up on the scheduled date and time summoned by the SR/MO or if the party/objector(s) request for official summons to be issued by the SR/MO for the witness(es) to be present for the enquiry, then the SR/MO issues summons to the required/requested witness(es) (see Form II – Summons to Witness(es))
81. On request, the SR/MO can issue summons to witness(es) from either/both party and objector side; 3. The party/objector should first make a payment i.e., **Fee for issuing Summons to the Witnesses to be paid by Objector = Rs.0.50 (for each witness)** through K2 and should inform the SR/MO, then only the SR/MO will **Issue Summons** to the witness(es) and schedules for another date and time calling them for an Enquiry; for this enquiry (2nd sitting), no official form I notice will be sent again to the applicants and the objector(s)
82. After the enquiry, the SR/MO writes the **Inquiry Results (Inquiry Order/ Speaking Order)** based on the merits and Records Inquiry Results & Scans the Order. The SR/MO can either Over-rule or Sustain the objection
- c. If the objection is sustained, then the marriage application can't be registered; the marriage shall not be solemnized, **Refusal Order (Inquiry Results)** shall be printed by FDA/SDA and given to the parties.
(Note: 1. The marriage applications status in the system to be changed to 'Objection Raised and Sustained' with an option to view the 'Inquiry Order')

- d. If the objection is over-ruled, then the marriage application is unaffected; then step 83 shall be followed

(Note: 1. The applicant & objector receive an email/sms as notification; also status gets updated in the applicant login; 2. Both the applicants and the objector(s) receive a scanned copy of the Inquiry Order via email (downloadable form) and/or post and/or physically handed over just after the enquiry)

(Note: After the end of the 30 days (objection notice period), and in case no objections are filed, the applicants along with 3 witnesses shall appear before the SR/MO for solemnization of their marriage (NO restrictions on marriage solemnization period of 90 days for registration of marriage as in case of special marriage (intended marriage notice) ie., Total period can exceed 3 calendar months from the date of filing of notice)

83. After **the end of the 30 days (objection notice period)**, and in case **no objections are filed** or in case the **objection is over-ruled (ie., not sustained)**, then the SR/MO shall approve the application and the applicant receives an email/sms as notification and can proceed to make payment option

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login) on Kaveri2.0)

Form II
(see. Rule 6(4))
Summons to Witness

Before the Marriage Officer (place) in the matter of the Special Marriage Act, 1954, and in the matter of the intended Marriage between/application to register the Marriage between :

AB

CD (Give names and addresses)

and

EF objector

To

whereas your attendance is required to give evidence on behalf of in the above matter, you are hereby required to appear personally before me or to cause to be produced before me the document specified hereunder on the day of19 A.M/P.M. A sum of Rs. being your travelling and other expenses for one day is herewith sent.

If you fail to comply with this summons without lawful>

Take notice that in default of your appearance on the aforesaid day, the inquiry will be made and decided in your absence.

Given under my hand and seal.

Station :

(Seal) Marriage Officer.

Date :

2nd Payment of Fee by the Applicant

84. The applicant shall enter the **Number of Additional Copies** (of the Final Marriage Registration Certificate) if required. Hence an option must be provided for the same (Note: For each additional copy of marriage registration certificate, Rs.10 per copy will be charged; which gets reflected in the Display of Fee Structure page)
85. After SR/MO accepts and approves the application, the applicant logs in the Kaveri 2.0 portal and makes the 2nd Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button
(Note: The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' option)
- f. Marriage Registration Fee = Rs.10 (fixed)
 - g. Scanning Fee = Rs.35 (per page of scanning)
(Note: Shall show the Names of the Forms and Annexures that need to be scanned)
 - h. No. of Additional Copies (of Marriage Registration Certificate) = Rs.10 (per copy)
 - i. Total Payable Amount = Rs..... (= a + b + c)
86. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment
87. On making the payment, a dialogue box/ flash message should appear stating 'Your payment has been successfully made'
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login on Kaveri2.0)
88. The applicant can choose '**Print Challan**', '**Go to Home**' or '**Book Appointment**'.

Scheduling 2nd Appointment with the SR/MO by the Applicant

89. Once payment is being made, the applicant shall Schedule an Appointment (for Oath & Solemnisation) with the SR/MO by clicking on '**Schedule Appointment**' button
90. The applicant shall select the Date and Time
91. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the office 15 minutes early for a smooth registration experience'
92. The screen displays the applicant's date, time and venue; and two buttons:
- c. Cancel Appointment and
 - d. Re-schedule Appointment
- (Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant (department) login on Kaveri2.0)

Steps taken by SRO (SR/MO) to Register Marriage and to secure Marriage Certificate to the Applicant(s)

On the day of appointment, the **Applicants (bridegroom, bride) along with witnesses** shall appear before SR/MO and shall present the physical application forms and memorandum of declaration

Allocation & Approval by SR/MO for Registration

93. The SR/MO shall login to the Kaveri 2.0 system

94. From the menu on his dashboard, the SR/MO shall click on '**Marriage Application**'

95. The SR/MO shall click on '**Marriage Appointment**' button

(Note: All the marriage appointments irrespective of their types for the day are listed in a table)

96. The SR/MO can take the following actions:

- c. **Allocate** – the SR/MO can allocate the firm appointments to FDA/SDA/Self by clicking on '**Allocate**' button so that they can verify, capture/edit the required details and generate the necessary forms/documents needed for registration

(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then SR/MO has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

- d. **Approve** – after the FDA/SDA has generated the required forms, they are sent to the SR/MO for approval; The SR/MO shall approve by clicking on the '**Approve**' button and only after his/her approval, the marriage registration number shall be generated by the system and shall be sent back to the FDA/SDA for further processing

(Note: Generally, the SR/MO shall allocate to FDA/SDA to verify, capture/edit the required details and generate the necessary forms/documents needed for registration. But in an **extra-ordinary situation where there are NO FDA/SDAs** (either absent on that particular day or permanently position is absent), the SR/MO allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Start Registration**' and NOT '**Allocate**'. Then the SR/MO himself/herself verifies, captures/edits the required details and generates the necessary forms/documents and shall approve the application in the system by clicking on the '**Check & Register**' button)

Steps taken by the FDA/SDA to Process the Marriage Registration Certificate

97. The marriage appointments allocated to the FDA/SDA by the SR/MO have to be displayed on the FDA/SDA dashboard. The table shall be in FIFO
98. The FDA/SDA shall click on the '**Start Registration**' button
(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login on Kaveri2.0)
99. The FDA/SDA shall **Review the Physical Documents, Application Summary** and if everything is in order
100. The FDA/SDA shall Capture/Modify/Edit the basic details of the 3 Witnesses (ifn't captured earlier or if change is required)
(Note: 1. The age of the witnesses should be ≥ 18 years; 2. Capture the details of 3 witnesses at the beginning (ie., during filling up the application form of notice); but later SDA/FDA should be given an 'Edit Option' to change the witness details keeping in mind the objection period of 30 days (in case of exigencies (death, cancellation, busy schedule, not showing up on the particular day, etc.))
(Note: In the case where the FDA/SDA edits the witness(es)' details, then the marriage application form (if any & if required) has to be printed again and signatures of the bridegroom, bride and 3 witnesses have to be taken again)
101. The FDA/SDA Screen displays the following:
 - e. **Application Details** – Application Number, Date of Submission, Application (Marriage) Type, Date of Marriage (whichever is applicable)
 - f. **Marriage Details** – Date and Place (Address) of Marriage
 - g. **Applicant Details** – Bridegroom Details, Bride Details, Witness Details
 - h. A '**Generate Certificate and Forms**' button to generate the required forms – the details of the applicants have to be auto-fetched in the set format to generate the required forms
(Note: Marriage registration number isn't generated yet)
(Note: Required Forms – Marriage Registration Certificate (without Registration Number, Fee Payment Receipt)
(Note: Here, the SDA/FDA has to be given an **edit option** to edit the details (if and wherever required))
102. The FDA/SDA shall **Generate the Summary Report** by clicking the '**Generate Certificate and Forms**' button
103. The FDA/SDA shall send it (above mentioned form) to the SR/MO for approval (check & register) by clicking on '**Send back to SR/MO**' button
104. The SR/MO shall view the certificate and forms generated by the FDA/SDA, and shall approve the application in the system by clicking on the '**Check & Register**' button
105. The system generates Marriage Registration Certificate with Registration Number

(Note: pop up message should appear once he clicks on '**Check and Register**' saying that 'Are you sure to Register? You cannot change later' for which the SR/MO confirm)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))

106. In the back end, the Index of Marriage are stored in **Index Register** (Forms V & VI for wife and husband separately)
107. After **Approval by SR/MO**, the firm registration certificate is pushed back to the FDA/SDA dashboard
108. After approval, the FDA/SDA shall click on the '**Print Certificate and Forms**' button to **Print** the Marriage Certificate (with Registration Number) (and other forms wherever required) and shall get them signed by the applicants and the witnesses (if/wherever required)
109. The FDA/SDA shall **physically affix the colour joint-photo of the couple** if required and get the **cross-signatures of bridegroom and bride on the pasted joint photo** of the couple (as the joint photo of the couple isn't captured by the FDA/SDA)
110. The FDA/SDA shall get **Seal and Signature** affixed by the SR/MO on the Marriage Certificate (with Registration Number) (and other forms wherever required)
111. The FDA/SDA shall click on the '**Upload**' button
112. The FDA/SDA upload screen shall display the following:
 - a. **Details:** Application Number, Application Type, Date of Marriage
 - b. **Scan and Preview buttons:** to scan and preview Certificate & Forms, Annexures/Enclosures
 - c. '**Save and Send back to SR/MO**' button
113. The FDA/SDA shall **Scan and Preview** (by clicking the '**Scan**' and '**Preview**' buttons respectively) the following documents:
 - a. Application Form of Notice
 - b. Signed Marriage Certificate
 - c. Enclosures/Annexures
114. The FDA/SDA shall click on the '**Save and Send back to SR/MO**' button and shall forward it to the SR
115. The SR shall view the documents uploaded by FDA/SDA, then shall click on '**Digital Sign & Complete**' button to put his digital signature, encrypt and to upload all the saved documents

(Note: pop up message should appear once he clicks on '**Digital Sign & Complete**' button saying that 'Are you sure to digitally sign and upload? Once uploaded, the details cannot be changed' for which the SR/MO has to confirm)

(Note: An option may be provided for the SR/MO if re-scan is required; on clicking on the '**Send for Re-scan**' button by SR/MO, it would request the SDA/FDA to re-scan and send it back to SR/MO; and then SR/MO shall view the scanned

documents and shall proceed further by clicking on the '**Digital Sign & Complete**' button)

(Note: The applicant receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))

116. Any **Additional Payment** by the applicant(s)/objector(s) is made through Cash; the applicant(s)/objector(s) receives an Acknowledgement (a copy of Fee Receipt has to be generated by the FDA/SDA on receipt of cash)
117. The scanned documents are sent to RGoM (Registrar General of Marriage)
118. The **Marriage Registration Certificate** is handed over physically to the applicant after receiving the acknowledgement and the applicant shall collect the Marriage Certificate
119. The **Sakala** is updated

(Note: 1. If applied for **CC (Certified Copy)** for Marriage Certificate, then **Digitally/Physically Signed Copy** from SR/MO may be issued by filling appropriate form; 2. In case any changes to be done to the Registration of Marriage due to erroneous data entry, the same shall be done in the system with approval from SR)



THE FIFTH SCHEDULE

(See Section 16)

CERTIFICATE OF MARRIAGE CELEBRATED IN OTHER FORMS

I, E.F., hereby certify that A.B. and C.D.* appeared before me this.....day of 20..... and the each of them, in my presence of three witnesses who have signed hereunder have declared that a ceremony of marriage has been performed between them and that they have been living together as husband and wife since the time of their marriage, and that in accordance with their desire to have their marriage registered under this Act, the said marriage has, this..... day of 20..... been registered under this Act, having effect as from.

(Signature)

E.F.,

Marriage Officer for.....

(Sd.)

A.B., Husband

(Sd.)

C.D. Wife

(Sd.)

G.H.

(Sd.)

I.J.

(Sd.)

K.L.

Three witnesses

Dated the..... day of 20.....

* Herein give particulars of the parties

Form IV

Index of Register

(See Rule 5(2) and Rule 6)

Index No. I

HUSBAND

Name of Husband	Place of Residence	Name of Wife	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Ram		Asha				YPR-HM11-2022-23 6-Apr-2022
Shyam		Usha				
Bhim		Nisha				

Form V

Index of Register

(See Rule 5(2) and Rule 6)

Index No. II

WIFE

Name of Wife	Place of Residence	Name of Husband	Place of Residence	Place of Marriage	Date of Marriage	Marriage Number
(1)	(2)	(3)	(4)	(5)	(6)	(7)
Asha		Ram				YPR-HM11-2022-23 6-Apr-2022
Usha		Shyam				
Nisha		Bhim				

(Note: Form V & VI - Index of Register Forms – wife & husband wise separately)

31.4 Validations and Controls

1. The system should record application details online through web
2. The system should accept payment and captures payment detail
3. The system should allow modification/deletion of entered data before registration and after registration with orders from the MO
4. The system should allow Approval/Rejection of application with mechanism for entering the mandatory remarks in the system and generation of endorsement against the same
5. The system should notify MO/FDA/Applicants if application is rejected through e-mail, SMS, notification or endorsement
6. The system should record notice of intended marriage in the system online
7. The system should Display the notice on public portal after authorization of the MO in the system
8. The system should generate marriage certificate
9. The system should capture delivery details once the certificate is issued
10. The system should show status of application
11. The system should display the application filed for editing by the applicant before registration
12. The system should display marriage records on query
13. The system should display available date and time for solemnization in case of special marriage
14. The system should book a slot for solemnization on request
15. The system should capture photographs of couple
16. The system should generate MIS reports based on data captured in the system. There should be authorization mechanism for role based access to reports for generation and view
17. The system should generate Summary Report for verification of data entered and make provision for correction if any changes found
18. Once the applicant submits the application and after the application being verified & approved by FDA/SDA/SR/MO, the **'URL and Barcode' should be generated on the Application Form of Notice** so that later, it would be helpful for the Objector to file an Objection on payment of Objection Fee

32 FIRM REGISTRATION MODULE

32.1 Brief Description

In addition to the information below, please find a detailed requirements document attached:

<https://csgkarnataka.sharepoint.com/:w:/r/sites/ULMS/Knowledge%20Base/FRS/Approved/FRS/Firm%20registration%20FRS.docx?d=w2d77d0a31812432fa19596d8e03eb8d0&csf=1&web=1&e=UI9vdZ>

Please use the above link to access Firm registration detailed FRS.

i. **Brief Description**

Firm is a collection of professionals need to work in the same direction under one roof. Firm comprised of capital, finance, asset, shareholders, funds, employee and many more. Different firms have different criteria to work as depend upon its theme and area of operating. These differentials in the numbers of elements of the varied firms bring a different set of rules and regulations for registration. Here, the partnership firm gets registered in accordance with Indian Partnership Act, 1932 read with Karnataka Partnership (Registration of Firms) Rules, 1954.

Overview

Any two or more citizens can enter into partnership and register the partnership firm. The firm is registered in the office of District Registrar of the concerned jurisdiction. Firm can be registered after following the procedure laid down in Section 59 of the Indian Partnership Act, 1932.

Actors

1. Applicant – fills the application form online, uploads require documents, makes payment, schedules appointment, collects firm registration certificate
2. Agent/Presenter – represents the applicant (on applicant's behalf) at DRO at the time of firm registration
3. DR – scrutinizes document and application forms, admits for registration, signs firm registration certificate and issues the registration certificate
4. FDA/SDA – scrutinizes document and application forms, captures/edits data, scans and uploads the documents
5. System – generates summary report, generates and sends email/sms, generates registration number
6. Kaveri 2.0 – software used in registration

Inputs

1. Filled & Signed Application Form (New Firm/ Amendment/ Re-constitution or Dissolution) in the prescribed format

2. Certified Original copy of the Partnership deed or the document detailing the terms and condition of partnership
3. A specimen of the Affidavit that is certifying the details that are mentioned in the partnership deed and the documents
4. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.)
5. Enclosures/Annexures (ID Proof, Address Proof, etc.)

Output

1. Certificate of Firm Registration in Form C with DR's seal and signature affixed

32.2 Stakeholder – Role and Responsibilities

Applicant

1. File the application for Registration/ Amendment/ Re-constitution/ Dissolution of the firm
2. Online data entry
3. Payment of fees
4. Book an appointment
5. Collect acknowledgement and fee receipt
6. Collect the Certificate of Registration under acknowledgement

District Registrar

1. Verification of the documents submitted
2. Data entry/edit in the System (May be performed by FDA/SDA if authorised by DR)
3. Approval of Registration in the system

FDA/SDA

1. Verification of the documents allocated by DR
2. Data edit/entry in the system (may be performed if authorised by DR)
3. Print acknowledgement and fee receipt
4. Scanning of documents
5. Printing of respective certificate/acknowledgement

System

1. Data edit/entry for the application at DRO
2. Firm's Name search (for existing or objectionable name)
3. Calculation of fee
4. Generate acknowledgement and fee receipt
5. Updation in the Register of Firms and its Index

6. Generating of respective certificate/acknowledgement
7. Accounting entry for each transaction in A-Register
8. MIS preparation

Process Triggers

1. Receipt of application at DR office
2. Check and Register
3. Digital Sign and Register

Data/ Information Requirements

1. Application form for the service required
2. Partnership deed copy
3. Declaration duly attested
4. Affidavit
5. Index of Register of Firms

Key Performance Indicators

1. Registration of Firm to be completed in 10 minutes

Interfaces and Purpose

System	Information Received	Information Sent
A-Register	Registration Number, Fee Collected, Fee Receipt Number, Duration of Firm Date and Time of Registration	Fee Collected, Stamp Duty paid on the partnership deed/ document
Register of Firms and its index	Details of Firms registered/ amended/ re-constituted/ dissolved as follows: Name of the Firm Name of the Partners Place of Business Duration of Firm Registration Number and Year and Date of Registration	Names and addresses of Firm for Query

Forms and Registers

1. Application Form
2. Register of Firms and its Index
3. A-Register for Accounting
4. Endorsement Form
5. Acknowledgement Form

MIS Reports

Daily, Weekly, Monthly and Annual statement of Following:

1. Number of Firms Registered, Amended, Re-constituted and Dissolved application-wise and in total
2. Amount of fee collected
3. Type of Business
4. Amount of stamp duty of the attached deed documents application-wise

Roles, Hierarchy and Responsibilities

1. As discussed in Stakeholders and Interface sections above

32.3 Types of Firm Registration

i. **Brief Description**

Firm is a collection of professionals need to work in the same direction under one roof. Firm comprised of capital, finance, asset, shareholders, funds, employee and many more

a. New Firm Registration – means constitution or declaration of terms and conditions of a firm signed by two or more individuals to carry out a business or institution

b. Amendment of Firm – means any change with respect to name or location of the principal place of business, change in the place of business other than the principal place of business, alteration in the name or permanent address of the partners, notice of election by person admitted to the benefit of partnership on attaining majority

c. Re-constitution – means change in the constitution of the firm

d. Dissolution of Firm – means dissolution of the firm

ii. **Process Flow:**




Figure 1: Registration of Firm (Page 1)




Figure 2: Registration of Firm (Page 2)

iii. Functional Step by Step Process:

Steps taken by Citizen/ Applicant to file Firm Registration Online Applicant Login

1. To file the application online, the applicant shall browse for **Kaveri Online Services** ie., Kaveri 2.0
2. The applicant shall register as a user by creating user id and password
3. The applicant shall now login in the Kaveri 2.0 portal
4. The applicant shall click on '**Start a New Application**'
5. The applicant shall click on '**Firm Registration**' on the screen
6. The applicant shall select the required service (among the four options) as per the requirement. **The services provided** are:
 - a. Registration of New Firm,
 - b. Amendment to the Constitution of Firm and
 - c. Re-constitution of Firm
 - d. Dissolution of Firm

32.3.1 New Firm Registration

7. For **New Firm Registration**, the system requests the applicant to fill in the following entry fields:

Details (User Inputs) to be captured for the New Firm:

Firm Details:

- i. Name of the Firm (mandatory field)
(Note: 1. The system shall search in the Index of Register of Firms for registered firms with same name and address exist. If found in search, or if name of firm is objectionable, the system shall ask for change in name of the firm; 2. Objectionable Names NOT to be used are: Crown, Emperor, Empress, Empire, Imperial, King, Queen, Royal, or words expressed or implying the sanction, approval or patronage of Government)
- ii. Place of Business
 - a. **Principal Place** – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
 - b. **Other Place(s) ie., the Branch(es)** – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields) (if required and only if branch(es) exist, hence an optional field)
(Note: Provision must be made for the applicant to enter any number of branches as he wishes)
- iii. Duration of the firm (calendar) (mandatory field)
(Note: The applicant has to mention either (i) Select a date (date, month, year) from the calendar or (ii) At Will (indefinite time))

Presenter Details:

- i. Whether Presenter is Partner or Agent? (radio button; keep default as partner which can be changed) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must capture the below mentioned details (from ii to ix) and should ensure that the information captured should be auto-fetched in Partner Details page under Partner 1)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)

(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)

- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: Only the partners can be applicants (ie., not the agent))

Partner Details:

- i. Name of the Partners in full (mandatory field)
(ie., Salutation-Name-Relationship-Relative Name)
 - a. Salutation (dropdown) (Eg: Sri., Smt., M/S, Mr., Mrs., Kumari., Kaumara.) (mandatory field)
 - b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Relationship (dropdown) (Eg: D/o, MG, C/o, S/o, M/o, W/o) (mandatory field)
 - d. Relative Name (manually enter data) (Eg: father/ mother/husband/ wife/care-of/guardian (if minor) name, etc.) (mandatory field)
- ii. Date of Birth (calendar) (optional field)
- iii. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. Even a minor can be a partner)
- iv. Gender (mandatory field)
- v. Occupation (optional field)
- vi. Mobile Number (mandatory) (mandatory field)
- vii. Email ID (optional field)
- viii. Date of Joining the firm (calendar) (mandatory field)
- ix. Present (ie., Current) Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
- x. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
(Note: to provide for 'same as above' button; if checked, then the Permanent Address should be auto-fetched from Current Address)
(Note: to provide for 'same as above' button; if checked, then the Permanent Address should be auto-fetched from Current Address)

(Note: fields from i to x (under Partner Details) should be captured SEPARATELY for all the partners)

Station & Date Details:

- i. Station (ie., Place) (mandatory field)
- ii. Date (calendar) (mandatory field)

Witness Details:

Details of Witness 1:

(Note: note/message – ‘witness who must be either a Gazetted Officer, Advocate, Attorney, Vakil, Honorary Pleader, Chartered Accountant or Registered State Auditor’ must be shown on the top of the witness page)

- i. Salutation (mandatory field)
- ii. First Name, Middle Name, Last Name (mandatory field)
- iii. Date of Birth (calendar) (optional field)
- iv. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)
- v. Gender (mandatory field)
- vi. Profession (dropdown) (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Date (calendar) (mandatory field)
- x. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: 1. Even a Minor (<18 years in age) can be a partner; 2. Witness should be a Major (>=18years); 3. 1 Mandatory Witness (but provision for adding witnesses has to be provided) is required for New Firm Registration; for each partner, 1 witness (which needn't be unique) is required (ie., single witness can sign for all the partners); 4. This form must be signed by all partners or their agents specially authorised in this behalf in the presence of a witness(es) who must be either a Gazetted officer, Advocate, Attorney, Vakil, Honorary Pleader, Chartered Accountant or Registered State Auditor; 5. In Partnership Deed document, minimum of 2 witnesses are required)

District Registrar Office (DRO) Selection

8. The system should freeze the DRO (District Registrar Office) based on the **Permanent Address (Principal Place of Business) of the Firm**
(Note: For New Firm – should be the same DRO where the firm is situated (principal place of business) or proposed; For Amendment and Dissolution of Firm – should be the same DRO where the firm was initially registered)

Generation of Application Summary

9. The applicant after filling up the application form, the **Application Summary** is shown by the system
10. The applicant either Accepts the '**Declaration**' and clicks on '**View Form**'; or the '**Edit**' option to make any changes to the application
11. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the firm details screen (Keep all previously filled data)
12. When clicked on '**View Form**', the corresponding new firm registration form shall be auto-fetched to the applicant by the system
13. Go to step 42

FORM I

[See Rule 3]

Filling Fee Rs. 3

APPLICATION FOR REGISTRATION OF FIRM BY THE NAME*

Presented or forwarded to the Registrar of Firms for filling by.....

We the undersigned, being the partners of the firm hereby apply for registration of the said firm and for that purpose supply the following particulars, in pursuance of Section 58 of the Indian Partnership Act, 1932.

The Firm name *

Place of business

(a) Principal place :

(b) Other places :

Names of Partners in full	Date of Joining the firm	Permanent Address in full
1.		
2.		
Duration of the firm		

Station:

Date:

Signature of the partners of their
specially authorised agents

I,Son of
..... year of age,
religion, do hereby declare that the above statement is true and correct to the best
of my knowledge and belief.

Date:

Witness:

Signature

I, Son of
..... year of age, do hereby declare that
the above statement is true and correct to the best of my knowledge and belief.

Date:

Witness:

Signature

*Here enter the name of firm.

If any partner is a minor the fact whether he is entitled to the benefits of partnership should be set out herein.

N.B.- This form must be signed by all partners or their agents specially authorised in this behalf in the presence of a witness or witness who must be either a Gazetted officer, Advocate, Attorney, Vakil, Honorary Pleader, Chartered Accountant or Registered State Auditor.

32.3.2 Amendment to the Constitution of firm

14. For **Amendment of Firm**, the system requests the applicant to enter the Registration Number of the firm
15. The system shall Retrieve & Populate the Data (auto-fetched) corresponding to the Registration Number of the firm and shall displays on the screen the details of the firm
16. The system shall request to select the type of amendment required. The system prompts for new entry as per the selected amendment
17. The applicant shall select from among the **Types of Amendments**:
 - i. Change in name of the firm or in the location of the principal place of business
 - ii. Change in the place of business other than the principal place of business
 - iii. Alteration in the name or permanent address of the partner
 - iv. Notice of election by person admitted to the benefit of partnership on attaining majority

(Note: If the applicant selects 'Alteration in the Name' ie., option (c), then the system shall search in the Index of Register of Firms for registered firms with same name exist. If found in search, or if name of firm is objectionable, the system shall ask for change in name of the firm; 2. The applicant can choose ≥ 1 types of amendments in a single application, BUT has to pay the FEE accordingly)

18. The system requests the applicant to fill in the following entry fields:

- a. Change in name of the firm or in the location of the principal place of business**
Details (User Inputs) to be captured for the above said type of Amendment of Firm: -

Firm Details:

- i. Name of the Firm
 - a. Previous Name (to be auto-fetched)
 - b. New Name

(Note: 1. The system shall search in the Index of Register of Firms for registered firms with same name and address exist. If found in search, or if name of firm is objectionable, the system shall ask for change in name of the firm; 2. Objectionable Names NOT to be used are: Crown, Emperor, Empress, Empire, Imperial, King, Queen, Royal, or words expressed or implying the sanction, approval or patronage of Government)

- ii. Principal Place of Business
 - c. Previous Place (to be auto-fetched)
 - d. New Place – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: Either b or d or both b&d must be entered)

Station & Date Details:

- iii. Station (ie., Place) (mandatory field)
- iv. Date (calendar) (mandatory field)

Presenter Details:

- i. Whether Presenter is Partner or Agent? (dropdown) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

Witness Details:

Details of Witness 1:

(Note: note/message – 'witness who must be either a Gazetted officer, Advocate, Attorney, Vakil, Honorary Pleader, Chartered Accountant or Registered State Auditor' must be shown on the top of the witness page)

- i. Salutation (mandatory field)
- ii. First Name, Middle Name, Last Name (mandatory field)
- iii. Date of Birth (calendar) (optional field)
- iv. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)
- v. Gender (mandatory field)
- vi. Profession (dropdown) (mandatory field)

- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Date (calendar) (mandatory field)
- x. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

(Note: 1. Even a Minor (<18 years in age) can be a partner; 2. Witness should be a Major (>=18years); 3. 1 Mandatory Witness (but provision for adding witnesses has to be provided) is required for New Firm Registration; for each partner, 1 witness (which needn't be unique) is required (ie., single witness can sign for all the partners); 4. This form must be signed by all partners or their agents specially authorised in this behalf in the presence of a witness(es) who must be either a Gazetted officer, Advocate, Attorney, Vakil, Honorary Pleader, Chartered Accountant or Registered State Auditor)

b. Change in the place of business other than the principal place of business

Details (User Inputs) to be captured for the above said type of Amendment of Firm: -

Firm Details:

- i. Name of the Firm (to be auto-fetched)
- ii. Place(s) of Business (Address) - Other Place(s) ie., the Branch(es)
 - a. Other Place(s) ie., the Branch(es) (to be auto-fetched)
 - b. Date of Change (ie., Date of Dis-continuation) (calendar)
 - c. New Place ie., the Branch (ie., Address) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode
 - d. Date of Commencement (ie., Start date) (calendar)

(Note: 1. Either a,b or c,d or a,b & c,d must be entered ; 2. c and d should be captured **separately** if asked for more than one place/branch; 3. Generally, the Date of Commencement is the Date of Dis-continuation; 4. Option to change one branch only at a time)

Station & Date Details:

- i. Station (ie., Place) (mandatory field)
- ii. Date (calendar) (mandatory field)

Presenter's/Agent's Details:

- i. Whether Presenter is Partner or Agent? (dropdown) (mandatory field)
- (Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system

must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)

- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age >= 18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

c. Alteration in the name or permanent address of the partners

Details (User Inputs) to be captured for the above said type of Amendment of Firm: -

Firm's Details:

- i. Name of the Firm (to be auto-fetched)

Presenter's/Agent's Details:

- i. Whether Presenter is Partner or Agent? (dropdown) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age >= 18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)

- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

Partner's Details:

- i. Name of the Partner
 - a. Previous Name (in full) (to be auto-fetched)
(Note: 1. All the names of the partners should be auto-fetched; 2. The applicant chooses from among them the name to be changed/modified; 2. Option to change one name at a time)
 - b. New Name (in full)
(ie., Salutation-Name-Relationship-Relative Name)
 - 1) Salutation (dropdown) (Eg: Sri., Smt., Mr., Mrs., etc.) (mandatory field)
 - 2) First Name, Middle Name, Last Name (only First Name is mandatory field)
 - 3) Relationship (dropdown) (Eg: s/o, w/o, d/o, etc.) (mandatory field)
 - 4) Relative Name (manually enter data) (Eg: father/mother/husband/ wife/care-of/guardian (if minor) name, etc.) (mandatory field)
- ii. Address of the Partner
 - c. Previous Permanent Address (in full) (to be auto-fetched)
(Note: 1. All the addresses of the corresponding partners should be auto-fetched; 2. The applicant chooses from among them the address to be changed/modified)
 - d. Present Permanent Address (in full) – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
(Note: 1. Either b or d or both b&d must be entered)

Station & Date Details:

- i. Station (ie., Place) (mandatory field)
- ii. Date (calendar) (mandatory field)

d. Notice of election by person admitted to the benefit of partnership on attaining majority

Details (User Inputs) to be captured for the above said type of Amendment of Firm: -

Firm's Details:

- i. Name of the Firm (to be auto-fetched)
(Note: 1. Option to change one partner's status (minor to major) only at a time)

Presenter's/Agent's Details:

- i. Whether Presenter is Partner or Agent? (dropdown) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

Station & Date Details:

- i. Station (ie., Place) (mandatory field)
- ii. Date (calendar) (mandatory field)

Generation of Application Summary

- 19. The applicant after filling up the application form, the **Application Summary** is shown by the system
- 20. The applicant either Accepts the '**Declaration**' and clicks on '**View Form**'; or the '**Edit**' option to make any changes to the application
- 21. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the firm details screen (Keep all previously filled data)
- 22. When clicked on '**View Form**', the corresponding amendment form shall be auto-fetched to the applicant by the system
- 23. Go to step 42

FORM II

[See Rule 3]

Filling Fee: Rs. 1.00

STATEMENT OF ALTERNATION IN THE NAME OF THE FIRM OR IN THE LOCATION OF THE PRINCIPAL PLACE OF BUSINESS

Presented or forwarded to the Registrar of Firms for filing by:

We, the undersigned, being the partners of the firm *.....
(here enter name of the firm) hereby supply the following particulars in pursuance of
Section 60(1) of the Indian Partnership Act, 1932.

Name of firm	
Previous name	New name

Principal place of business

Previous place	New place

Station:

Date:

Signature of the partners of their
specially authorised agents

I, Son of Year of age, of
..... do hereby declare that the above statement is true and correct to the
best of my knowledge and belief.

Date :

Witness :

Signature

I, Son of Year of age, of
..... do hereby declare that the above statement is true and correct to the
best of my knowledge and belief.

Date :

Witness :

Signature

N.B.-Strikeout item not required.

FORM III

[See Rule 4(1)]

Filing Fee: Rs. 5

INTIMATION OF CHANGE IN THE PLACE OF BUSINESS (OTHER THAN PRINCIPAL PLACE OF BUSINESS)

Presented or forwarded to the Registrar of Firms for filing by:

Under Section 61 of the Indian partnership Act, 1932, intimation is hereby given that the changes specified below have occurred in the place of business of the firm (here enter the name and Registration No. of the firm)*

Date of change

(1) The firm has discontinued business at

(2) The firm has begun to carry on business at

Station :

Date :

Signature of any partners or
Agent of the Firm.

*Here enter the name of the firm.

N.B.- Strikeout items not required.

FORM IV

[See Rule 4(1)]

Filing Fee: Rs. 1.00

INTIMATION OF ALTERNATION IN THE NAME OR PERMANENT ADDRESS OF PARTNER

Presented or forwarded to the Registrar of Firms for filing by:

Under Section 62 of the Indian Partnership Act, 1932, intimation is hereby given that the change specified below has occurred in the name and/or permanent address of partner in the firm (here enter the name and register No. of the firm) *

Name of partner	
Previous name (full)	New name (full)

Name of partners	
Previous permanent address (in full)	Present permanent address (in full)

Station :

Date :

Signature of any partners or
Agent of the Firm.

*Here enter the name of the firm.

N.B.- Strikeout items not required.

FORM VI

[See Rule 4(1)]

Filling Fee: Rs. 1.00

**NOTICE OF ELECTION BY PERSON ADMITTED TO THE BENEFIT OF
PARTNERSHIP ON ATTAINING MAJORITY**

Presented or forwarded to the Registrar of Firms for filing by:

Under Section 53(2) of the Indian Partnership Act, 1932, notice is hereby given that admitted to the benefit of partnership of the firm having now attained majority elects to become/elects to become a partners of the said firm.

Station :

Date :

Signature of the person electing or of
his specially authorized agent.

32.3.3 Re-constitution of Firm

24. For **Re-constitution of Firm**, the system requests the applicant to enter the Registration Number of the firm
25. The system shall Retrieve & Populate the Data (auto-fetched) corresponding to the Registration Number of the firm and shall displays on the screen the details of the firm
26. The system prompts for new entry as per the selected amendment.
 - a. Change in the constitution (re-constitution) of the firm
27. The system requests the applicant to fill in the following entry fields:
Details (User Inputs) to be captured for re-constitution of the firm:

Firm Details:

- i. Name of the Firm (to be auto-fetched)

Presenter Details:

- i. Whether Presenter is Partner or Agent? (radio button; keep default as partner which can be changed) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age >= 18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

Incoming Partner Details:

- i. Name of the Partner in full (mandatory field)
(ie., Salutation-Name-Relationship-Relative Name)

- a. Salutation (dropdown) (Eg: Sri., Smt., Mr., Mrs., etc.) (mandatory field)
 - b. First Name, Middle Name, Last Name (only First Name is mandatory field)
 - c. Relationship (dropdown) (Eg: s/o, w/o, d/o, etc.) (mandatory field)
 - d. Relative Name (manually enter data) (Eg: father/mother/husband/ wife/care-of/guardian (if minor) name, etc.) (mandatory field)
 - ii. Date of Birth (calendar) (optional field)
 - iii. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. Even a Minor (<18 years in age) can be a partner)
 - iv. Gender (mandatory field)
 - v. Occupation (optional field)
 - vi. Mobile Number (mandatory field)
 - vii. Email ID (optional field)
 - viii. Date of Joining the firm (calendar) (mandatory field)
 - ix. Present (ie., Current) Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
 - x. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)
(Note: to provide for 'same as above' button; if checked, then the Permanent Address should be auto-fetched from Current Address)
- (Note: 1. To provide for 'same as above' button; if checked, then the Permanent Address should be auto-fetched from Present Address; 2. There can be more than one incoming partner and hence an option must be provided to capture the details for more than one incoming partner through 'add incoming partner' button; 3. The fields from i to x (under Incoming Partner's Details) should be captured SEPARATELY for all the incoming partners)

Outgoing Partner

- i. Name of the Partner in full (to be auto-fetched)
 - ii. Full Address of the Partner (to be auto-fetched)
 - iii. Date of Ceasing to be Partner (calendar) (mandatory field)
- (Note: 1. Even a Minor (<18 years in age) can be a partner; 2. There can be more than one outgoing partner and hence an option must be provided to select the names of all the outgoing partners and their date of ceasing to be partner SEPARATELY through calendar)

Station & Date Details:

- i. Station (ie., Place) (mandatory field)
- ii. Date (calendar) (mandatory field)

Generation of Application Summary

- 28. The applicant after filling up the application form, the **Application Summary** is shown by the system
- 29. The applicant either Accepts the '**Declaration**' and clicks on '**View Form**'; or the '**Edit**' option to make any changes to the application
- 30. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the firm details screen (Keep all previously filled data)
- 31. When clicked on '**View Form**', the corresponding re-constitution form shall be auto-fetched to the applicant by the system
- 32. Go to step 42

FORM V

[See Rule 4(1)]

Filling Fee: Rs. 1.00

NOTICE OF CHANGE IN THE CONSTITUTION OF THE FIRM OR THE DISSOLUTION OF THE FIRM

Presented or forwarded to the Registrar of Firms for filing by:

Under Section 63(1) of the Indian partnership Act, 1932, notice is hereby given that.-

(1) The constitution of the firm has been altered as follows.-

Name and full address of the incoming partner and date of his joining the firm	Name and full address of the outgoing partner and date of his ceasing to be partner

Station :

Date :

Signature of the continuing, incoming or outgoing partners or of his specially authorized agent.

(2) The firmhas been dissolved with effect from the

Station :

Date :

Signature of the person who was a partners immediately before the dissolution or of his specially authorized agent

*Here enter the name of the firm.

N.B.- Strikeout items not required.

32.3.4 Dissolution of Firm

33. For **Dissolution of Firm**, the system requests the applicant to enter the Registration Number of the firm
34. The system shall Retrieve & Populate the Data (auto-fetched) corresponding to the Registration Number of the firm and shall displays on the screen the details of the firm
35. The system prompts for new entry as per the selected amendment.
 - a. Dissolution of the firm
36. The system requests the applicant to fill in the following entry fields:
Details (User Inputs) to be captured for dissolution of the firm:

Firm Details:

- i. Name of the Firm (to be auto-fetched)
- ii. Date of Dissolution of Firm (calendar) (mandatory field)

Presenter Details:

- i. Whether Presenter is Partner or Agent? (radio button; keep default as partner which can be changed) (mandatory field)
(Note: If presenter is an **Agent**, then the system must capture the below mentioned details (from ii to ix); If presenter is a **Partner**, then the system must provide an option to select from among the existing Partners from the dropdown menu and auto-fetch the selected partner's details; have to capture his/her mobile number isn't captured earlier, which might be required while he/she reports to the DR at DR Office on the day of appointment for further processing of the application)
- ii. Salutation (mandatory field)
- iii. First Name, Middle Name, Last Name (mandatory field)
- iv. Date of Birth (calendar) (optional field)
- v. Age (in years) (mandatory field)
(Note: 1. Age (in years) should auto-fetch once DoB is entered; 2. The system should register only if age>=18 years)
- vi. Gender (mandatory field)
- vii. Mobile Number (mandatory field)
- viii. Email ID (optional field)
- ix. Permanent Address – House No./Building Name, Street Address, State, District, Taluka, Hobli/Ward, Village/City, Pincode (all are mandatory fields)

Station & Date Details:

- iii. Station (ie., Place) (mandatory field)
- iv. Date (calendar) (mandatory field)

Generation of Application Summary

- 37. The applicant after filling up the application form, the **Application Summary** is shown by the system
- 38. The applicant either Accepts the '**Declaration**' and clicks on '**View Form**'; or the '**Edit**' option to make any changes to the application
- 39. If Applicant chooses to **Edit** the application, the system shall take the applicant back to the firm details screen (Keep all previously filled data)
- 40. When clicked on '**View Form**', the corresponding dissolution form shall be auto-fetched to the applicant by the system
- 41. Go to step 42

FORM V

[See Rule 4(1)]

Filling Fee: Rs. 1.00

NOTICE OF CHANGE IN THE CONSTITUTION OF THE FIRM OR THE DISSOLUTION OF THE FIRM

Presented or forwarded to the Registrar of Firms for filing by:

Under Section 63(1) of the Indian partnership Act, 1932, notice is hereby given that.-

(1) The constitution of the firm has been altered as follows.-

Name and full address of the incoming partner and date of his joining the firm	Name and full address of the outgoing partner and date of his ceasing to be partner

Station :

Date :

Signature of the continuing, incoming or outgoing partners or of his specially authorized agent.

(2) The firmhas been dissolved with effect from the

Station :

Date :

Signature of the person who was a partners immediately before the dissolution or of his specially authorized agent

*Here enter the name of the firm.

N.B.- Strikeout items not required.

Print of filled Application Form and Affix of Signatures

42. The applicant shall take the print out of the filled application form by clicking on the '**Print**' button
(Note: 1. The details entered by the applicant gets auto-filled in the corresponding (relevant) Form and the filled application has to get printed when 'Print' button is pressed)
43. The applicant shall sign (signature of partners, 1 witness (needn't be unique) for each partner), scan and upload the same along with the below mentioned enclosures

Scan & Upload of Signed Application Form(s) & Enclosures/Annexures by the Applicant

44. The system provides the List of Enclosures to be Uploaded and the applicant shall **Scan and Upload** the below mentioned documents:

For NEW FIRM

Firm related documents:

- a. Filled & Signed Application Form I - Form I duly filled in and signed by all partners and affixing witness who must be either Gazetted Office, Advocate, Vakil, Magistrate, or Registered Chartered Accountant, Auditor
- b. Partnership Deed - Certified Original Copy of Notarised Partnership deed on Rs.2,000/- E-stamp Paper /Challan
- c. Affidavit - A specimen of the Affidavit that is certifying the details that are mentioned in the partnership deed and the documents (optional)
- d. Address Proof of Firm - If the firm Address is own Building, Tax Paid Receipt or Sale deed and if it is rented, Duly stamped Rental Agreement

Presenter related documents:

- e. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Partner related documents:

- f. ID Proof (for each partner)
- g. Address Proof (for each partner)
(Note: Self-attested ID and Address Proof of the Partners)

Additional Supporting Document (if any) (optional)

- h. Supporting Document 1
- i. Supporting Document 2

For AMENDMENT OF FIRM

i. For Change of Name or Address of Firm:

Firm related documents:

- a. Filled & Signed Application Form II - Form II duly filled in and signed by all partners and affixing witness who must be either Gazetted Office, Advocate, Vakil, Magistrate, or Registered Chartered Accountant, Auditor
- b. Amendment Deed in Rs.1000/- E-Stamp Paper /Challan signed by all the partners
- c. Address Proof of Firm - If the changed firm Address is own Building, Tax Paid Receipt or Sale deed and if it is rented, Duly stamped Rental Agreement

Presenter related documents:

- d. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Additional Supporting Document (if any) (optional)

- e. Supporting Document 1
- f. Supporting Document 2

ii. For Opening New Branches or Closing Existing Branches of Firm:

Firm related documents:

- a. Filled & Signed Application Form III - Form III duly filled in and signed by all partners and affixing witness who must be either Gazetted Office, Advocate, Vakil, Magistrate, or Registered Chartered Accountant, Auditor
- b. Address Proof of Firm - If the Branch Address is own Building, Tax Paid Receipt or Sale deed and if it is rented, Duly stamped Rental Agreement

Presenter related documents:

- c. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Additional Supporting Document (if any) (optional)

- d. Supporting Document 1
- e. Supporting Document 2

iii. For Change in the Name or Permanent Address of Partner:

Firm related documents:

- a. Filled & Signed Application Form IV - Form IV duly filled in and signed by all partners and affixing witness who must be either Gazetted Office, Advocate, Vakil, Magistrate, or Registered Chartered Accountant, Auditor

Partner related documents:

- b. Affidavit - In case of change in the name - Proof of the - Notarised Affidavit for change in name and the same published in Newspaper, i.e Newspaper cutting
- c. ID Proof (for each partner) - In case of change in the name of partner

- d. Address Proof (for each partner) - In case of change in the address of partner

(Note: Self-attested ID and Address Proof of the Partners)

Presenter related documents:

- e. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Additional Supporting Document (if any) (optional)

- f. Supporting Document 1
- g. Supporting Document 2

iv. Minor Partner now attained Majority Elect to become/elects not to become a Partner of the said firm:

Firm related documents:

- a. Filled & Signed Application Form VI - Form VI duly filled in and signed by all partners attested by Notary

Presenter related documents:

- b. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Partner related documents:

- c. ID Proof (for each partner)
 - d. Address Proof (for each partner)
- (Note: Self-attested ID and Address Proof of the Partners)

Additional Supporting Document (if any) (optional)

- e. Supporting Document 1
- f. Supporting Document 2

For RE-CONSTITUTION OR CHANGE IN CONSTITUTION OF FIRM

Firm related documents:

- a. Filled & Signed Application Form V - Form V duly filled in and signed by all partners attested by Notary
- b. Registered Re-constitution Deed

(Note: (i) For either movable property or immovable property (where there is no distribution ie., they are taking back their share of their properties), a Copy of (Notarised) Re-constitution Deed on Rs. 1,000/- E-stamp Paper/ Challan and (ii) For Immovable property (where there is distribution ie., they are not taking back their share of their properties), a Copy of Registered Re-constitution Deed has to be enclosed)

- c. Affidavit - If the Retiring Partner has not contributed any immovable Property to the firm and not taking away any immovable property from the firm, Notarised Affidavit on Rs.20/- E Stamp Paper swearing that he has not contributed any immovable Property to the firm and not taking away any immovable property from the firm

Presenter related documents:

- d. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Incoming Partner related documents:

- g. ID Proof (for each partner)
 - h. Address Proof (for each partner)
- (Note: Self-attested ID and Address Proof of the Incoming Partners)

Additional Supporting Document (if any) (optional)

- i. Supporting Document 1
- j. Supporting Document 2

For DISSOLUTION OF FIRM

Firm related documents:

- a. Filled & Signed Application Form V - Form V duly filled in and signed by all partners attested by Notary
- b. Registered Re-constitution Deed
(Note: (i) For either movable property or immovable property (where there is no distribution ie., they are taking back their share of their properties), a Copy of (Notarised) Re-constitution Deed on Rs. 1,000/- E-stamp Paper/ Challan and (ii) For Immovable property (where there is distribution ie., they are not taking back their share of their properties), a Copy of Registered Re-constitution Deed has to be enclosed)
- c. Affidavit - If the Partners have not contributed any immovable Property to the firm and not taking away any immovable property from the firm, Notarised Affidavit on Rs.20/- E Stamp Paper swearing that they have not contributed any immovable Property to the firm and not taking away any immovable property from the firm

Presenter related documents:

- d. Proof of Authorisation for the Agent (GPA/Letter of Authority/ Vakalat/ etc.) (only if the Presenter is an Agent (ie., not a partner))

Additional Supporting Document (if any) (optional)

- e. Supporting Document 1
- f. Supporting Document 2

(Note: In the Scan and Upload Screen/Page, an option has to be provided for the system to ask Whether the Document is either **Registered or Notarised** when the applicant is about to upload the Deed Document? if Registered, then enter the **Document Number** to fetch the stamp duty; if Notarised, then enter **the E-stamp Number or Challan Number** to fetch the stamp duty; the same (stamp duty) shall get displayed in the Fee Table)

(Note: 1. All the uploaded documents should be in pdf format and their size shouldn't exceed 5 MB; 2. Scanning Fee is calculated for All the documents uploaded (including Enclosures); 3. System should auto-calculate no. of pages for All the documents uploaded; 4. Upload only the necessary documents as demanded in different cases; 5. REGISTERED Deed Re-constitution or Dissolution means that where the immovable properties are involved & where the value of immovable properties are more than Rs.100, as per section 17 of Registration Act, 1908, it is compulsory to get it Registered in the Sub-registrar Office/ District-registrar Office; 6. There should be a mechanism to validate Registered Deed of Re-constitution or Dissolution)

(Note: List of Permitted Documents supporting **ID Proof**:

1. Aadhar Card
2. PAN Card
3. Driving License
4. Passport
5. EPIC Card (Voter ID)

List of Permitted Documents supporting **Address Proof**:

1. Aadhar Card
2. Driving License
3. Passport
4. EPIC Card (Voter ID))

Display of Fee Structure

45. The System shall calculate and display the fee for processing the application as per the Type of Application/Service selected (New Firm/ Amendment of Firm/ Re-constitution of Firm/ Dissolution of Firm):

For NEW FIRM

- a. Stamp Duty on Deed of New Firm = Rs.2000 (fixed)
(Instrument of Constitution)
- b. Registration Fee = Rs.100 (fixed)
- c. Application Fee = Rs.3 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Firm Registration Certificate))
- e. Total Payable Amount (in Rs.) = a + b + c + d

For AMENDMENT OF FIRM

- i. Change in Name of Firm or in Location of the Principal Place of Business**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee for Change in name of firm or in location of the principal place of business = Rs.50 (fixed)
 - c. Application Fee = Rs.1 (fixed)
 - d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
 - e. Total Payable Amount (in Rs.) = a + b + c + d

- ii. Change in the Place of Business Other than the Principal Place of Business**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee for Change in the place of business other than the principal place of business = Rs.25 (fixed)
 - c. Application Fee = Rs.5 (fixed)
 - d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
 - e. Total Payable Amount (in Rs.) = a + b + c + d

- iii. Alteration in the Name or Permanent Address of the Partner**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee = Rs.25 (fixed)
 - c. Application Fee = Rs.1 (fixed)
 - d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
 - e. Total Payable Amount (in Rs.) = a + b + c + d

- iv. Notice of election by person admitted to the benefit of partnership on attaining majority**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee for Notice of election by person admitted to the benefit of partnership on attaining majority = Rs.0
 - c. Application Fee = Rs.1 (fixed)
 - d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
 - e. Total Payable Amount (in Rs.) = a + b + c + d

For RE-CONSTITUTION OF FIRM

- a. Stamp Duty on Deed of Re-constitution (ie., Change in the Constitution) of Firm
 - i. Where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner(s) on re-constitution of such firm, the Stamp Duty = 3% on the MV (Market Value) of the immovable property remaining with the firm
 - ii. In any other case, Stamp Duty = Rs.1000 (fixed)
- b. Registration Fee = Rs.25 (fixed)
- c. Application Fee = Rs.1 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a(i) or a(ii) + b + c + d

For DISSOLUTION OF FIRM

- a. Stamp Duty on Deed of Dissolution of Firm
 - i. Where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner(s) on re-constitution of such firm, the Stamp Duty = 3% on the MV (Market Value) of the immovable property remaining with the firm
 - ii. In any other case, Stamp Duty = Rs.1000 (fixed)
- b. Registration Fee = Rs.25 (fixed)
- c. Application Fee = Rs.1 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a(i) or a(ii) + b + c + d

(Note: During the verification process, FDA/SDA/DR would have verified the data (say, number of pages entered by the applicant to be scanned); if any changes are needed, then necessary changes would be made by DR)

Example:

In the formation of firm at the initial stage,

Ram – had given his land

Shyam – had given his machinery

At the time of **Dissolution**,

Use-case 1: ram & shyam get back their respective properties ie., in the same ratio as they had invested in the beginning, then 2 = Rs.1000 (fixed)

Use-case 2: ram & shyam won't get back their respective properties ie., not in the same ratio as they had invested in the beginning, then 2 = 3% on the MV (Market Value) of the immovable property

Submission of Application Form

46. The applicant clicks on '**Submit**' button to submit the application online. The applicant will get an application number generated as acknowledgement and receives an email/sms as notification
47. On submission of application, a dialogue box/ flash message should appear stating 'Your application has been successfully submitted'
(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0; the application gets logged in in order in the SR login)

Steps taken by DRO to Register Firm and to secure Firm Registration Certificate to the Applicant(s)

DR Login and Allocation/Verification by DR

48. District Registrar (DR) shall login to the Kaveri 2.0 system
49. From the menu on his dashboard, the DR shall click on '**Firm Application**'
50. The DR receives the firm applications irrespective of their types in one place. Table is supposed to be FIFO
51. The DR can take the following actions:
 - a. **View** - The DR views the firm application by clicking on '**View**' button, and then allocates to FDA/SDA/Self
 - b. **Allocate** – The DR can allocate the firm application to FDA/SDA/Self by clicking on '**Allocate**' button
(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then DR has the option allocate to a particular FDA/SDA of his choice from the dropdown list)

(Note: If the DR allocates to himself/herself by choosing the '**Self**' in the drop menu, then the action button must change to '**Verify**' and NOT '**Allocate**'. In this case, there are NO FDA/SDA Remarks on the UI. The DR himself/herself verifies (the application and enclosures) and sends back to the applicant by clicking on '**Send to Applicant**' button)

FDA/SDA Login and Verification by the FDA/SDA

52. The FDA/SDA shall login
53. All the applications regardless of their type that the DR allocates are supposed to show on FDA/SDA dashboard. Table is supposed to be FIFO.
54. The FDA/SDA shall start the verification process by selecting '**Start Verification**' button
55. The FDA/SDA Application Verification screen is split into 2 sides:

- c. **LHS** (Left hand side of the page) – the Summary sheet containing all the Details which the Applicant has entered (firm details, presenter details, partner details, witness details, stamp duty & fee details), a section to add his Remarks and a button to send it back to the DR
 - d. **RHS** (Right hand side of the page) – contains the Uploads by the Applicant which are Forms and Enclosures
56. The FDA/SDA shall crosscheck the application(s) and the enclosures thoroughly; FDA/SDA fills a **Checklist mentioning Remarks** for each category – firm details, presenter details, partner details, witness details, stamp duty & fee details; sends it back to the DR with Remarks by clicking on '**Send back to DR**'

Verification & Approval by the DR

57. After the application is received from FDS/SDA, the DR shall login and shall view the remarks made by FDA/SDA by clicking on '**View**' button and shall add his/her own remarks filling the checklist and shall send it back to the applicant by clicking on '**Send to Applicant**' for either to attend to the remarks made and resend the application (in the applicant login, 'Your application cannot be registered as it is, Kindly Refer to the Sub Registrar Remarks to know more' message shall be displayed) or to proceed to make payment
58. The DR has an **additional checkbox** named '**Can proceed to Make Payment**' which if ticked, then it takes the applicant to make payment option; ifn't ticked will request the applicant to make changes (as per remarks made by DR) in the application and re-submit the application
(Note: 1. When the changes (attend to DR remarks) are requested by the DR to the applicant, the system takes the applicant to the 'Firm Details' page (ie., the first page in each type of required service as requested by the applicant) with the pre-filled data being retained as earlier over which he can over-write to make changes and then shall send back to the DR by pressing the 'Submit' button; 2. If the applicant wants to change the type of service, then he/she has to re-apply)
59. On the Remarks section, there is a checklist - If the checkbox in the checklist is ticked, the remarks are voluntary; ifn't ticked, then the remarks are mandatory
(Note: 1. In either case, the applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0 dashboard; also the status of the application gets updated in the applicant dashboard on Kaveri2.0; 3. Until unless '**Can proceed to Make Payment**' is checked, the applicant can't proceed to make the payment)
- (Note: 1. If the applicant is willing to attend to the remarks made by DR, then resend the application after corrections are made. If not willing to attend to the remarks made by DR, then the system shall generate the Endorsement with Reason for Rejection; 2. Based on the remarks made by the FDA/SDA, the DR has the option to change (make modification) to the number of pages to be scanned)

Payment of Fee by the Applicant

60. After DR accepts and approves the application, the applicant shall login in the Kaveri 2.0 portal and make the Payment of Fee (Total Payable Amount) online through K2 portal by clicking on '**Make Payment**' button
(Note: The system should show the calculated fee (freeze it and no changes can be made by the applicant at this stage) before applicant makes the payment and then give 'Make Payment' option)
61. The System calculates the fee for processing the application **AS PER THE TYPE OF APPLICATION/SERVICE (as mentioned below)**

Fee Calculation:

62. The System shall calculate and display the fee for processing the application as per the Type of Application/Service selected (New Firm/ Amendment of Firm/ Re-constitution of Firm/ Dissolution of Firm):

For NEW FIRM

- a. Stamp Duty on Deed of New Firm = Rs.2000 (fixed)
(Instrument of Constitution)
- b. Registration Fee = Rs.100 (fixed)
- c. Application Fee = Rs.3 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Firm Registration Certificate))
- e. Total Payable Amount (in Rs.) = a + b + c + d

For AMENDMENT OF FIRM

- i. **Change in Name of Firm or in Location of the Principal Place of Business**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee for Change in name of firm or in location of the principal place of business = Rs.50 (fixed)
 - c. Application Fee = Rs.1 (fixed)
 - d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
 - e. Total Payable Amount (in Rs.) = a + b + c + d
- ii. **Change in the Place of Business Other than the Principal Place of Business**
 - a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
 - b. Registration Fee for Change in the place of business other than the principal place of business = Rs.25 (fixed)
 - c. Application Fee = Rs.5 (fixed)

- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a + b + c + d

iii. Alteration in the Name or Permanent Address of the Partner

- a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
- b. Registration Fee = Rs.25 (fixed)
- c. Application Fee = Rs.1 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a + b + c + d

iv. Notice of election by person admitted to the benefit of partnership on attaining majority

- a. Stamp Duty on Deed of Amendment of Firm = Rs.1000 (fixed)
(Write the corresponding name of the Amendment in brackets ())
- b. Registration Fee for Notice of election by person admitted to the benefit of partnership on attaining majority = Rs.0
- c. Application Fee = Rs.1 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a + b + c + d

For RE-CONSTITUTION OF FIRM

- a. Stamp Duty on Deed of Re-constitution (ie., Change in the Constitution) of Firm
 - i. Where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner(s) on re-constitution of such firm, the Stamp Duty = 3% on the MV (Market Value) of the immovable property remaining with the firm
 - ii. In any other case, Stamp Duty = Rs.1000 (fixed)
- b. Registration Fee = Rs.25 (fixed)
- c. Application Fee = Rs.1 (fixed)
- d. Scanning Fee = Rs.35 (per page of scanning)
(Note: Total number of pages to be scanned = X+1 (Acknowledgement))
- e. Total Payable Amount (in Rs.) = a(i) or a(ii) + b + c + d

For DISSOLUTION OF FIRM

a. Stamp Duty on Deed of Dissolution of Firm

- i. Where immovable property contributed as share by a partner or partners remains with the firm at the time of outgoing in whatever manner by such partner(s) on re-constitution of such firm, the Stamp Duty = 3% on the MV (Market Value) of the immovable property remaining with the firm
- ii. In any other case, Stamp Duty = Rs.1000 (fixed)

b. Registration Fee = Rs.25 (fixed)

c. Application Fee = Rs.1 (fixed)

d. Scanning Fee = Rs.35 (per page of scanning)

(Note: Total number of pages to be scanned = X+1 (Acknowledgement))

e. Total Payable Amount (in Rs.) = a(i) or a(ii) + b + c + d

(Note: During the verification process, the FDA/SDA/DR would have verified the data (say, number of pages entered by the applicant to be scanned); if any changes are needed, then necessary changes would be suggested/made by FDA/SDA/DR and the applicant must have incorporated the same)

63. The applicant shall receive an **Acknowledgement** from the K2 for making the online payment. The applicant can choose '**Print Challan**', '**Return to Application**' or '**Book Appointment**'.

(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login) on Kaveri2.0)

Scheduling an Appointment (by the Applicant) with DR

64. Once payment is being made, the applicant shall Schedule an Appointment (date & time) with the DR by clicking on '**Schedule Appointment**' button

65. The applicant shall select the **Date and Time**

66. Once the schedule is booked, then a dialogue box/ flash message should appear stating 'Your appointment for 15th November, 2021 is successfully scheduled. Please reach the office 15 minutes early for a smooth registration experience'

67. The screen displays the applicant's date, time and venue; and two buttons:

- e. Cancel Appointment and
- f. Re-schedule Appointment

(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login) accordingly on Kaveri2.0)

Firm Registration at DRO on the Day of Appointment

On the day of appointment, the **Applicant** or **Presenter/Agent** will appear before the DR and shall present the physical copy of the documents (Filled & Signed Application Form (New Firm/ Amendment/ Re-constitution or Dissolution), Certified Original copy of the Partnership deed, a specimen of the Affidavit that is certifying the details that are mentioned in the partnership deed, Proof of Authorisation for the Agent (GPA/Letter of Authority/Vakalat/etc.) and other Supporting Documents & Enclosures)

Allocation & Approval by DR for Registration

68. The DR shall login to the Kaveri 2.0 system
69. From the menu on his dashboard, the DR shall click on '**Firm Application**'
70. The DR shall click on '**Firm Appointment**' button
71. All the firm appointments irrespective of their type of services requested for the day are listed in a table
72. The DR can take the following actions:
 - e. **Allocate** – the DR can allocate the firm appointments to FDA/SDA/Self by clicking on '**Allocate**' button so that they can verify, capture/edit the required details and generate the necessary forms/documents needed for registration
(Note: 1. The dropdown which fetches all the FDA/SDAs in the office who are present on that particular day; 2. In case there are many FDAs/SDAs, then DR has the option allocate to a particular FDA/SDA of his choice from the dropdown list)
 - f. **Approve** – after the FDA/SDA has generated the required forms, they are sent to the DR for approval; The DR shall approve by clicking on the '**Approve**' button and only after his/her approval, the firm registration number shall be generated by the system and shall be sent back to the FDA/SDA for further processing

Steps taken by the FDA/SDA to Process the Firm Registration Certificate

73. The firm appointments allocated to the FDA/SDA by the DR have to be displayed on the FDA/SDA dashboard. The table shall be in FIFO
74. The FDA/SDA shall **Review the Physical Documents, Application Summary** and if everything is in order ie., the FDA/SDA shall crosscheck the application(s) and the enclosures thoroughly – application form(s), partnership deed copy (with proper stamp duty), affidavit, proof of authorisation for the agent and other enclosures (ie., firm details, presenter details, partner details, witness details, deed copy details, uploaded documents)
75. The FDA/SDA shall click on the '**Start Registration**' button

(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also status gets updated in the applicant login (and department login) on Kaveri2.0)

76. The FDA/SDA shall first **Verify the Authenticity** of the **Presenter/Agent** either by generating an OTP (to the presenter's (partner/agent) mobile number as entered in the filled application form) and entering it in the system or by physically verifying the Letter of Proof of Authorisation for the Agent (GPA/Letter of Authority/Vakalat/ etc.)

(Note: The system should allow the FDA/SDA to proceed further ONLY after confirmation of the Authenticity of the Presenter (Partner/Agent))

77. The FDA/SDA Screen displays the following:

- i. **Application Details** – Application Number, Date of Submission, Application Type (whichever is applicable)
- j. **Firm Details** – Firm Details, Branch Details
- k. **Applicant Details** – Presenter Details, Partner Details, Witness Details
- l. A '**Generate Certificate and Forms**' button to generate the required forms – the details of the applicants have to be auto-fetched in the set format to generate the required forms

(Note: Firm registration number isn't generated yet)

(Note: Required Forms – Firm Registration Certificate (without Registration Number, Fee Payment Receipt)

78. The FDA/SDA shall **Generate the Summary Report** by clicking the '**Generate Certificate and Forms**' button

79. The FDA/SDA shall send it (above mentioned certificate and forms) to the DR for Approval (Check & Register) by clicking on '**Send back to DR**' button

80. The DR shall view the certificate and forms generated by the FDA/SDA, and shall approve the application in the system by clicking on the '**Check & Register**' button

81. The system generates Firm Registration Certificate with Registration Number

(Note: pop up message should appear once he clicks on 'Check and Register' saying that 'Are you sure to Register? You cannot change later' for which the DR has to confirm)

(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant (and department) login)

Accounting:

82. The system then updates the Index to the Register of Firms and A-Register

83. Details logged in the **Index to the Register** of Firms are as follows:

- a. Firm Name
- b. Name of the Partners
- c. Place of Business
- d. Volume No. (now, it is stored directly in data base/center)
- e. 1st Page Entry
- f. Number Bourne on the Register

84. Details logged in the **A-Register** are as follows:

- a. Firm Registration Number / Serial Number
- b. Name of the Firm
- c. Date of Registration
- d. Duration of Firm
- e. Address of the Firm
- f. Date of change, Remarks, Name of the Partners, Date of Joining & Ceasing, Remarks
- g. Principal Place of Business and changes therein – Particulars regarding the place, Date of change, Remarks
- h. Other places of business – Name of the place, Date of Opening & Ceasing
- i. Name of the Firm – Serial No. of the document, Description of the document, Date of Filing, Signature of the Registrar
- j. Name of the Firm – Serial No. of the document, Description of the document, Date of Filing, Signature of the Registrar
- k. Fee Collected
- l. Fee Receipt Number
- m. Stamp duty paid on the deed document
- n. Date of Stamping

Issue of Certificate of Registration:

85. After **Approval by DR**, the firm registration certificate is pushed back to the FDA/SDA dashboard
86. The FDA/SDA shall click on the '**Print Certificate and Forms**' button to **Print** the Firm Certificate (with Registration Number) (and other forms wherever required)
87. The FDA/SDA shall get **Seal and Signature** affixed by the DR on the Firm Certificate (with Registration Number) (and other forms wherever required)
88. The FDA/SDA shall click on the '**Upload**' button
89. The FDA/SDA upload screen shall display the following:
 - d. **Firm Registration Details:** Application Number, Application Type, Date of Registration
 - e. **Scan and Preview buttons:** to scan and preview Certificate & Forms, Annexures/Enclosures
 - f. '**Save and Send back to DR**' button
90. The FDA/SDA shall **Scan and Preview** (by clicking the '**Scan**' and '**Preview**' buttons respectively) the following documents:

Duly Filled Application Form and Enclosures/Annexures (Firm related documents, Presenter related documents, Partner related documents, Witness related documents)

(Note: Scan ONLY the Required Documents as Demanded by the Service/Amendment Request)
91. The FDA/SDA shall click on the '**Save and Send back to DR**' button and shall forward it to the DR
92. The DR shall view the documents uploaded by FDA/SDA, then shall click on '**Digital Sign & Complete**' button to put his digital signature, encrypt and to upload all the saved documents

(Note: A pop up message should appear once he clicks on '**Digital Sign & Complete**' button saying that 'Are you sure to digitally sign and upload? Once uploaded, the details cannot be changed' for which the DR has to confirm)

(Note: An option may be provided for the DR if re-scan is required; on clicking on the '**Send for Re-scan**' button by DR, it would request the SDA/FDA to re-scan and send it back to DR; and then DR shall view the scanned documents and shall proceed further by clicking on the '**Digital Sign & Complete**' button)

(Note: The applicant (and/or presenter/agent and all the partners) receives an email/sms; the applicant receives a notification on Kaveri2.0; also the status gets updated in the applicant login (and department login))
93. Any **Additional Payment** by the applicant or the presenter/agent is made through Cash; the applicant(s) receives an Acknowledgement (a copy of Fee Receipt has to be generated by the FDA/SDA on receipt of cash)

94. The **Firm Registration Certificate** is handed over physically to the applicant or the presenter/agent after acknowledgement and the applicant or the presenter/agent collects the Firm Registration Certificate
95. The **Sakala** is updated

(**Note:** 1. If applied for **CC (Certified Copy)** for Firm Registration Certificate, then **Digitally Signed/ Physically Signed Copy** from DR may be issued by filling appropriate form by paying corresponding fee ie., **Copies from the register of firms = Rs.10 (for each 100 words or part thereof)**; 2. In case any changes to be done to the Register of Firms due to erroneous data entry, the same shall be done in the system with approval from DR)

(Note: As per section 10-A of Karnataka Stamp Act, 1957, the stamp duty has to be paid **within 2 months** from the date of execution of the deed document. If it exceeds 2 months, then the document can be Impounded under section 33 of Karnataka Stamp Act, 1957. As per section 39 of Karnataka Stamp Act, 1957, the payment of the proper duty or the amount required to make up the same, together with a penalty of five rupees; or if he thinks fit; an amount not exceeding ten times the amount of the proper duty or of the deficient portion thereof, whether such amount exceeds or falls short of five rupees has to be made)

FORM A

[See Rule 5]

REGISTER OF FIRMS

(Maintained under Section 59 of the Indian partnership Act , 1932)

1. Serial number of firm.....
2. Name of the firm
3. Date of registration
4. Duration of the firm
5. Address.....

Date of change	Remarks	Name of the Partners	Partners' Address	Date of		Remarks
				Joining	Ceasing	
(6)						

Principal Place of business and changes therein			Others places of business		
Particular Regarding the place	Date of change	Remarks	Name of place	Date of	
				Opening	Ceasing
(7)			(8)		

Name of firm				Name of firm			
Serial No. of the document	Description of the document	Date of filling	Signature of Registrar	Serial No. of the document	Description of the Document	Date of filling	Signature of the Registrar

FORM B
[See Rule 9(a)]
INDEX TO THE REGISTER OF FIRMS

2022-2023

File name	Names of partners	Principal place of business	Volume No.	1 st page entry	Number borne on the register
(1)	(2)	(3)	(4)	(5)	(6)

FORM C

[See Rule 10(a)]

ACKNOWLEDGMENT OF REGISTRATION OF FIRM

The Registrar of Firms, Karnataka hereby acknowledges the receipt of the statement prescribed by Section 58(1) of the Indian Partnership Act, 1932. The statement has been filed and the name of the firm* has been entered in the Register of Firms as No.of 19.....

Bangalore City

Dated theday of20....

Registrar of Firms

*Here enter the name of firm.

FORM D

[See Rule 10(a)]

MEMORANDUM ACKNOWLEDGING RECEIPTS OF DOCUMENTS

The Registrar of Firms, Karnataka hereby acknowledges the receipt of the undermentioned document / documents and intimates that / it has they have been filed in pursuant to the Indian Partnership Act, 1932.

(Here enter description of / document/ documents)

Bangalore

Dated20....

REGISTRAR OF FIRMS

To

Mr. /Messers.....

FORM E

[See Rule12]

RECEIPT FOR FEES

Received the sum of Rupees (in words) Being
the fees for

Rs.a.p.

Filing Statement

Filing notice

Inspection of

Copy of

(Number of words)

Total

Station.....

Registrar of Firms

Dated20.....

32.4 Validations and Controls

1. The system should record application details
2. The system should search firm's name and address in its database and give alert if firm with same name as applied for exists or is objectionable. It should not allow registration with existing name and address or if objectionable. The application form will have the mechanism for the applicant to check for firms' names that are not feasible
3. The system should calculate firm registration fee on basis of department's business rules
4. The system should verify the authenticity of the presenter (partner/agent) before starting the firm registration process at DR office
5. The system should print acknowledgement and fee receipt on updating of payment details in the system
6. The system should generate unique firm registration number once the registration process is completed
7. The system should enable updating in register of firms and it's Index in case of request for amendment/re-constitution/dissolution
8. The system should enable printing of respective endorsements and certificate based on application type whether registration, amendment, re-constitution or dissolution of firm
9. The system should enable scan and upload of the documents attached with the application
10. The system should make automatic accounting entry for each transaction in A-Register
11. The system should generate CVC reports based on data captured in the system. There should be authorization mechanism for role-based access to reports for generation and view
12. The system should generate summary report for verification of data entered and make provision for correction if any changes found before registration

33 ADDITIONS to the FRS – UPDATION REQUIRED

1. Discussion with Saurabh Sir, Bhoja Naik Sir and Prashanth

- If restriction is Y and restrictiontype is NOT 'pyki' then no transaction should be allowed, and a message should be shown with restriction description and type a popup
- If restriction is Y and restrictiontype is 'pyki' then 11ESketch should be asked
- If availableextent is zero, then the transaction should not be allowed
- If availableextent is less than totalextent, then the sale is part, and 11E sketch should be asked
- If Category is 'PRV' then sale and all other transactions should be allowed; for others no Sale should be allowed
- If a property is multi-owner, then insist on 11ESketch number.

2. Discussion with Saurabh Sir, Bhoja Naik Sir and Prashanth

Please see the process -

1. Document is sent to SRO with summary sheet having only one party details (photo and fingerprint)
2. SRO keeps it on hold (CD119)
3. The application is now in Minute Book list also and in DEO login for generate endorsement.
4. The endorsement to have the 1st section (10A Certificate), the 2nd section with the parties present photo and biometric.
5. After that when other parties appear then the SRO releases it by going to minute book report and sends it for DEO to take the remaining picture and biometric.
6. The DEO takes remaining photo and biometric, sends the updated summary sheet back to SRO again
7. This time the SRO approves it and sends back for final Generation of Endorsement
8. Now endorsement is generated with 2nd section having remaining party photo and biometric and the 3rd section (60A Certificate). At this stage the final registration number is generated.

Dear All,

We had a discussion to review the e-Aasthi and e-Swathu integrations and following are the conclusions -

E-Aasthi Property -

- <responsecode> is to be looked into before allowing transactions. It has to be zero '0' for transaction to proceed or else the contents in the <exceptionmessage> has to be shown.
- There are 4 types of <propertycategory> -> Site, Building, Apartment or any other such as multi-ownership, **masters for which will be provided by NIC.**
- In case of Building as Property Category -> <floordetails> tag is to be used and all <floorarea> tag within <floor> tags are to be added to get the built-up area. <sitearea> tag to be used for getting the underlying area size.

- In case of Apartment/multi-ownership -> <apartmentdetails> tag has to be used and the <superbuiltuparea> value has to be used for identifying the area.
- In case of Site as Property Category -> <sitearea> tag to be used for getting the land size.
- The <propertyclassification> tag will contain two options - Adhikrita (for A-Khatha) and Anadhikrita (for B-Khatha) in Kannada. Only Adhikrita to be allowed for transaction. The **exact Kannada words for performing the match will be shared by NIC.**

E-Swathu Property –

- <responsecode> is to be looked into before allowing transactions. It has to be zero '0' for transaction to proceed or else the contents in the <exceptionmessage> has to be shown.
- <propertytype> tag will have the following values -> 1. Site, Building, Apartment/ Row/Villa and Building with multiple owners. **The masters for the same shall be provided by NIC.**
- <propertycategory> tag contains the following values -> residential, commercial, industrial, KIADB, etc. **The masters for the same shall be provided by NIC.**
- <propertyclassification> tag contains the following values -> Gramthana, Layout, Industrial Purpose, etc. **The masters for the same shall be provided by NIC.**
- Property Form depends upon classification.
- The following are the type of JSLIP files that have to be sent for different types of deed documents -
 - Type A - Ownership Change will take place such as Gift Deed, Sale Deed, etc.
 - Type B - Mortgage/Release Case there would be mortgage and release ID. Only liability changes. Bank Auction deed, Mortgage with possession and without possession, etc.
 - Type C - Partition Deed Case, with cash transaction - Ownership Change
 - without cash transaction - With new property getting created
 - Type D - Rectification Deed, Correction Deed, etc. against previous deed transaction
 - Type Z - Cancellation Deed, Settlement Deeds, existing deeds to be captured

Regards,

Saurabh Bhattacharya,
Addl. Executive Director,
Centre for Smart Governance,
Bengaluru
Mobile: +91 99010 66089
Alt. Email: addl.edcsg@karnataka.gov.in
<https://csg.karnataka.gov.in>

Existing SD:

Stamp (Govt) Duty - (variable)
Exemption Duty on SD - (variable)
Govt Duty after Exemption - (variable)
Cess - (variable)
Surcharge - (variable)
Duplicate SD – Rs.500 (fixed)

Denotation of SD - (variable)

Things to be ADDED to SD:

Deficit SD - (variable)
Affidavit SD – Rs.20 (fixed)
Preemption SD – Rs.100 (fixed)
Certified Copy SD – Rs.10 (per copy) (variable)

Existing RF:

Registration Fee (RF) - (variable)
Duplicate RF – Rs.200 (fixed)

Things to be ADDED to RF:

Exemption (Concession) Duty on RF - (variable)
RF after Exemption - (variable)
RF after Set Off – (variable between Rs.100 and Rs.500)
RF u/s 30 (in DR Office) – Rs.2000 (fixed)
Consenting Fee – Rs.100 (fixed)
Map Filing Fee – Rs.100 (fixed)
Memo Fee – – Rs.100 (fixed)
Private Attendance Fee – Rs.1000 (fixed)
Delay Condonation Fee – Rs.200 (fixed)
Delay Condonation Fine – (variable)
Holiday RF – Rs.2000 (fixed)
Authentication or Attestation POA Fee – Rs.100 (fixed)

Others:

Mutation Fee – Rs.45 (fixed)
Service Charge (Scanning Fee) - Rs.35 per page

Things to be ADDED to Others:

Appeal Fee – Rs.1000 (fixed)
Document Withdrawal Fee – Rs.200 (fixed)
Will Deposit Fee – Rs.1000 (fixed)
Filing of Translation Fee – Rs.50 (fixed)
Safe Custody Fee– Rs.10 per 15 days (Maximum of Rs.100)
Protest Application Fee – Rs.200 (fixed)

MOJINI Concept - 11E Sketch, Parties (Transferer (Co-Transferers) & Transferee (Co-Transferees)), Schedules, Schedule to Party Mapping, Calculation of SD & RF based on No. of Schedules

I. Conditions In case of agriculture land where 11E Sketches are required:

1. Party to Party

- a. if Full Extent of land is Transacted, then NO 11E Sketch is required
- b. if Part Extent of land is Transacted, then 11E Sketch is required and the available extent should be less than total extent
- c. If available extent is zero, then Registration should not happen

2. In case of Partition/Settlement/Gift/Release

- a. Single property divided into several schedules (share) - single 11E Sketch is enough which contains single transferer and multiple transferees (ie., co-transferees)
- b. Single transferer and Single transferee,
 - i. For Full Extent - then 11E Sketch isn't required
 - ii. For Part Extent - then 11E Sketch is required

II. Parties

1. Transferer (and Co-transferers) - are Executants
2. Transferee (and Co-transferees) - are Claimants

(Note: 1. There shall be one Transferer and remaining are Co-transferers

2. There shall be one Transferee and remaining are Co-transferees)

III. Schedule to Party Mapping

This arises in case of **Partition, Settlement, Gift, Release and Exchange**

1. In case of single doner, single property (single schedule) and single donee, then there will be single SD and single RF
2. In case of single doner, single property (single schedule) and multiple donees, then there will be single SD and single RF
3. In case of multiple doners, single property (single schedule) and single donee, then there will be single SD and single RF
4. In case of multiple doners and single property (divided into multiple schedule) for multiple donees, then SD and RF will be on the number of schedules
5. In case of multiple doners, multiple properties (divided into multiple schedule) and single donee, then there will be multiple SD and multiple RF based on the number of schedules
6. In case of multiple doners, multiple properties (divided into multiple schedule) and multiple donees, then there will be multiple SD and multiple RF based on the number of schedules

III. Fields to Capture/Record for Part Property

1. Transferer (and Co-transferers) - Name, Gender, Address, ID Type, ID No., Mobile No., Name of Relative, Relationship, Ownercategory (PRV)
2. Transferee (and Co-transferees) - usual process as in Kaveri 2.0
3. Schedule - Acre, Gunta and f-gunta (ie., Ext_acre, Ext_gunta, Ext_fgunta)
4. Party to Schedule Mapping
5. Calculation of SD and RF based on the No. of Schedules

Sir, I don't have the XML file which you were sharing. I forgot to download it from the chat on Teams Meeting. I will make additions to the same once I get the XML File for various types of transactions.

Sir, do let me know if the above looks good and if any correction is required.

Dear Sir

As requested, an Excel file is enclosed containing the master details of e-Swathu Property type, Property Category, Property Classification and SRO Mutation based on Article number and XML type.

with regards

K. Satish Shankar
TD, NIC

Dear Sir

As discussed in e-Swathu Property over VC on following RESPONSECODE point:

- <responsecode> is to be looked into before allowing transactions. It has to be zero '0' for transaction to proceed or else the contents in the <exceptionmessage> has to be shown.

You have to make little modification that

We are sending the "response code " values 0 to 10".

You should not process / proceed when the "response code " is 0 or 8. Other than 0 & 8 you have to proceed / process at SRO.

(Contacted Mr. Prashanth, CDAC, confirmed the same).

When the "response code " is 8, response message is as below

"This property is undergoing mutation and cannot be transacted Except for DTD/ Mortgage without possession / Cancellation Deed, Correction Deed, Modification Deed, Rectification Deed, Supplemental Deed, Surrender of Lease / ಈ ಸ್ವತ್ತಿನ ಮೇಲೆ ಹಕ್ಕು ಬದಲಾವಣೆ ಜಾರಿಯಲ್ಲಿದೆ, ಈ ಪ್ರಕ್ರಿಯೆ ರದ್ದತಿ ಪತ್ರ, ತಿದ್ದುಪಡಿ ಪತ್ರ, ತಿದ್ದುಪಡಿ ಡೀಡ್, ಸರಿಪಡಿಸುವ ಪತ್ರ, ಪೂರಕ ಪತ್ರ, ಲೀಸ್ ಶರಣಾಗತಿ ಇದ್ದರೆ ಮಾತ್ರ ನೋಂದಾಯಿಸಬಹುದು"

Here you have to check Article code for mentioned deed like DTD / cancellation deed etc., in message to be allowed for proceed / process at SRO.
otherwise don't allow to proceed / process at SRO.

This is for your information .

with regards
K. Satish Shankar
TD, NIC

Dear Sir

As requested the list of Master of ArticalCode mapped with xml type is as below

xmltype	articalcode	MutationDescription_En
A	28	Award
A	39	Certification of Sale
A	42	Certified copy of the decree or order of court
A	66	Exchange of Property
A	69	Gift Deed
A	100	Relinquishment Deed
A	104	Revocation of Settlement
A	106	Sale Deed
A	107	Conveyance of decree or final order of any civil court
A	116	Settlement
A	121	Transfer
B	3	Reconveyance
B	4	Release of Mortgage Right
B	17	Agreement of Sale of Immovable Property (Possession given / agree to be given)
B	45	Mortgage Deed (Article 34(C))
B	56	DTD

B	58	Joint Development Agreement
B	59	Discharge Deed
B	68	Further charge
B	71	Indemnity Bond
B	72	Instrument of Assignment
B	77	Lease Of immovable property
B	85	Mortgage with Possession
B	86	Mortgage without Possession
B	97	Reconveyance of mortgaged property
B	114	Security Bond
B	122	Transfer of Lease
C	91	Partition Deed
D	48	Correction Deed
D	83	Modification Deed
D	98	Rectification Deed
D	119	Supplemental Deed
Z	32	Cancellation Deed
Z	120	Surrender of Lease

with regards
K. Satish Shankar

Dear Sir

As discussed in e-Swathu Property over VC on following RESPONSECODE point:

- <responsecode> is to be looked into before allowing transactions. It has to be zero '0' for transaction to proceed or else the contents in the <exceptionmessage> has to be shown.

You have to make little modification that

We are sending the "response code " values 0 to 10".

You should not process / proceed when the "response code " is 0 or 8. Other than 0 & 8 you have to proceed / process at SRO.

(Contacted Mr. Prashanth, CDAC, confirmed the same).

When the "response code " is 8, response message is as below

"This property is undergoing mutation and cannot be transacted Except for DTD/ Mortgage without possession / Cancellation Deed, Correction Deed, Modification Deed, Rectification Deed, Supplemental Deed, Surrender of Lease / ಈ ಸ್ವತ್ತಿನ ಮೇಲೆ ಹಕ್ಕು ಬದಲಾವಣೆ ಜಾರಿಯಲ್ಲಿದೆ, ಈ ಪ್ರಕ್ರಿಯೆ ರದ್ದತಿ ಪತ್ರ, ತಿದ್ದುಪಡಿ ಪತ್ರ, ತಿದ್ದುಪಡಿ ಡೀಡ್, ಸರಿಪಡಿಸುವ ಪತ್ರ, ಪೂರಕ ಪತ್ರ, ಲೀಸ್ ಶರಣಾಗತಿ ಇದ್ದರೆ ಮಾತ್ರ ನೋಂದಾಯಿಸಬಹುದು"

Here you have to check Article code for mentioned deed like DTD / cancellation deed etc., in message to be allowed for proceed / process at SRO.
otherwise don't allow to proceed / process at SRO.

This is for your information .

with regards
K. Satish Shankar
TD, NIC

**Boundary Change – upto 3 changes (name/schedule/etc) – No Problem – For
Modification/Rectication/Correction/Revocation Deed**

**For more than 3 changes for property schedule – the property only changes – then have to change
the MV**

ARTICLE-SPECIFIC LOGIC (CUSTOMIZATION)

1. Rectification/ Cancellation/ Modification/ Revocation Deed
2. Partition/ Settlement/ JDA/ Gift/ Exchange
3. Will/ Will including Cancellation
4. Miscellaneous
5. e-Asthi, e-Swathu, BDA, BBMP, UROP, Others
6. Special Articles – by me and meghana
7. Exceptional Cases

Cancellation DEED – (Cancellation, Rectification, Modification, Revocation)

[17:10] Naveen Gowda - PM10

[5:09 PM] Naveen Gowda - PM10

1. 3 Inputs will be provided -
 1. Old Final Registration Number
 2. New Application Number
 3. Mutation Flag
 4. Add Regarticlecode, Stamparticlecode, Stampruleid
2. Search the Document Master for Old Final Registration Number and Fetch the Old Application Number
3. Use the Old Application Number to fetch data from the following tables -
 1. Property Master
 2. Property Schedule
 3. Property Number Details
 4. Party Info
4. Re-insert the same data into their respective tables, property-wise, but with the following changes -
 1. In Property Master generate new Property IDs, and then insert the old data along with new application number, new property ids and new Timestamp
 2. In property Schedule as well as in property number details, insert the old rows with new application number and property ids generated previously
 3. In party info table first swap the roles by changing executant of old application to claimant in the new application and claimant in the old application into executant in the new application. Also, if mutation flag is set to true then while inserting data, update the executant with the new property ids and in case the flag is set to false then update the new claimants with the new property ids. Finally, insert the data with new application number.

MEMO CONCEPT

In case of change of Jurisdiction during Registration of Document, then the Origination SR (ie., Registration SR ie., R-SR) sends a MEMO to the Jurisdictional SR (J-SR)

Registration SR (R-SR) Login

1. 2 Buttons shall be present in the Registration SR (R-SR) Login - 'Print' & 'Send' buttons

2. Here, Print button for printing the Form 25

and Send button for marked as sent by R-SR to Jurisdictional SR (J-SR)

Jurisdictional SR (J-SR) Login

1. 3 Buttons shall be present in the Jurisdictional SR (J-SR) Login - 'View', 'Accept' and 'Print' buttons

2. Here, 'View' button for viewing the Form 25

'Accept' button for accepting the Form 25 and sending back Form 26 to the R-SR

'Print' button for printing the Forms 25 and 26

On clicking on 'Accept' button, the following things must happen:

1. Creation/Generation of New Document ID

2. Execution Date - will be the Same

3. Presentation Date - will change

4. Stamp 1 to Stamp 5 Date & Time - as Current Dates only

5. CD No. ()

6. R-SRO will be changed to J-SRO

7. Document No. & Final Registration No. Generated

8. All the Transaction Tables must be Updated Simultaneously - Document Master, Party Master, Property Master, Property Schedule Master, Property No. Details (Tables)

9. Update Document Master with Final Registration No., Book Type and Part Details

10. Generate Form 26 and send the same to R-SR

Registration SR (R-SR) Login

1. Generate and Print Endorsement at R-SR - must Print Only 60 Certificate
2. Replace OLD Registration No. with NEW Registration No

The inclusive massive order and NMG -01- 007865-2025-26. THERE ARE LOT OF the existing software development and never and ever yet ti be saved and yet to be finalized and this case must be

Location – Local ho0st

Date – 2036- 02-06- 13.20

Reason – Diocument registration

Digitally signed by local host

Bamgalore urban and Kumari Priya N

Maruthinagar, Bagalokot

Claimant

Karnataka 607895